

**AGRICULTURAL RESOURCES SURVEY  
PHASE II  
HARRISON COUNTY, WEST VIRGINIA  
2003/2004**



**REPORT**

The activity that is the subject of this report has been financed in part with Federal funds from the National Park Service, U.S. Department of the Interior and administered by the West Virginia Division of Culture & History.

This program received Federal funds from the National Park Service, U.S. Department of the Interior. Regulations of the U.S. Department of the Interior strictly prohibit unlawful discrimination in departmental Federally Assisted programs on the basis of race, color, national origin, age or handicap. Any person who believes he or she has been discriminated against in any program, activity or facility operated by a recipient of Federal Assistance should write to: Office of Equal Opportunity, National Park Service, 1849 C Street. NW, Washington, D.C. 20240.

**HARRISON COUNTY AGRICULTURAL  
HISTORIC RESOURCE SURVEY/PHASE II**

**Located in**

**Harrison County, West Virginia**

Conducted in the Spring of 2004

For

The Harrison County Historic Landmarks Commission  
Mr. Thomas C. Green, Vice President

The West Virginia Division of Culture and History  
The Cultural Center of the Capitol Complex  
Charleston, West Virginia  
Mr. Troy Body, Acting Commissioner

CONSULTANT  
Michael Gioulis  
Historic Preservation Consultant  
612 Main Street  
Sutton, WV 26601  
(304) 765-5716

## CONTENTS

|                                            |                                   |
|--------------------------------------------|-----------------------------------|
| Preface                                    | Page 1                            |
| Purpose                                    | Page 2                            |
| Methodology                                | Page 3                            |
| Outline History of the Survey Area         | Page 5                            |
| Description of the Survey Area             | Page 8                            |
| List of Sites                              | Page 16                           |
| Photograph Log                             | Page 105                          |
| UTM Reference Log                          | Page 113                          |
| Survey Analysis and Recommendations        | Page 120                          |
| Bibliography                               | Page 127                          |
| Appendix I/USGS Map Details                | Page 129                          |
| Appendix II (NR LISTED "INDIAN CAVE" SITE) | Page 130 -- REDACTED/CONTACT SHPO |
| Inventory Forms                            | Separate Cover                    |
| Map of Survey Areas with Sites Noted       | Separate Cover                    |

## PREFACE

The Agricultural Historic Resource Survey/Phase II of Harrison County, West Virginia is a continuation of the Harrison County Historic Landmarks Commission's (HLC) commitment to identify and document the architectural, agricultural and historical resources located in Harrison County, West Virginia. The Harrison County HLC had contracted with the firm the previous year and Phase I of the Agricultural Historic Resource Survey was completed at that time. This survey represents Phase II of the process and will be akin to a Reconnaissance Survey. This report and survey will be used to guide the HLC on where to concentrate efforts in future work.

A grant from the West Virginia Division of Culture and History, State Historic Preservation Office (SHPO), was awarded in the Spring of 2003 to the Harrison County Historic Landmarks Commission to do an Agricultural Historic Resource Survey/Phase II of Harrison County, West Virginia. The HLC had identified farms in the county through research in the county records and the HLC and the Consultant agreed upon the initial focus of the survey within the county. The area surveyed was to encompass one hundred and twenty (120) resources in addition to any and all outbuildings associated with each primary structure.

The survey area was to include traditional/historic farms in Harrison County as identified by the survey team. The survey area encompasses approximately 66,720 acres; this is approximately one-fourth of the total county area. The area surveyed yielded one hundred and twenty (120) primary resources. This count does not include modern resources. A total of six hundred and ten (610) resources were included within the one hundred and twenty (120) resources recorded. This includes six hundred and nine (609) buildings and one (one) site.

USGS topographic maps and county maps were used for the field work and initial field notes were prepared. It was agreed by all that the focus of the survey would be agricultural properties.

The consultant team would like to acknowledge the willing cooperation he received from the property owners in the survey area, particularly Mr. James McDougal, Ms. Lulu Belle Law McDougal, and Mr. and Mrs. David Allman. Property owners were helpful, friendly and knowledgeable about their homes and the area's history. Ms. Becky Nesbitt and Mr. Jeff Wyne of the Harrison County Historic Landmarks Commission were invaluable in researching, through deeds and courthouse records, current property owners' names and addresses and farm acreage and use. Becky and Jeff also spent a day in the field assisting the survey team with the field work.

## PURPOSE

The purpose of the survey was to investigate the extant historic built environment of agricultural properties of Harrison County, West Virginia and determine the extent of remaining historic resources. These were then to be evaluated based on the National Register Criteria for Evaluation to determine the significance and historical context of each of the resources. From this, decisions as to National Register eligibility could be made. It was expected that due to the closeness of the Clarksburg-Bridgeport area, that some of the resources would have been modified to the point of having lost integrity. Modifications were found in number. It was also expected that many modern resources would be found. This was the case in areas close to towns but not rurally. The majority of the areas surveyed retained their rural landscape. The HLC's goal is to incorporate the protection and interpretation of the historic built environment into its overall plan.

While it was beyond the scope of this particular survey to develop a true picture of farms, particularly traditional or long-term family farms, within Harrison County, due to the number of modern primary resources; one thing can be extrapolated from this survey, the areas surveyed were generally rural and agricultural in nature. Many of the current farms have modern homes and consequently were not identified and recorded in this survey. It may be possible from building permits or other courthouse records to determine this. Many of the resources identified and recorded were traditionally farms but the primary structures are vacant or the land is no longer used for self-sufficient farming. Many of the farms lease their land to family or neighbors for hay production and/or livestock pasture.

The HLC wishes to identify the resources in the area and include them in its and the County's planning procedures. An understanding of the amount, concentration and quality of resources is needed for this purpose. The project was intended to identify and preliminarily quantify agricultural resources in Harrison County, West Virginia and assist in making decisions for future activities, including National Register of Historic Places nominations for individual structures or historic districts. Specific architectural styles, building types and functions were also studied under this survey to allow for a broader understanding of the area's history and development.

## METHODOLOGY

The first step in the process was to gather and review the archival research on the history and development of Harrison County. Ms. Becky Nesbitt and Mr. Jeff Wyne of the Harrison County Historic Landmarks Commission provided the consultant team with property owners' names and addresses and dates of buildings.

The base maps used for the survey were the USGS topographic maps for the specific areas of the county surveyed. These maps and county highway maps were provided by the HLC. This gave the consultant a good snapshot of modern and historic structures. Modern structures were not noted in the survey as the majority of the area is rural. This survey will be a snapshot of agricultural properties within the specific geographic areas noted on the USGS topographic maps.

It was agreed upon by both parties that the consultant team would focus on specific areas of the county and that the focus would be on identifying agricultural properties. It was also agreed that the numbering system would begin with #0151 for the Phase II survey. This numbering continues the same system used for Phase I; the last number used in Phase I was #0150.

The consultant drove to a specific geographic area of the county and began identifying agricultural properties. A field log of all properties identified as or observed to be pre-1955 was compiled. This included a field number for each of these resources and a brief description of the property and any outbuildings. This log served as the basis for the documentation of these sites on West Virginia Historic Property Inventory forms. Also included was an initial determination if the property contained historic or architectural qualities warranting listing on the National Register of Historic Places, either individually or as contributing to a historic district. In all, one hundred and twenty (120) resources were logged in. This includes six hundred and ten (610) resources when primary and secondary resources are counted. One (1) site is included within the six hundred and ten (610). One hundred and twenty (120) individual resources were recorded on West Virginia Historic Property Inventory forms. It should be noted that one site was recorded in this survey that is physically located in Lewis County, #0251. It was recorded as some of the farm may be located in Harrison County and the only access to this resource is via a county road in Harrison County.

The background research material provided by all parties was correlated with the field notes and subsequent on-site follow up to provide an architectural and historic time line of the areas.

Following these phases, with the maps and the field notes, the consultant team drove the survey area. For properties previously identified, or in the opinion of the surveyor, as pre-1955, a photograph was taken, black and white, and information confirmed on the description, architectural style, modifications, etc. for documentation on inventory forms.

Numbers were added to the map, corresponding to the field notes. Properties that had lost integrity through modifications or additions were noted as not eligible but were still documented on the West Virginia Historic Property Inventory form.

For analysis and recommendations purposes, several classifications were used: contributing to an eligible historic district (CHD); individually eligible to the National Register of Historic Places (CE); not eligible due to modifications or deterioration (NE); and already listed on the National Register of Historic Places (NR). These classifications allowed the consultant team to place the resource within an architectural or historical context and for a broader view of the entire survey area.

Additional slides were also taken of the resources in the survey area.

Current owners' information and historical information for the inventory forms was derived from research done by the Harrison County HLC and individual property owners. Any and all pertinent information was also compiled from current property owner interviews during this survey; on-site and via telephone and e-mail.

The field and research information was transferred to the West Virginia Historic Property Inventory forms and they were prepared for final typing. One hundred and twenty (120) West Virginia Historic Property Inventory forms were completed for the Harrison County Agricultural Historic Resource Survey/Phase II.

At this point, the survey team also evaluated the resources to determine the significance of the resources. Evaluation was conducted following the National Register of Historic Places Criteria for Evaluation and the classifications noted earlier were used in the analysis section of this report.

Site numbers were recorded on the survey map and this numbering system is consistent for the report, inventory forms, maps and photographs. The topographic maps used in this survey are under separate cover. Individual UTM references for each site are noted on the inventory form and in the UTM reference log in this report.

The report was then compiled to provide a reference and analysis of the survey activities and to provide direction for future activities by the Harrison County Historic Landmarks Commission.

## **OUTLINE HISTORY OF THE SURVEY AREAS LOCATED IN HARRISON COUNTY, WEST VIRGINIA**

The following is a brief historical synopsis of the areas surveyed within Harrison County, West Virginia. Several in-depth histories of Harrison County and the towns within it have already been written and it is redundant to reiterate these. These histories were utilized in this summary. See the Bibliography.

Harrison County, located in the north central part of West Virginia, was formed in 1784. It was named after Benjamin Harrison, father of William Henry Harrison, ninth U.S. president. One of the first white settlers in Harrison County was a trapper, John Simpson, who arrived in 1764. By 1771 other settlers had arrived. In 1773, David Davisson took claim to 400 acres of land which is now the central business district of Clarksburg, the county seat. Clarksburg was named in honor of George Rogers Clark in 1781. Harrison County was known in the past and continues to be known for its livestock and agricultural industry.

The first area surveyed in this project was the Salem area. Salem is located in the western portion of Harrison County. It includes the small communities of Marshville, Bristol and Jarvisville and the hollows of Marshville Road, Rush Run, Panther Run, Grass Run, Rockcamp Run, Ten Mile Creek Road, Flinderation Fork, Indian Run, Cherry Camp Run, Turkey Run, Halls Run, Raccoon Run, Jarvisville Road, Shaws Run, Wolfpen Run, and Lick Run.

**Salem** was settled by Seventh Day Baptists in 1790. About forty families settled at the headwaters of Tenmile Creek and built a blockhouse near the forks of Patterson and Tenmile Creeks. Samuel Fitz Randolph had purchased the land without ever seeing it from the widow of Joseph Swearingen and urged his congregation of the Shrewsbury, New Jersey, Seventh Day Baptists Church to relocate. The town was first known as New Salem. Early area names include Patterson, Davis, Lippincott, Maxson, Thorp, Clayton, Jackson and Haymond. Many of the family names are still extant in the same areas. The area remained sparsely settled until ca. 1830 when the Northwestern Turnpike was begun and established. New Salem was soon called only Salem by the railroad company who built a road through the middle of town and by most of its citizens by the mid 1850s. In 1885 the post office officially changed the name. By 1885 there were only about 25 homes in town. At this time there was a post office, a grist mill, a planning mill, a hardware store, a blacksmith and assorted "hotels" and stores.

The State Legislature located the Industrial Home for Girls in Salem in 1897. This was a big boost to the local economy especially as other small communities were having such a hard economic period. The homes and streets of Salem were lit by gas from 1896 until 1913. Electricity arrived in 1913 provided by W.F. Meredith and his son, J.W. The period starting about ca. 1900 was Salem's boom time due to the oil and gas industry in the area. This boom effectively doubled Salem's population.

As with many communities, Salem's extant built environment is a product of natural disasters such as flood and fire. In the winter of 1901 a great fire engulfed Salem. It burned the greatest number of buildings in the history of the county. The downtown was rebuilt in "fireproof" brick. Floods were a major problem during the 1930s and 1940s. A major watershed project was implemented with the building of eight dams on Upper Tenmile Creek, farmers planted one-half million seedling trees and creek beds were cleared and widened. The entire project was completed in about a year with the dedication held in September of 1958 on Glenn L. Post's farm.

Salem College was founded in 1888 by the Seventh Day Baptists. Jesse Fitz Randolph was the President of the first Board of Directors. There were eighteen other members on the board, all local businessmen and farmers. The Seventh Day Baptists had founded the college in order to keep their children from leaving home and attending school in New Jersey. Salem College continues to be a major presence in the town to this day.

The small community of **Bristol** is located twelve miles west of Clarksburg and was originally known as Cherry Camp during the Civil War. Cherry Camp Run flows northwest into the town. It was established in about 1866 with lots sold. At that time there was a store run by John and Samuel Good. They progressed with a steam saw and grist mill with milling machinery. The post office was established in 1873. As with Salem, Bristol prospered with the oil boom but it is virtually non-existent now except for in people's memories.

The next area to be surveyed was the West Milford and Good Hope areas. This includes the small communities of Benson, Kincheloe and Tichenal. It also includes the hollows of Buffalo Creek, Isaacs Creek, Two Lick Run, Campbell Run, Two Lick, Stutler Fork, Right Fork, County Route 270, Long Run, Kincheloe Road, Tanner Fork, Vens Run and a few properties along US Route 19.

**West Milford** was founded by Jesse Lowther in 1815. Jesse was the first white child born in this area. Lowther and Samuel Hoff laid out the town and the lots. In 1817 Lowther sold two acres of land to Samuel Clemens and Jacob Romine. Clemens and Romine built a dam across the West Fork River backing up the river for seven miles and they built a grist mill and saw mill. The mill had such power from the great water resource that a town began to grow up around it. The Virginia Assembly established the town of "Millford" on January 15, 1821. The post office was established in 1827 but in 1833 the post office officials let the Lost Creek Post Office serve both communities. In 1843, the citizens of West Milford petitioned the post office to be re-established and it was done so under the new name of West Milford in 1844. In 1852, the West Milford and New Salem Turnpike began a projected thirty-foot highway that would run from the West Road to the Northwestern Turnpike at Wolf Summit. A bridge was not built over the West Fork River for the turnpike until 1875.

West Milford was incorporated in 1885 and consisted of 160 acres. A major flood disabled the town in 1888 and washed the bridge away. At this time the townspeople decided to do away with the city government and let the county be responsible for

infrastructure and other costly maintenance, including a new bridge. The county did build a new bridge a year later but the town remained unincorporated until 1920.

West Milford's population in 1890 was 210; in 1930 it was 349; and by 1970 it was only 353. As can be seen by these figures, West Milford is and remains a small rural village. It is also the oldest town in Harrison County. West Milford is also the home to West Virginia's first woman physician, Dr. Susan Dew Hoff who was born in West Milford November 24, 1842. She practiced medicine in the community for about fifty years.

The **Good Hope** community is located alongside the West Fork River on US Route 19 about ten miles south of Clarksburg. The area was first known as "Washburn Settlement" until a Grange was established in 1875 and it was called Good Hope. It had three houses initially but once the Grange was built a store was opened as well as a blacksmith shop, post office and school. Lloyd Washburn ran the first hotel out of his home and he owned the land the town was situated on. He plotted and sold the land for the town. The New Bethel United Methodist Church has been the focus of the town for many years and remains so.

**Kincheloe** is located along the very south-western border of Harrison County. Lewis County is just to the south of Kincheloe Creek. The community is named for Richard Kincheloe, one of the earliest settlers in the area. It was and is a very rural community and until recently, most of the families supported themselves through beef cattle. At one time the community had two stores, a gas station, three churches, two schools and a post office. Of that list, two churches remain.

The areas surveyed remain chiefly rural and agricultural although, for the most part, no longer self-sufficient. Many changes are occurring and long-standing family farms are the exception rather than the rule. Good quality of life and a beautiful environment remain.

## DESCRIPTION OF THE SURVEY AREA

The areas surveyed within Harrison County are enumerated below. The survey focused on agricultural properties and did not record any resources within a community. The survey area encompasses approximately 66,720 acres; this is approximately one-fourth of the total county area.

Harrison County is located in the north central portion of West Virginia on the Allegheny Plateau and consists of 418 square miles. The county seat is Clarksburg, located in the center of the county. The West Fork River is the largest river in the county.

The first area surveyed in this project was the Salem area. Salem is located in the western portion of Harrison County. It includes the small communities of Marshville, Bristol and Jarvisville and the hollows of Marshville Road, Rush Run, Panther Run, Grass Run, Rockcamp Run, Ten Mile Creek Road, Flinderation Fork, Indian Run, Cherry Camp Run, Turkey Run, Halls Run, Raccoon Run, Jarvisville Road, Shaws Run, Wolfpen Run, and Lick Run.

The next area to be surveyed was the West Milford and Good Hope areas. This includes the small communities of Benson, Kincheloe and Tichenal. It also includes the hollows of Buffalo Creek, Isaacs Creek, Two Lick Run, Campbell Run, Two Lick, Stutler Fork, Right Fork, County Route 270, Long Run, Kincheloe Road, Tanner Fork, Vens Run and a few properties along US Route 19.

It should be noted that site #0251 located on Turkeypen Creek Road in the Kincheloe area is actually located in Lewis County rather than Harrison County. It was included within this survey as some of its farm land may be located in Harrison County. The only access to the resource is via the Harrison County side.

It was expected that the survey area would contain primarily mid to late nineteenth century and early twentieth century farms and residences in a rural setting. This was the case. It was also expected that many of the resources would have been modified to the point of having lost integrity and that modern intrusions would be numerous. Modifications were found in number but in the rural areas modern intrusions were not numerous. While modifications were found many of the homes still retain their basic configuration and many, their character defining elements. Almost all of the primary resources recorded were located in rural settings. The land remains agricultural with large tracts dominating.

One of the major changes for these once self-sufficient farms is the fact that many are no longer farms. Many of the homes are still lived in by the long-time owners but they are unable to be self-sufficient on the farm. They lease out the land for hay production and/or livestock grazing or they farm "on the side" while maintaining a full-time outside job or

are retired. The farming way of life is irrevocably changed. Many of these farms remain as symbols of the family's "home place" and the families struggle to maintain these physical touch stones of their own history.

The majority of the recorded resources fall within the late nineteenth and early twentieth centuries and the buildings are primarily two-story, wood frame houses. There are also many intact secondary farm buildings such as barns, chicken coops, silos, granaries, machine sheds and especially, cellar houses. Several farms retain their original secondary buildings but the primary residence has been torn down and a new house constructed.

Two small rural school houses were also recorded in this survey although both have been converted to residences. They are site #0174 and site #0195. Site #0174 was the Indian Run School House and site #0195 was the Laurel Run School. The Laurel Run School/House retains its original entrance bay.



**Site #0195.  
Laurel Run School**

It was expected that the majority of the resources would have no specific style and have very little ornamentation. While the majority of the resources had no architectural style they had many stylistic details and ornamentation. Most of the resources were also quite large to accommodate large farm families and the workers. Architectural styles include Folk Victorian, Prairie, Classical Revival, Ranch, Queen Anne, Colonial Revival, Four Square, Italianate, Bungalow and Midland Log. As can be seen by the styles represented, these resources illustrate a broad range of time periods from the mid nineteenth century up to the mid twentieth century.


As is true for much of West Virginia, the most represented style in the survey is the Folk Victorian style. This includes: the Glaspell House & Farm, site #0152; the Randolph House, site #0171; the Post House & Farm/New Dale Farm, site #0181; the Cole/Bond House & Farm, site #0182; the Rapking/Post House & Farm, site #0206; the McDonald Farm, site #0217; the Coffindaffer House & Farm, site #0224; the Dawson/Kennedy House & Farm, site #0230; the Ferrell/Gusman House, site #0245; the Coffindaffer House, site #0256; and the Doak House & Farm, site #0261. Examples of the style are shown below.

Site #0171



Site #0261  
Front elevation

Site #0261  
Side elevation



Site #0261  
Side elevation

The Queen Anne style is also represented within the survey area. These include: the Summers/Pinkhan/Williams House & Farm, site #0157; the Seckman House, site #0166; the George House & Farm, site #0168; the Ross/Golden/Johnson House & Farm, site #0188; the Pedrick/Headley House & Farm, site #0189; the Williams House & Farm, site #0193; the Dawson/Bond House & Farm, site #0229; the Sutler/Richards/Sheets House & Farm, site #0238; the Layman/Hughes House & Farm, site #0244; the Baird House, site #0253; the Lough House, site #0257; the Moser/Clemans House & Farm, site #0262; and the Freeman House & Farm, site #0270. All of these have been somewhat modified.



Site #0157

The Italianate style is illustrated also by the following: the Hitt House & Farm, site #0158; the McWilliam/Shaffer/Haymond House & Farm, site #0173; the Myers House, site #0191; and the Riley House & Farm, site #0202.



Site #0202

The Colonial Revival style is shown with the following: the Southern House, site #0192; and the Maxson/Bond House & Farm, site #0237. These houses are more regional

adaptations of the Colonial Revival style and illustrate the style through porch details, materials, etc.

The Four Square style is illustrated with the following: the Peter Ross House & Farm, site #0154; the Butler House & Farm, site #0160; the Dennison House, site #0180; the Trovato House, site #0184; the Tyler/Turner/Sommers House/J&T Produce/Jane Lew Tile & Block Company, site #0243; and the Jenkins House, site #0246.

Site #0160



As is common throughout West Virginia, the Bungalow/Craftsman style is also well represented in the survey area. These include: the Davis/Posey House & Farm, site #0161; the Reaser House, site #0169; the Ross House, site #0187; the Portillo House & Farm, site #0199; the Bowyer House & Farm, site #0211; the Gabriel/McDonald House, site #0219; the Law House & Farm, site #0228; the Bartlett House, site #0241; the Gillespie House & Taxidermy, site #0249; and the Snyder House & Farm, site #0267. Again, many of these have been modified but the most intact example is shown below.



Site #0219

One of the more unusual resources within the survey area is the England/Stonestreet House, site #0190. It is in the Prairie style and is located in a remote section of the county. It is a very large high style house for its location. It was constructed of rock-faced concrete block. It appears that this area had several tile and block plants within the

historic time period. Many of the houses recorded have rock-faced concrete block retrofitted to their foundations, chimneys and facades.



One Ranch style house was included within this survey. It is the Nay House & Farm/Riverbend Dairy Farm, site #0266. This was a case where the original four room, wood frame home place was replaced by a more modern home.

There is one log house recorded in the survey area. This is the Jablon/Lanham House, site #0167. There were several other resources that have log framing but the houses have been very modified and it is no longer apparent that the house is log. The lack of log houses was one major difference in Phase II compared to Phase I where several extant log houses were recorded. The Jablon/Lanham House is in the Midland Log House style. The Midland building tradition evolved in the Mid-Atlantic states as one of three folk building traditions; the other two are the New England and Tidewater South. The Midland tradition was introduced into America by the German immigrants who came from heavily wooded areas of Europe and thus their building materials rely on hewn logs. Log construction was a sharp contrast to the English frame buildings. Later settlers of Scotch-Irish and English extraction adopted and adapted this building tradition as they settled in Appalachia and settlement spread to the west.

As stated previously, the most common house within the survey area has no specific architectural style but the plan configurations include two-story, "L" houses, most commonly with gable roofs but occasionally hip and two-story, hip roof houses with projecting gable bays and "I" and "T" house plan configurations. These types of houses are often known as "Vernacular" and they represent almost 50% of the styles within this survey area. An example of a typical "I" house is shown below.

Site #0156



There were also several Queen Anne Cottage style houses within the survey area. These are simpler plans of the Queen Anne style and include: the Lynch House, site #0159; the McDougal/Law House & Farm, site #0213; and the Richards/Davisson House & Farm, site #0234.

There were several other Revival styles recorded in the survey. The Gothic Revival style is illustrated in site #0251, located in Lewis County on Turkeypen Creek Road. The Laurel Run School house, site #0195 retains its Classical Revival entrance bay and stylistic details but it has been converted to a residence. The Greek Revival style is evident in the Poole House/Maplewood, site #0247, constructed ca. 1840.

There were also several more contemporary houses in the Minimal Traditional style and these include: the Andrews House/Indian Run School House, site #0174; the Post House & Farm, site #0205; and the Rigdon House, site #0235. These houses represent this style primarily through the alterations they have received.

As can be seen by the above many different styles of architecture are represented in the survey area. They range from the mid nineteenth century up to and including the mid twentieth century. As stated previously, the predominant use of the resources is residential, farm houses and their associated outbuildings. The majority of the resources recorded fall into the late nineteenth and early twentieth centuries. A complete list of sites follows.

|                                                                                                                                |
|--------------------------------------------------------------------------------------------------------------------------------|
| <p style="text-align: center;"><b>HARRISON COUNTY AGRICULTURAL<br/>HISTORIC RESOURCE SURVEY/PHASE II<br/>LIST OF SITES</b></p> |
|--------------------------------------------------------------------------------------------------------------------------------|

**0151. MARSHVILLE ROAD/COUNTY ROUTE 5, residential      HS-0580**

**Ritter House & Farm**

date: Ca. 1900

description: Two-story, front facing "L" house. Metal roof. Central, interior, brick chimney. Asphalt shingle siding. Vertical 2/2 windows. One-story, modified hip roof, enclosed, front porch in corner of ell; slightly battered square posts remain from original open porch. One-story, shed roof, enclosed, side entrance. Stone foundation. 3 X 3 bays. Gabled-ell house.

1 not-eligible building (NE)

**151A.**

date: Ca. 1900

description: Two-story, end gable, cellar house. First floor mostly underground. Corrugated metal roof. Board siding on second floor; stone on first floor and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**151B.**

date: Ca. 1900

description: Two-story, gambrel roof barn with flanking, shed roof wings. Corrugated metal roof. Board and batten siding. Pier foundation. 7 X 1 bays.

1 not-eligible building.

**151C.**

date: Ca. 1990

description: One-story, shed roof, machine shed with attached, shed roof wing. Corrugated metal roof. Square posts. Pier foundation. 5 X 1 bays.

1 not-eligible building.

**0152. RUSH RUN, residential      HS-0581      Glaspell House & Farm**

date: Ca. 1900

description: Large, two-story, front facing "L" house. Standing seam metal roof. Partial return cornice. Decorative vergeboard and saw-cut shingles in gable end. Interior, brick chimney. German siding with frieze and corner boards with caps. Modern 1/1 windows with simple hoods. One-story, modified hip roof, non-original, front porch with T-111 siding and French doors. Large, two-story, shed roof addition on the left with particle board and concrete block foundation. Cut stone foundation. 4 X 3 bays. Folk Victorian style.

1 not-eligible building (NE)

**152A.**

date: Ca. 1900

description: One-story, shed roof outbuilding. Metal roof. Board and batten siding. Stone pier and concrete block pier foundation. 3 X 1 bays.

1 not-eligible building (NE)

**152B.**

date: Ca. 1900

description: One-story, shed roof, cellar house. Roof is collapsed. Vertical board siding. Cut stone foundation. 1 X 1 bays.

1 not-eligible building (NE)

**152C.**

date: Ca. 1900

description: One-story, end gable barn. Metal roof. Board and batten siding. Stone pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**152D.**

date: Ca. 1900

description: One-story, shed roof outbuilding. Metal roof. Board and batten siding. Pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**152E.**

date: Ca. 1900

description: Two-story, end gable barn. Metal roof. Board and batten siding. Stone foundation. 1 X 1 bays.

1 not-eligible building (NE)

**152F.**

date: Ca. 1900

description: One-story, end gable barn with shed roof wing on the left. Metal roof. Board and batten siding. Stone pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**152G.**

date: Ca. 1980

description: Trailer. Deteriorated.

1 not-eligible building (NE)

**0153. PANTHER RUN ROAD. Residential      HS-0582**

**Wilcox/Fletcher House & Farm**

date: Ca. 1890

description: Two-story, side gable house with a one-story, gable wing on the rear. One-story, gable addition/garage attached to rear wing and original cellar house. Interior, stone chimney on rear; central, interior, stone chimney on front. "V" seam metal roof. Vinyl siding. Modern 6/6 windows; vertical 2/2 windows. One-story, modified hip roof, three-quarter length, front porch with Doric columns. Open porch on rear gable with square posts. Stone foundation; concrete block foundation on addition. 3 X 5 bays. "I" house.

1 not-eligible building (NE)

**153A.**

date: Ca. 1950

description: One-story, end gable garage. Corrugated metal roof. Corrugated metal siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**153B.**

date: Ca. 1980

description: One-story, side gable garage. Asphalt shingle roof. Concrete block façade. Concrete foundation. 3 X 1 bays.

1 not-eligible building (NE)

**153C.**

date: Ca. 1895

description: Two-story, end gable barn with flanking, shed roof wings; both enclosed. Standing seam metal roof. Log façade; wings have vertical board and board and batten siding. Pier foundation. 3 X 1 bays.

1 not-eligible building (NE)

**0154. MARSHVILLE ROAD/COUNTY ROUTE 5      Peter Ross Farm      HS-0583**

date: Ca. 1920

description: Two-story, hip roof house. Asphalt shingle roof. Central, corbelled brick chimney. Paired, scrolled corner brackets. Clapboard, German, asbestos shingle and vinyl siding. Modern 1/1 and 6/6 windows. One-story, hip roof, three-quarter length, enclosed, front porch. Side gable wing on the right with an open porch on the rear with concrete block foundation. One-story, shed roof, back porch with slightly battered posts on a wood deck. Stone foundation. 5 X 2 bays. Four Square style. Modified.

1 not-eligible building (NE)

**154A.**

date: Ca. 1915

description: Two-story, end gable, cellar house. Asphalt shingle roof. Clapboard siding. Vertical 2/2 windows. One-story, hip roof, enclosed, entrance bay on the front with concrete block foundation. Cut stone façade and foundation on first floor. 3 X 2 bays.

1 not-eligible building (NE)

**154B.**

date: Ca. 1915

description: One-story, shed roof outbuilding. Metal roof. Vertical board siding. Stone pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**154C.**

date: Ca. 1980

description: One-story, shed roof, machine shed. Metal roof. Metal siding. Open front. 5 X 1 bays.

1 not-eligible building (NE)

**154D.**

date: Ca. 1990

description: One-story, end gable, two bay garage. Metal roof. Plywood siding. Concrete block foundation. 2 X 1 bays.

1 not-eligible building (NE)

**154E.**

date: Ca. 1950

description: Large, three-story, gambrel roof barn. Metal roof. Clapboard siding on upper stories; concrete block first floor and foundation. Metal, vertical 3/3 windows. 1 X 6 bays.

1 not-eligible building (NE)

**154F.**

date: Ca. 1950

description: One-story, end gable, milk house. Metal roof. Concrete block façade and foundation. Metal windows. 1 X 1 bays.

1 not-eligible building (NE)

**154G.**

date: Ca. 1915

description: Two-story, end gable, corn crib. Metal roof. Vertical board siding. Stone pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0155. GRASS RUN ROAD/COUNTY ROUTE 5/6, residential  
Evans/Rogers House & Farm**

HS-0584

date: Ca. 1920

description: Large, two-story, hip roof house with one-story, gable wing on the rear that attaches to a gable, one-story, concrete block wing that attaches to a two-story, cellar house that attaches to another gable wing. Metal roof. Paired, scrolled brackets at the corners of the roof. Vinyl siding. Modern 1/1 windows with decorative hoods and simple surrounds. Two, entrance doors on the front with same hoods and surrounds and undivided transoms. Two-story, front porch with square columns and slatted balustrades. Stone foundation. 4 X 5 bays. "I" house. Modified.

1 not-eligible building (NE)

**155A.**

date: Ca. 1930

description: One-story, end gable barn. Metal roof. Vertical board siding. Stone pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**155B.**

date: Ca. 1930

description: Two-story, end gable barn with rear, hip roof wing. Metal roof. Vertical board siding. Pier foundation. 1 X 2 bays.

1 not-eligible building (NE)

**0156. GRASS RUN ROAD/COUNTY ROUTE 5/6, residential**

HS-0585

**Fahey/Carter House & Farm**

date: Ca. 1889

description: Two-story, side gable house with one-story, gable wing on the rear. Two, interior, corbelled brick chimneys; interior, brick chimney on the rear. "V" seam metal roof. Decorative shingles in the gable ends. Scrolled brackets at the corners of the roof. Clapboard siding with frieze and corner boards with caps. Modern 1/1 and vertical 3/1 windows. Small, one-story, shed roof wing on the left. Rear wing has an open, shed roof porch with modern square posts on enclosed, brick balustrade. Front porch has been removed. Stone and concrete foundation. 4 X 4 bays. "I" house.

1 not-eligible building (NE)

**156A.**

date: Ca. 1985

description: One-story, end gable, well house. Roll roofing. T-111 siding. Concrete block foundation. 1 X 1 bays.

1 not-eligible building (NE)

**156B.**

date: Ca. 1985

description: One-story, end gable garage. Metal roof. T-111 siding. Concrete block foundation. 1 X 1 bays.

1 not-eligible building (NE)

**156C.**

date: Ca. 1985

description: One-story, end gable barn/machine shed. Metal roof. Metal siding. Concrete foundation. 1 X 1 bays.

1 not-eligible building (NE)

**156D.**

date: Ca. 1985

description: One-story, side gable, machine shed/hay storage building. Metal roof. Vertical board siding. Pier foundation. 4 X 1 bays.

1 not-eligible building (NE)

**156E.**

date: Ca. 1895

description: Two-story, end gable barn. Corrugated metal roof. Vertical board siding. Stone pier foundation. 3 X 1 bays.

1 not-eligible building (NE)

**156F.**

date: Ca. 1890

description: House converted to hay barn. One and one-half-story, side gable building. Metal roof. Central, interior, stone chimney. Board and batten siding – non-original. Vertical 2/2 windows; most are missing. Front porch has been removed. Stone pier foundation. 3 X 1 bays. Rear wall has been removed.

1 not-eligible building (NE)

**156G.**

date: Ca. 1985

description: One and one-half-story, end gable barn. Metal roof. Wood siding. Concrete foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0157. GRASS RUN ROAD/COUNTY ROUTE 5/6, residential  
Summers/Pinkham/Williams House & Farm**

HS-0586

date: Ca. 1910

description: Two-story, hip gable roof house with two-story, shed roof wing on the rear and two-story, gable bays. Interior, brick chimney. Asphalt shingle roof. Decorative shingles and circular louver in gable ends. Aluminum siding. Modern 1/1 windows with shutters. One-story, modified hip roof, wraparound porch with Doric columns on a wood deck with rock-faced concrete block foundation. Open porch on the rear. Rock-faced concrete block foundation. 2 X 3 bays. Queen Anne style.

1 not-eligible building (NE)

**157A.**

date: Ca. 1910

description: Two-story, side gable, cellar house. Metal roof. Clapboard siding with frieze and corner boards on second floor; rock-faced concrete block on first floor. 2 X 1 bays.

1 not-eligible building (NE)

**157B.**

date: Ca. 1975

description: Trailer.

1 not-eligible building (NE)

**157C.**

date: Ca. 1975

description: One-story, end gable, corn crib. Metal roof. Metal siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**157D.**

date: Ca. 1910

description: Two-story, side gable barn with several shed roof wings. Metal roof. Vertical board siding. Pier foundation. 3 X 2 bays.

1 not-eligible building (NE)

**157E.**

date: Ca. 1910

description: One-story, shallow end gable, saw mill. Metal roof. Metal siding. Still has remnants of some of the equipment in it.

1 not-eligible building (NE)

**0158. GRASS RUN ROAD/COUNTY ROUTE 5/6, residential**

HS-0587

**Hitt House & Farm**

date: Ca. 1890

description: Large, two-story, side gable house with two-story, shed roof wing on the rear with the second floor of the wing enclosed. Rear wing was probably originally a two-story porch. Gable wing attached to rear wing. Metal roof. Asbestos shingle siding. Vertical 2/2 and 1/1 windows. Two-story, hip roof, projecting, three-sided bay on the front. The front door has an undivided transom and arched glazing. One-story, modified hip roof, entrance porch with appliquéd vergeboard, cut-out and scrolled brackets and square posts on an enclosed balustrade. Cut stone and concrete block foundation. 2 X 4 bays. Italianate style.

1 not-eligible building (NE)

**158A.**

date: Ca. 1900

description: Two-story, end gable barn with flanking, shed roof wings. Metal roof. Vertical board siding. Pier foundation. 5 X 1 bays.

1 not-eligible building (NE)

**158B.**

date: Ca. 1900

description: One-story, side gable outbuilding. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**158C.**

date: Ca. 1900

description: One-story, shed roof outbuilding. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**158D.**

date: Ca. 1900

description: One-story, shed roof garage. Metal roof. Board and batten siding. Stone pier foundation. 3 X 1 bays.

1 not-eligible building (NE)

**0159. GRASS RUN ROAD/COUNTY ROUTE 5/6, residential**

HS-0588

**Lynch House**

date: Ca. 1945

description: Two-story, cross gable house. Asphalt shingle roof. German siding with frieze and corner boards. Vertical 3/1 and 1/1 windows; paired on the front porch. One-story, shed roof, front porch with very battered square posts on an enclosed balustrade. One-story, shed roof, full length, rear porch with square posts on an enclosed balustrade. Concrete block foundation. 3 X 3 bays. Queen Anne Cottage style.

1 not-eligible building (NE)

**159A.**

date: Ca. 1975

description: Two-story, side gable, hay barn with rear, shed roof, open wing. Metal roof. Metal siding. Pier foundation. 4 X 2 bays.

1 not-eligible building (NE)

**159B.**

date: Ca. 1930

description: Two-story, end gable garage. Metal roof. Concrete block first floor façade and foundation; clapboard siding on upper floor.

1 not-eligible building (NE)

**159C.**

date: Ca. 1930

description: Two-story, end gable, cellar house. Metal roof. Clapboard siding on upper floor; rock-faced concrete block and concrete block first floor and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**159D.**

date: Ca. 1975

description: One-story, shed roof outbuilding. Metal roof. Metal siding. Pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**0160. GRASS RUN ROAD/COUNTY ROUTE 5/6, residential      HS-0589**

**Butler House & Farm**

date: Ca. 1910

description: Large, two-story, hip roof house with central wall gable on the rear. Asphalt shingle roof. Clapboard siding. Modern 1/1 with snap-in muntins with decorative hoods and surrounds. Metal canopy over rear entrance door. One-story, shed roof, enclosed, rear porch. Small, shed roof, entrance porch on the side with turned posts on a wood deck. Cut stone and stone pier foundation. 3 X 3 bays. Four Square style.

1 not-eligible building (NE)

**160A.**

date: Ca. 1915

description: One-story, end gable outbuilding attached via a breezeway to its twin. Metal roof. Clapboard siding. Vertical 2/2 windows. Stone pier foundation. 3 X 1 bays. The building on the left is collapsing.

1 not-eligible building (NE)

**160B.**

date: Ca. 1950

description: One-story, end gable garage. Asphalt shingle roof. Concrete block façade and foundation. 1 X 3 bays.

1 not-eligible building (NE)

**160C.**

date: Ca. 1915

description: One and one-half-story, end gable barn. Metal roof. Board and batten siding. Pier foundation. 1 X 5 bays. Somewhat deteriorated.

1 not-eligible building (NE)

**160D.**

date: Ca. 1915

description: Large, two and one-half-story, side gable barn. Metal roof. Board and batten siding. Pier foundation. 4 X 1 bays.

1 not-eligible building (NE)

**160E.**

date: Ca. 1950

description: Small, one-story, modified hip roof, well house. Asphalt shingle roof. Vertical board siding. Concrete foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0161. GRASS RUN ROAD/COUNTY ROUTE 5/6, residential**

HS-0590

**Davis/Posey House & Farm**

date: Ca. 1910

description: One-story, rear facing "L" house. Roll roofing. Asphalt shingle and clapboard siding. Vertical 2/2 windows. One-story, shed roof, entrance porch with square posts and lattice balustrade. Two-story, cellar house attached on rear. Concrete block and stone pier foundation. 4 X 8 bays. Bungalow style.

1 not-eligible building (NE)

**161A.**

date: Ca. 1930

description: One-story, side gable outbuilding. Metal roof. Asphalt shingle siding. Stone pier foundation. 4 X 1 bays.

1 not-eligible building (NE)

**161B.**

date: Ca. 1940

description: One-story, side gable garage. Metal roof. Asphalt shingle siding. Concrete block foundation. 2 X 1 bays.

1 not-eligible building (NE)

**161C.**

date: Ca. 1940

description: One-story, shed roof outhouse. Roll roofing. Vertical board siding. Concrete block pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**161D.**

date: Ca. 1930

description: One-story, side gable outbuilding. Metal roof. Asphalt shingle siding. Stone pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**161E.**

date: Ca. 1960

description: One-story, side gable outbuilding. Metal roof. Board and batten siding. Concrete block pier foundation.

1 not-eligible building (NE)

**161F.**

date: Ca. 1980

description: One-story, shed roof, machine shed. Metal roof. 4 X 2 bays.

1 not-eligible building (NE)

**161G.**

date: Ca. 1920

description: One-story, side gable, corn crib. Metal roof. Horizontal board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**161H.**

date: Ca. 1940

description: Two-story, end gable barn. Metal and roll roofing. Concrete block first floor and foundation. 2 X 2 bays.

1 not-eligible building (NE)

**0162. GRASS RUN ROAD/COUNTY ROUTE 5/6, residential  
Marsh/Goodwin House & Farm**

HS-0591

date: Ca. 1910

description: Large, two-story, side gable house with one-story, gable wing on the rear. Interior, corbelled brick chimney on the front portion of the house; interior, brick chimney on rear wing. Asphalt shingle roof. Clapboard siding. Vertical 2/2 windows. One-story, modified hip roof, entrance porch with turned posts and enclosed balustrade. Porch also has Eastlake spindled vergeboard. Open porch on rear wing with square posts on a wood deck. Stone foundation. 3 X 3 bays. "I" house.

1 not-eligible building (NE)

**162A.**

date: Ca. 1910

description: Two-story, side gable, cellar house. Metal roof. Clapboard siding on upper floor; rock-faced concrete block first floor and foundation. 2 X 1 bays.

1 not-eligible building (NE)

**162B.**

date: Ca. 1910

description: One-story, shed roof outbuilding. Roof is collapsed. Vertical board siding. Pier foundation.

1 not-eligible building (NE)

**162C.**

date: Ca. 1910

description: One-story, shed roof outhouse. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**162D.**

date: Ca. 1910

description: Two-story, end gable, log barn with partially collapsed, shed roof wing on the left. Metal roof. Log and vertical board siding façade. Stone pier foundation. 2 X 2 bays.

1 not-eligible building (NE)

**162E.**

date: Ca. 1910

description: One and one-half-story, side gable barn. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**162F.**

date: Ca. 1980

description: One-story, shed roof, wood shed. Metal roof. Horizontal board siding. Pier foundation.

1 not-eligible building (NE)

**0163. GRASS RUN ROAD/COUNTY ROUTE 5/6, residential** HS-0592

**Todd/Goodwin House & Farm**

date: Ca. 1945

description: One-story, side gable house with rear, gable wing of concrete block. Asphalt shingle roof. Chimney has been removed. Clapboard siding. 1/1 windows. One-story, shed roof, enclosed, entrance porch. One-story, shed roof, side porch with square posts on an enclosed balustrade. Pier foundation. 2 X 3 bays. Gabled-ell house. Modified.

1 not-eligible building (NE)

**163A.**

date: Ca. 1945

description: One-story, end gable, banked, cellar house. Metal roof. Concrete block façade and foundation. 2 X 1 bays.

1 not-eligible building (NE)

**163B.**

date: Ca. 1980

description: Trailer.

1 not-eligible building (NE)

**163C.**

date: Ca. 1930

description: One-story, shed roof outbuilding. Roll roofing. Weatherboard siding. Pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**0164. ROCKCAMP RUN ROAD, residential** HS-0593

**Cummings/Day House**

date: Ca. 1890

description: Two-story, rear facing "L" house. Three, interior, corbelled brick chimneys. Asphalt shingle roof. Scrolled brackets at the corners of the roof. There are applied florettes on the frieze board. German siding with frieze and corner boards. 1/1 and vertical 2/2 windows with gable pedimented hoods and simple surrounds; the windows on the rear have surrounds with bulls-eye corner blocks. One-story, shed roof, three-quarter length, enclosed, front porch with concrete block foundation. One-story, shed roof, enclosed porch on the rear. Small, open, rear porch with chamfered posts on concrete block foundation. End gable outbuilding attached on rear. One-story, shed roof

wing on the side attaches to another gable outbuilding. Cut stone foundation. 4 X 3 bays. "T" house.

1 not-eligible building (NE)

**164A.**

date: Ca. 1915

description: Two-story, end gable, cellar house with one-story, shed roof wing on the right. Metal roof. Clapboard siding on upper floor; rock-faced concrete block first floor and foundation. 2 X 1 bays.

1 not-eligible building (NE)

**164B.**

date: Ca. 1930

description: One-story, end gable, milk house. Roll roofing. Concrete block façade and foundation. 3 X 1 bays.

1 not-eligible building (NE)

**0165. TEN MILE CREEK ROAD/COUNTY ROUTE 5, residential      HS-0594  
Pleasant Prospect Farm/Wikert/Hardman House & Farm**

date: Ca. 1900

description: Two-story, rear facing "L" house. Two, interior, corbelled brick chimneys. Asphalt shingle roof. Aluminum siding. Modern 1/1 windows with metal shed canopies. One-story, modified hip roof, entrance porch with wrought iron posts and railing. Gable breezeway in the rear attaches house to a two-story, end gable, cellar house. Cellar house has a metal roof, plywood siding on the upper floor and cut stone first floor and foundation. One-story, shed roof wing on the right with a large, exposed, brick chimney. Concrete block foundation. 5 X 2 bays. "T" house. Modified.

1 not-eligible building (NE)

**165A.**

date: Ca. 1940

description: One-story, end gable garage. Metal roof. Weatherboard siding. Concrete block foundation. 1 X 2 bays.

1 not-eligible building (NE)

**165B.**

date: Ca. 1950

description: One and one-half-story, end gable garage. Metal roof. Painted metal siding. 8/8 windows. Stone foundation.

1 not-eligible building (NE)

**165C.**

date: Ca. 1920

description: One-story, shed roof, chicken coop. Metal roof. Board and batten siding. Pier foundation. 3 X 1 bays.

1 not-eligible building (NE)

**165D.**

date: Ca. 1900

description: One-story, end gable barn with shed roof, enclosed wing on the rear. Metal roof. Vertical board siding. Stone pier foundation.

1 not-eligible building (NE)

**165E.**

date: Ca. 1900

description: Two-story, end gable barn with shed roof wing on the right. Metal roof. Vertical board siding. Pier foundation. 2 X 2 bays.

1 not-eligible building (NE)

**165F.**

date: Ca. 1900

description: Two-story, end gable barn with shed roof wing on the right. Metal roof. Vertical board siding. Pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**165G.**

date: Ca. 1900

description: One-story, shed roof outbuilding. Metal roof. Vertical board siding. Stone pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0166. TEN MILE CREEK ROAD/COUNTY ROUTE 5, residential                      HS-0595**  
**Seckman House & Farm**

date: Ca. 1910

description: One-story, hip gable roof house. Asphalt shingle roof. Interior, brick chimney. Vinyl siding. Modern 1/1 windows. One-story, end gable, enclosed, entrance porch. Three-sided, projecting, gable bays. Foundation is covered. 2 X 3 bays. Queen Anne style. Modified.

1 not-eligible building (NE)

**166A.**

date: Ca. 1990

description: One-story, end gable outbuilding. Asphalt shingle roof. Vinyl siding. Concrete foundation. 1 X 1 bays.

1 not-eligible building (NE)

**166B.**

date: Ca. 1990

description: One-story, shed roof, machine shed. Metal roof. 6 X 1 bays.

1 not-eligible building (NE)

**166C.**

date: Ca. 1990

description: One-story, end gable barn. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0167. TEN MILE CREEK ROAD/COUNTY ROUTE 5, residential                      HS-0596**  
**Jablon/Lanham House & Farm**

date: Ca. 1875

description: Two-story, side gable, log house with one-story, shed roof, flanking wings. Metal roof. Wings have board and batten and plywood siding. 1/1, single pane, metal and vertical 2/2 windows. Two, shed roof wings on the rear: one is partially log and

board and batten siding; the other has plywood siding. Stone pier and concrete block pier foundation. 3 X 3 bays. Midland Log style. Modified.

1 not-eligible building (NE)

**167A.**

date: Ca. 1910

description: One-story, rear facing "L" house. Two, interior, cut stone chimneys. Asphalt shingle roof. Clapboard siding. Vertical 2/2 windows with simple hoods. One-story, shed roof, entrance porch with slender, square posts. Two entrance doors with undivided transom. Stone foundation. 4 X 2 bays.

1 not-eligible building (NE)

**167B.**

date: Ca. 1910

description: Two-story, end gable, cellar house with forebay. Metal roof. Board and batten siding on upper floor; cut stone on first floor and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**167C.**

date: Ca. 1910

description: One-story, shed roof, corn crib. Metal roof. Slatted siding. Pier foundation. 1 X 1 bays.

1 not-eligible building(NE)

**167D.**

date: Ca. 1880

description: One-story, end gable, log barn with flanking, shed roof wings. Some of the logs have been covered with vertical board siding. Metal roof. Concrete block and stone pier foundation. 5 X 1 bays.

1 not-eligible building (NE)

**167E.**

date: Ca. 1985

description: One-story, shed roof outbuilding. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0168. FLINDERATION FORK ROAD, residential**

HS-0597

**George/Davis House & Farm**

date: 1905

description: Two-story, hip roof house with gable dormers and a gable wing on the rear. Small, shed roof wing on the right. Asphalt shingle roof. Chimney was removed. Clapboard siding. Modern 1/1 windows. Appears that the original front porch was incorporated into the main body of the house historically. Brick and stone pier foundation. 3 X 4 bays. Queen Anne style.

1 not-eligible building (NE)

**168A.**

date: Ca. 1905

description: Two-story, side gable, cellar house with shed roof wing. Metal roof. Asbestos shingle and clapboard siding on upper floor; cut stone first floor and foundation. Vertical 2/2 and 1/1 windows. 2 X 1 bays.

1 not-eligible building (NE)

**168B.**

date: Ca. 1940

description: One-story, shed roof outhouse. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**168C.**

date: Ca. 1910

description: Two-story, end gable barn with flanking, shed roof, enclosed wings. Metal roof. Asphalt shingle siding over vertical boards. Pier foundation. 4 X 7 bays.

1 not-eligible building (NE)

**168D.**

date: Ca. 1910

description: One-story, shed roof outbuilding. Metal roof. Asbestos shingle and asphalt shingle siding over vertical boards. Pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**168E.**

date: Ca. 1930

description: One-story, end gable, gas shack. Metal roof. Metal siding. 8/8 window. Stone pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0169. FLINDERATION FORK ROAD, residential      Reaser House      HS-0598**

date: Ca. 1940

description: Two-story, side gable house with large, central, wall gable on the front. Asphalt shingle roof. Exposed, brick chimney on the end. Asbestos shingle siding. Vertical 3/1 windows; some are paired. Small, end gable, entrance portico supported by slightly battered posts on brick balustrade. One-story, modified hip roof, side porch with slightly battered posts on an enclosed balustrade. One-story, shed roof, enclosed, rear porch. Concrete block foundation. 3 X 2 bays. Craftsman style.

1 not-eligible building (NE)

**169A.**

date: Ca. 1945

description: One-story, end gable garage with shed roof wing on the right. Metal roof. Concrete block façade and foundation. Wing is covered with asphalt shingle siding and there is asbestos shingle siding in the gable end. 2 X 1 bays.

1 not-eligible building (NE)

**169B.**

date: Ca. 1950

description: Large, two-story, gambrel roof barn with shed roof wing on the front. Metal roof. Board and batten siding. Pier foundation. 4 X 3 bays.

1 not-eligible building (NE)

**169C.**

date: Ca. 1950

description: One-story, shed roof outhouse. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**169D.**

date: Ca. 1940

description: One-story, end gable outbuilding. Metal roof. Clapboard siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**169E.**

date: Ca. 1950

description: One-story, shallow end gable outbuilding. Metal roof. Vertical board siding. Pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**0170. FLINDERATION FORK ROAD, residential**

HS-0599

**Ebony Glen Farm/Reaser/Shahan House & Farm**

date: Ca. 1890/Ca. 1910

description: Tall, narrow (15' deep), two-story, side gable house with one-story, gable wing. Rear wing ca. 1890; front portion ca. 1910. Asphalt shingle roof. Interior, stone chimney on rear wing; non-original. Large, two-story, shed roof, projecting, entrance portico with two-story Doric columns on a concrete and stone deck. Aluminum siding. Modern 6/6 windows. Rear wing has an open, shed roof porch on the side with modern Doric posts on an enclosed stone balustrade. Cut stone foundation covered with real stone veneer. 3 X 3 bays. "I" house. Modified.

1 not-eligible building (NE)

**170A.**

date: Ca. 1895

description: One and one-half-story, end gable granary. Metal roof. Board and batten and lattice siding. Stone foundation. 1 X 1 bays.

1 not-eligible building (NE)

**170B.**

date: Ca. 1895

description: Two-story, end gable, cellar house. Corrugated metal roof. Board and batten siding on second floor; cut stone first floor and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**170C.**

date: Ca. 1995

description: One-story, side gable garage. Corrugated metal roof. Vinyl siding. Modern windows. Concrete block foundation. 3 X 1 bays.

1 not-eligible building (NE)

**170D.**

date: Ca. 1895

description: Large, two-story, side gable barn with shed roof wing on the left and on the rear. "V" seam metal roof. Board and batten siding. Stone pier foundation. 2 X 2 bays.

1 not-eligible building (NE)

**0171. INDIAN RUN ROAD/COUNTY ROUTE 5/7**

HS-0600

**Randolph House**

date: Ca. 1905

description: Large, tall, steep, two-story, end gable with a narrow, side gable, projecting bay on the right and two, one-story, gable wings on the rear: one of the rear wings is modern. Asphalt shingle roof. Interior, brick chimney. The gable ends have vergeboard, fishscale shingles and dropped finials. Scrolled corner brackets. Clapboard siding with frieze and corner boards. Modern 1/1 and 6/6 windows with simple hoods and decorative surrounds. One-story, end gable, projecting, entrance portico with scrolled vergeboard and dropped finials. Ball finials on the supporting braces for the portico. Porch has Eastlake spindled vergeboard, scrolled brackets, turned posts and spindled balustrade. Cut stone foundation; concrete block on porch. 2 X 6 bays. Folk Victorian style.  
1 building eligible to the National Register (CE)

**171A.**

date: Ca. 1905

description: Small, end gable, one-story, cellar house with shed roof wing on the right. Asphalt shingle roof. Plywood and cut stone façade. Stone foundation. 3 X 6 bays.  
Modified.

1 not-eligible building (NE)

**171B.**

date: Ca. 1980

description: One-story, end gable garage with shed roof wing on the left. Metal roof. Plywood siding. Pier foundation. 3 X 1 bays.

1 not-eligible building (NE)

**171C.**

date: Ca. 1905

description: Large, three-story, end gable barn. Metal roof. Board and batten siding. Stone pier foundation. 2 X 3 bays.

1 building eligible to the National Register (CE)

**171D.**

date: Ca. 1990

description: Two-story, pyramidal roofed house. Asphalt shingle roof. Board siding. Vinyl windows. Concrete foundation. Two elevated small decks.

1 not-eligible building (NE)

**0172. INDIAN RUN ROAD/COUNTY ROUTE 5/7, residential**

HS-0601

**Matthey/Morgan House/Haymond Farm**

date: Ca. 1915

description: Small, two-story, end gable house. Interior, corbelled brick chimney. "V" seam metal roof. Unpainted board and batten siding. 1/1 windows; paired in the gable end. Small, shed roof, one-story, entrance porch with square posts on a wood deck – non-original. Stone pier foundation covered with wood siding and asphalt shingle siding. 3 X 2 bays.

1 not-eligible building (NE)

**172A.**

date: Ca. 1990

description: One-story, side gable, machine shed. Metal roof supported by steel posts and trusses.

1 not-eligible building (NE)

**172B.**

date: Ca. 1980

description: One-story, shed roof outbuilding. Metal roof. Particleboard siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**172C.**

date: Ca. 1980

description: One-story, side gable, machine shed/barn with flanking, enclosed, shed roof wings. Metal roof. Vertical board siding. Pier foundation. 3 X 1 bays.

1 not-eligible building (NE)

**172D.**

date: Ca. 1915

description: Small, one-story, shed roof, corn crib. Metal roof. Lattice siding. Pier foundation. 2 X 2 bays.

1 not-eligible building (NE)

**0173. INDIAN RUN ROAD/COUNTY ROUTE 5/7, residential      HS-0602**

**McWilliams House/Shaffer/Haymond House & Farm**

date: 1905/Ca. 1945

description: Very large, two-story, rear facing "L" house. Original portion is the front, ca. 1905, and the rear is ca. 1940. Hip asphalt shingle roof. Interior, corbelled brick chimney. Scrolled corner and roof brackets. Clapboard siding with frieze and corner boards. 1/1 windows with simple hoods and surrounds. One-story, hip roof, three-sided, projecting bay on the front. One-story, modified hip roof, wraparound porch with turned posts and spindled balustrade. Rear has a breezeway that attaches the house to a two-story, side gable, cellar house. Stone foundation under original portion of house; remainder has rock-faced concrete block foundation. 3 X 4 bays. Italianate style.

1 building eligible to the National Register (CE)

**173A.**

date: Ca. 1910

description: One-story, side gable outbuilding. Metal roof. Board and batten siding. Vertical 2/2 windows. Stone and concrete block pier foundation.

1 building eligible to the National Register (CE)

**173B.**

date: Ca. 1990

description: Two-story, end gable garage/outbuilding with shed roof wing on the right that is the garage bay. Roll roofing. Clapboard siding. Modern windows. Concrete block foundation.

1 not-eligible building (NE)

**173C.**

date: Ca. 1910

description: Small, one-story, end gable outbuilding. Metal roof. Vertical board siding. Stone pier foundation. 1 X 1 bays.

1 building eligible to the National Register (CE)

**173D.**

date: Ca. 1990

description: One-story, end gable outbuilding. Roll roofing. Plywood siding. Concrete block foundation. 2 X 1 bays.

1 not-eligible building (NE)

**0174. INDIAN RUN ROAD/COUNTY ROUTE 5/7, residential**

HS-0603

**Andrews House/Indian Run School House**

date: Ca. 1925

description: Two-story, cross gable house. Interior, corbelled brick chimney. Asphalt shingle roof. Vinyl siding. Modern 9/9 and 4/4 windows. One-story, end gable, projecting, entrance portico with square posts and wrought iron railing. One-story, shed roof, enclosed, rear porch. Concrete block foundation. 3 X 2 bays. Minimal Traditional style. Modified.

1 not-eligible building (NE)

**174A.**

date: Ca. 1980

description: One-story, end gable garage. Asphalt shingle roof. Concrete block façade and foundation. 2 X 1 bays.

1 not-eligible building (NE)

**174B.**

date: Ca. 1925

description: One-story, end gable, corn crib. Metal roof. Vertical board and lattice siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**174C.**

date: Ca. 1925

description: Large, two-story, end gable barn. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0175. INDIAN RUN ROAD/COUNTY ROUTE 5/7, residential**

HS-0604

**Matthey House & Farm**

date: Ca. 1910

description: Two-story, side gable house with central, projecting wall gable on the front. Enclosed bay on the second story over the front porch. Metal roof. Interior, brick chimney. Asphalt shingle and clapboard siding. 1/1 and vertical 2/2 windows. One-story, modified hip roof, front porch partially enclosed; remainder has slightly battered square columns on an enclosed concrete balustrade. Pier foundation. 4 X 1 bays. "I" house.

1 not-eligible building (NE)

**175A.**

date: Ca. 1935

description: Two-story, hip roof garage with central, end gable dormer on the front. Asphalt shingle roof. 1/1 windows on the second floor. Asphalt shingle siding on the second floor; concrete block first floor and foundation. Two garage bays on the first floor. 2 X 2 bays.

1 not-eligible building (NE)

**175B.**

date: Ca. 1980

description: Two-story, end gable, machine shed. Metal roof supported by telephone poles. 3 X 2 bays.

1 not-eligible building (NE)

**175C.**

date: Ca. 1910

description: Two-story, end gable barn. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**175D.**

date: Ca. 1935

description: One-story, end gable outbuilding. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0176. INDIAN RUN ROAD/COUNTY ROUTE 5/7, residential**

HS-0605

**Leinbach House**

date: Ca. 1900

description: Large, two-story, side gable house with a two-story, shed roof wing on the rear. Central, interior, corbelled brick chimney. Standing seam metal roof. Clapboard siding with frieze and narrow corner boards. Vertical 3/1, vertical 2/2 and 1/1 windows with simple hoods; tripartite windows on the front porch. One-story, shed roof, three-quarter length, front porch with square posts on an enclosed balustrade. Small, gable wing on the rear. Modern deck on rear. Concrete block and stone veneer foundation. 3 X 2 bays. "T" house.

1 not-eligible building (NE)

**176A.**

date: Ca. 1970

description: One-story, end gable garage. Roll roofing. Concrete block façade and foundation. 2 X 1 bays.

1 not-eligible building (NE)

**176B.**

date: Ca. 1900

description: Two-story, end gable barn. Metal roof. Board and batten siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0177. CHERRY CAMP RUN ROAD/COUNTY ROUTE 50/3, residential      HS-0606**  
**McCarty House**

date: Ca. 1915

description: Large, tall, two-story, side gable house. Asphalt shingle roof. Corner scrolled brackets. Asbestos shingle siding with frieze and corner boards. Modern 1/1 windows with simple hoods. One-story, hip roof, three-sided, projecting bay on the front on the left. Small, one-story, shed roof, entrance porch with wrought iron posts and railing on a concrete block pier foundation – non-original. One-story, modified hip roof, full length, rear, enclosed porch. Stone foundation. 4 X 2 bays. “I” house.

1 not-eligible building (NE)

**177A.**

date: Ca. 1915

description: Two-story, side gable barn with shed roof wing on the rear and on the right, enclosed. Corrugated metal roof. Vertical board siding. Pier foundation. 3 X 3 bays.

1 not-eligible building (NE)

**177B.**

date: Ca. 1915

description: Small, one-story, end gable building. Old School? Metal roof. Exposed rafter tails. Clapboard siding. Stone pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**177C.**

date: Ca. 1990

description: Large, tall, one-story, shed roof, machine shed. Metal roof. Metal siding. Steel supports and beams. 6 X 1 bays.

1 not-eligible building (NE)

**177D.**

date: Ca. 1915

description: One-story, side gable barn with shed roof wing on the left. Front has been removed to create a machine shed. Corrugated metal roof. Vertical board and metal siding. Pier foundation. 3 X 1 bays.

1 not-eligible building (NE)

**0178. CHERRY CAMP RUN ROAD/COUNTY ROUTE 50/3, residential      HS-0607**  
**Ashcraft House**

date: Ca. 1915

description: Two-story, front facing “T” house with one-story wing on the rear. Exposed, brick chimney on the front – non-original. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows. One-story, end gable, projecting, entrance porch with square columns on a concrete deck – non-original. Stone and concrete block foundation. 2 X 4 bays. “I” house. Modified.

1 not-eligible building (NE)

**178A.**

date: Ca. 1915

description: Small, one-story, end gable outbuilding with flanking, shed roof wings. The wings are garage bays. Metal roof. Board siding. Stone foundation. 3 X 1 bays.

1 not-eligible building (NE)

**178B.**

date: Ca. 1930

description: One-story, end gable outbuilding with shed roof wing on the right. Metal roof. Metal siding. Pier foundation. 1 X 1 bays. Gas shack.

1 not-eligible building (NE)

**178C.**

date: Ca. 1995

description: One-story, side gable garage with shed roof wing on rear. Asphalt shingle roof. Concrete façade and foundation. 4 X 2 bays.

1 not-eligible building (NE)

**0179. CHERRYCAMP RUN ROAD/COUNTY ROUTE 50/3, residential**

**Matthey House & Farm**

HS-0608

date: Ca. 1900

description: Two-story, side gable house with one-story, gable wing. Interior, stone chimney. Standing seam metal roof. Asphalt shingle siding. 1/1 windows. Small, end gable, entrance canopy supported by knee braces. Two-story, end gable, cellar house attached to the main house in the rear. Stone foundation. 3 X 3 bays. "I" house.

1 not-eligible building (NE)

**179A.**

date: Ca. 1900

description: Two-story, end gable, cellar house. Roof is collapsed. Metal roof. Vertical board siding on upper floor; stone first floor and foundation. 1 X 1 bays. Deteriorated.

1 not-eligible building (NE)

**179B.**

date: Ca. 1900

description: Large, three-story, gambrel roof barn with shed roof wing on the right. Metal roof. Vertical board siding. Stone pier foundation. 3 X 2 bays.

1 not-eligible building (NE)

**179C.**

date: Ca. 1900

description: Small, one-story, end gable outbuilding. Metal roof. Board and batten siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0180. CHERRYCAMP RUN ROAD/COUNTY ROUTE 50/3, residential**

**Dennison House**

HS-0609

date: Ca. 1915

description: Large, two-story, hip roof house. Central, interior, brick chimney. Asphalt shingle roof. Vinyl siding. 1/1 windows. One-story, modified hip roof, wraparound porch with Doric columns on a wood deck with stone pier foundation. Two-story, cellar house attached to main house via a small breezeway in the rear. Stone foundation. 4 X 3 bays. Four Square style.

1 not-eligible building (NE)

**180A.**

date: Ca. 1940

description: One-story, end gable garage. Asphalt shingle roof. Concrete block façade and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0181. COUNTY ROUTE 50/53, residential**

HS-0610

**Haught House & Farm/New Dale Farm**

date: Ca. 1916

description: Large, two-story, cross gable house. Metal roof. German siding. 1/1 windows; paired on the front porch. Central chimney – partially dismantled. Shingles in the gable end. One-story, hip roof, wraparound porch with chamfered posts and spoked brackets. Two-story, shed roof, rear porch with the second floor enclosed; the first floor has square posts. One-story, hip roof, three-sided, projecting bay on the rear. Stone pier foundation covered with faux stone and metal siding. 2 X 3 bays. Folk Victorian style.

1 not-eligible building (NE)

**181A.**

date: Ca. 1920

description: Small, one-story, hip roof outbuilding with flanking, enclosed, shed roof wings. Metal roof. Rock-faced concrete block and concrete block façade.

1 not-eligible building (NE)

**181B.**

date: Ca. 1970

description: One-story, end gable outbuilding. Metal roof. Board and batten siding. Wood pier foundation. 3 X 4 bays.

1 not-eligible building (NE)

**181C.**

date: Ca. 1920

description: One-story, end gable barn with front parapet roof. Metal roof. Board siding. Pier and concrete block foundation. 3 X 1 bays.

1 not-eligible building (NE)

**181D.**

date: Ca. 1920

description: Large, two-story, gambrel roof barn. Metal roof. Vertical board siding. Pier foundation. 3 X 1 bays.

1 not-eligible building (NE)

**181E.**

date: Ca. 1940

description: One-story, end gable outbuilding. Metal roof. Metal siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**181F.**

date: Ca. 1940

description: Large, two-story, hip gable roof, cellar house with numerous attachments. Roll roofing. German siding on upper floor; concrete block on first floor. Metal casement windows.

1 not-eligible building (NE)

**0182. TURKEY RUN ROAD/COUNTY ROUTE 50/2, residential HS-0611**

**Cole/Bond House**

date: Ca. 1900

description: Two-story, rear facing "L" house. Asphalt shingle roof. Central, corbelled brick chimney. Large, central, end gable dormer on the front flanked by smaller, end gable dormers. Decorative shingles and herringbone siding with ends that are cut off at a 45 degree angle in the gable ends. Clapboard siding with frieze and corner boards. 1/1 windows with decorative, projecting window hoods. One-story, shed roof, three-quarter length, front porch with square posts on an enclosed balustrade. Porch has rock-faced concrete block pier foundation infilled with concrete block. Small, one-story, shed roof wing on the left with rock-faced concrete block pier foundation infilled with concrete block. One-story, shed roof, breezeway on the rear attaches to a one-story, gable wing with board and batten siding and pier foundation. Stone foundation. 3 X 3 bays. Folk Victorian style.

1 not-eligible building (NE)

**182A.**

date: Ca. 1900

description: One and one-half-story, end gable barn with flanking, shed roof, enclosed wings. Open, shed roof wing on the front also. Metal roof. Vertical board siding. Pier foundation. 4 X 1 bays.

1 not-eligible building (NE)

**182B.**

date: Ca. 1900

description: Two-story, side gable barn with shed roof wing on the left. Corrugated metal roof. Vertical board siding. Concrete block on the wing. Pier foundation. 2 X 2 bays.

1 not-eligible building (NE)

**182C.**

date: Ca. 1940

description: One-story, end gable garage. Metal roof. Board and batten and weatherboard siding. Concrete foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0183. HALLS RUN ROAD/COUNTY ROUTE 50/8, residential HS-0612**

**Williams House/Yale Frame Home Place/One Room Log School House**

date: Ca. 1861

description: Two-story, rear facing "L" house; rear portion not original. Asphalt shingle roof. Interior, corbelled brick chimney on the front; interior, brick chimney on the rear. Vinyl siding. Modern 6/1 windows with shutters; vertical 2/2 windows on front porch. One-story, shed roof, three-quarter length, front porch with modern square posts on an

enclosed balustrade. Pier foundation under porch; main house has stone foundation; rear wing has concrete foundation. 3 X 3 bays. "T" house. Modified.

1 not-eligible building (NE)

**183A.**

date: Ca. 1940

description: One-story, end gable garage. Asphalt shingle roof. Weatherboard siding. Concrete block foundation. 2 X 1 bays.

1 not-eligible building (NE)

**183B.**

date: Ca. 1860

description: One-story, shed roof, cellar house. Original second story has been removed. Metal roof. Cut stone façade and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0184. HALLS RUN ROAD/COUNTY ROUTE 50/8, residential**

HS-0613

**Trovato House**

date: Ca. 1930

description: Two-story, hip roof house. Interior, corbelled brick chimney. Asphalt shingle roof. Aluminum siding. Modern 1/1 windows; paired on the front porch; tripartite on the second floor on the front. One-story, shed roof, full length, front porch with modern square posts and lattice balustrade. One-story, modified hip roof, rear porch has been partially enclosed; remainder has modern square posts on a concrete block deck. Concrete block, well house attached on the side of the house. Concrete block foundation. 3 X 2 bays. Four Square style. Modified.

1 not-eligible building (NE)

**184A.**

date: Ca. 1995

description: One-story, end gable outbuilding. Roll roofing. Plywood siding. Concrete block pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**184B.**

date: Ca. 1930

description: Two-story, end gable, cellar house with forebay. Roll roofing. Board and batten siding on the second floor; terra cotta block on the first floor and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**184C.**

date: Ca. 1995

description: One-story, shed roof, chicken coop. Roll roofing. Particle board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0185. RACoon RUN ROAD/COUNTY ROUTE 50/6, residential  
Bowen/Keesy/Boggess House**

HS-0614

date: Ca. 1865

description: Two-story, side gable house with one-story, gable wing on the rear. Onduline roofing. Interior, brick chimney. Partial return cornice. Aluminum siding. A variety of modern 1/1 windows. One-story, modified hip roof, three-quarter length, front porch with modern square posts and lattice balustrade. One-story, hip roof, three-sided, projecting bay on the rear wing. Cut stone foundation; front porch has rock-faced concrete block pier foundation. 3 X 3 bays. "T" house. Modified.

1 not-eligible building (NE)

**185A.**

date: Ca. 1990

description: One-story, end gable outbuilding with enclosed, shed roof wing on the rear. Asphalt shingle roof. Particle board and plywood siding. Concrete block pier foundation.

1 not-eligible building (NE)

**185B.**

date: Ca. 1990

description: One-story, shed roof, wood shed. Metal roof. Metal siding. Pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**0186. RACoon RUN ROAD/COUNTY ROUTE 50/6, residential  
Barker/Poling House/Edgar Matthey House & Farm**

HS-0615

date: Ca. 1863

description: Large, two-story, rear facing "L" house. Interior, corbelled brick chimney; exposed, concrete block chimney on rear wing porch. One-story, gable addition on rear that appears to have been the original cellar house as it has a cut stone foundation. Asphalt shingle roof. Partial return cornice. Vinyl siding. Modern 9/1 and 1/1 windows; many with arches that have been infilled with wood. Two-story, modified hip roof, full length, front porch that has been enclosed on the second floor and the ends of the first floor; rock-faced concrete block square columns and enclosed brick balustrade. Novelty windows on enclosed front porch. Original rear wing has its original porch fully enclosed. Rock-faced concrete block foundation on porch; stone foundation on main house; concrete and concrete block foundation on rear wings/additions. Front door has an undivided arched transom and divided, glazed sidelights. 3 X 7 bays. Gabled-ell house with Italianate details. Modified.

1 not-eligible building (NE)

**186A.**

date: Ca. 1950

description: One-story, side gable garage. Asphalt shingle roof. Concrete block façade and foundation. Vinyl siding in gable end. Metal casement windows. 4 X 1 bays.

1 not-eligible building (NE)

**0187. RACOON RUN ROAD/COUNTY ROUTE 50/6, residential**

HS-0616

**Ross House**

date: Ca. 1925

description: Steep, two-story, cross gable house. Asphalt shingle roof. Chimney has been removed. Two, gable dormers on the front; one appears to be modern. Partial return cornice. Vinyl siding. Modern 1/1 windows with shutters; modern bow windows added to front, side and rear. One-story, modified hip roof, front porch with modern Doric posts on an enclosed balustrade. Rock-faced concrete block and concrete block foundation. 4 X 2 bays. Bungalow style. Very modified.

1 not-eligible building (NE)

**187A.**

date: Ca. 1910

description: One-story, end gable barn. Corrugated metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**187B.**

date: Ca. 1910

description: Two-story, end gable barn with shed roof wing. Metal roof. Vertical board siding. Pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**187C.**

date: Ca. 1925

description: Two-story, end gable, cellar house. Asphalt shingle roof. Vinyl siding on second floor; rock-faced concrete block first floor and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**187D.**

date: Ca. 1940

description: Two-story, side gable barn with flanking, shed roof wings. Metal roof. Board and batten siding on second floor; concrete block first floor and foundation. Pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**187E.**

date: Ca. 1910

description: One-story, shed roof outbuilding. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**187F.**

date: Ca. 1940

description: One-story, side gable outbuilding. Metal roof. Board siding. Concrete block pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**187G.**

date: Ca. 1940

description: One-story, shed roof, chicken coop with shed roof wing. Roll roofing. Board and batten siding. Concrete block pier foundation. 8 X 1 bays.

1 not-eligible building (NE)

**0188. RACoon RUN ROAD/COUNTY ROUTE 50/6, residential** HS-0617  
**Ross/Golden House/Johnson House and Farm**

date: Ca. 1920

description: Large, two-story, hip roof house with gable wing on rear. Wall gable on the front and side. Metal shingle roof. Two, interior, corbelled brick chimneys. Gable ends have decorative shingles and diamond-shaped windows. Asbestos shingle siding. 1/1 windows with simple hoods. One-story, modified hip roof, wraparound porch with Doric columns on an enclosed balustrade of fishscale shingles. Stone foundation; rear wing has concrete block foundation; front porch has rock-faced concrete block foundation. 2 X 5 bays. Queen Anne style.

1 not-eligible building (NE)

**188A.**

date: Ca. 1930

description: One-story, side gable outbuilding. Roll roofing. Clapboard siding. Pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**188B.**

date: Ca. 1930

description: Two-story, end gable, cellar house. Interior, brick chimney. Clapboard siding on second floor; terra cotta block first floor and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**188C.**

date: Ca. 1950

description: One-story, hip gable garage. Roll roofing. Concrete block façade and foundation. 2 X 1 bays.

1 not-eligible building (NE)

**0189. RACoon RUN ROAD/COUNTY ROUTE 50/6, residential** HS-0618  
**Pedrick House/Headley Farm**

date: Ca. 1920

description: Two-story, hip roof house with gable bay on the front. Asphalt shingle roof. Interior, brick chimney – partially dismantled. Scrolled, cut-out brackets at the roofs corners. Clapboard siding with frieze and corner boards. 1/1 windows. One-story, hip roof, three-sided, projecting bay on right of house. One-story, wraparound porch with curved corner and modern square posts with “Y” braces at the top. Portion of the porch on the side has been enclosed. Diamond-shaped window on front porch. Picture window in front gable bay. One-story, shed roof, enclosed, rear wings. Brick foundation. 2 X 3 bays. Queen Anne style.

1 not-eligible building (NE)

**189A.**

date: Ca. 1925

description: Two-story, end gable outbuilding. Top section was a school house and it was moved to the present location with horses. “V” seam metal roof. Clapboard siding with frieze and corner boards on second floor. 9/9 and metal casement windows. Rock-faced concrete block first floor and foundation. 1 X 2 bays.

1 not-eligible building (NE)

**0190. JARVISVILLE ROAD/COUNTY ROUTE 31, residential  
England/Stonestreet House & Farm**

HS-0619

date: 1918

description: Large, two-story, hip roof, rear facing "L" house. Three, interior, stone chimneys. Asphalt shingle roof. Central, hip dormer on front. Rock-faced concrete block façade. Vertical 4/1 and 3/1 novelty windows with rock-faced concrete block lintels with keystones and concrete sills. One-story, modified hip roof, full length, front porch with large square columns on a concrete deck. Double entrance doors with divided transom and glazed sidelights. Bronze plaque on the front porch reads "Erected by Alexander and Martha A. Carr Stonestreet 1918 \*1919." Rear porch with square columns on a concrete deck. Rear portion of house has a one-story, gable wing attached with faux stone façade and an exposed, brick chimney. Concrete foundation. 5 X 6 bays. Prairie style.

1 building eligible to the National Register (CE)

**190A.**

date: Ca. 1925

description: One-story, hip roof garage. Asphalt shingle roof. Terra cotta block façade and foundation. 2 X 1 bays.

1 building eligible to the National Register (CE)

**190B.**

date: Ca. 1925

description: One-story, end gable outbuilding. Metal roof. Terra cotta block façade and foundation. Metal casement windows. 5 X 1 bays.

1 building eligible to the National Register (CE)

**190C.**

date: Ca. 1918

description: One-story, side gable outbuilding. Asphalt shingle roof. Rock-faced concrete block façade and foundation. 4 X 1 bays.

1 building eligible to the National Register (CE)

**190D.**

date: Ca. 1940

description: Two-story, end gable outbuilding/residence. Asphalt shingle roof. Weatherboard siding on second floor; concrete block on first floor. 2 X 1 bays.

1 not-eligible building (NE)

**190E.**

date: Ca. 1940

description: One-story, end gable, machine shed with shed roof, enclosed wing on the right. Roll roofing. Vertical board siding. Pier foundation. 2 X 1 bays.

1 building eligible to the National Register (CE)

**190F.**

date: Ca. 1940

description: One-story, end gable outbuilding. Metal roof. Concrete block façade and foundation. 1 X 1 bays.

1 building eligible to the National Register (CE)

**190G.**

date: Ca. 1940

description: Two-story, end gable barn. Metal roof. Vertical board siding. Pier foundation. 3 X 1 bays.

1 building eligible to the National Register (CE)

**0191. JARVISVILLE ROAD/COUNTY ROUTE 31, residential**

HS-0620

**Myers House & Farm**

date: Ca. 1910

description: Large, two-story, end gable house. One, interior, stone chimney; one, interior, brick chimney. Metal roof. Scrolled brackets. Clapboard and cove siding with frieze and corner boards. Vertical 2/2 windows with gable pedimented hoods with applied diamond-shaped appliques and simple surrounds. One-story, wraparound porch with Doric posts on rock-faced concrete block piers. As the porch wraps to the side there is a small, enclosed portion of the porch with a chimney in it. Entrance door has undivided transom with gable pedimented hood and simple surround. Stone foundation. 3 X 3 bays. Italianate style.

1 not-eligible building (NE)

**191A.**

date: Ca. 1910

description: Two-story, side gable, cellar house. Corrugated metal roof. Corner brackets. Clapboard siding on second floor; cut stone first floor and foundation. 12/12 windows. Entrance door with divided transom.

1 not-eligible building (NE)

**191B.**

date: Ca. 1985

description: One-story, side gable house. Asphalt shingle roof. Vinyl siding. Modern vinyl windows. Concrete block foundation. Attached garage bay on the right that is partially open. Exposed, brick chimney. 4 X 2 bays.

1 not-eligible building (NE)

**191C.**

date: Ca. 1970

description: One-story, end gable garage/barn with shed roof wing on the right. Corrugated metal roof. Metal and board siding. 2 X 1 bays. Deteriorated and partially collapsed.

1 not-eligible building (NE)

**191D.**

date: Ca. 1920

description: Large, two-story, end gable barn. Metal roof. Two roof monitors. Vertical board siding. Rock-faced concrete block foundation. 2 X 5 bays.

1 not-eligible building (NE)

**0192. SHAWS RUN ROAD/COUNTY ROUTE 33/1, residential**

HS-0621

**Southern House**

date: Ca. 1915

description: Large, two-story, hip roof house with large, two-story, end gable, projecting bay on the front. Gable bay has partial return cornice and Palladian window. Asphalt shingle roof. Chimney has been removed. Clapboard siding with frieze and corner boards. 1/1 windows; many are paired. One-story, shed roof, entrance porch with Doric columns on a concrete deck. Think porch is non-original; believe original porch wrapped to the side because there is an entrance door on the left. Small, one-story, hip roof, projecting bay on the left. Entrance door has a divided transom and divided sidelights. One-story, shed roof wing on right with pier foundation. One-story, hip roof, enclosed, entrance porch on the rear. Rock-faced concrete block foundation. 4 X 2 bays. Colonial Revival style.

1 not-eligible building (NE)

**192A.**

date: Ca. 1915

description: One-story, end gable, cellar house. Roll roofing. Clapboard siding. Stone pier and rock-faced concrete block foundation. 1 X 1 bays.

1 not-eligible building (NE)

**192B.**

date: Ca. 1950

description: One-story, end gable outbuilding. Metal roof. Concrete block façade and foundation. 2 X 2 bays.

1 not-eligible building (NE)

**192C.**

date: Ca. 1985

description: Trailer.

1 not-eligible building (NE)

**192D.**

date: Ca. 1985

description: Trailer.

1 not-eligible building (NE)

**0193. SHAWS RUN ROAD/COUNTY ROUTE 33/1, residential**

HS-0622

**Williams House & Farm**

date: Ca. 1915

description: Large, two-story, hip roof house with two-story, gable, projecting bay on the front. Two, interior, corbelled brick chimneys. Asphalt shingle roof. Clapboard siding with frieze and corner boards with caps. Decorative shingles and a louver in front gable bay. 1/1 windows. One-story, hip roof, wraparound porch with square columns on a wood deck. One-story, hip roof wing on left. One-story, shed roof, enclosed, rear porch. Two-story, end gable, cellar house attached to wing on the side; cellar house has rock-faced concrete block and brick foundation. Concrete block foundation on porch. Cut stone foundation. 5 X 5 bays. Queen Anne style.

1 not-eligible building (NE)

**193A.**

date: Ca. 1940

description: Massive, four-story, gambrel roof barn. Metal roof. Concrete block façade and foundation. Garage on one end and on the side. 3 X 10 bays.

1 not-eligible building (NE)

**0194. SHAWS RUN ROAD/COUNTY ROUTE 33/1, residential**

HS-0623

**Huffman House & Farm**

date: Ca. 1925

description: Two-story, side gable house. Central, interior, brick chimney. "V" seam metal roof. Non-original, T-111 siding. 1/1 windows. One-story, modified hip roof, three-quarter length, front porch enclosed with T-111 siding and windows. One-story, gable, concrete block garage attached to house on the right, below grade. One-story, shed roof, rear porch that is partially enclosed with concrete block. Concrete block foundation. 3 X 1 bays. Central Passage house. Modified.

1 not-eligible building (NE)

**194A.**

date: Ca. 1925

description: One-story, end gable garage. Metal roof. Clapboard siding. Pier foundation. 1 X 2 bays.

1 not-eligible building (NE)

**194B.**

date: Ca. 1925

description: One-story, end gable outbuilding with shed roof wing on the right. Metal roof. Clapboard siding. Pier foundation. 3 X 2 bays.

1 not-eligible building (NE)

**194C.**

date: Ca. 1950

description: Two-story, shed roof outbuilding. Metal roof. Variety of siding. Pier foundation. 4 X 2 bays.

1 not-eligible building (NE)

**0195. JARVISVILLE ROAD/COUNTY ROUTE 31, residential**

HS-0624

**Keogh House/Laurel Run School**

date: Ca. 1900

description: Small, two-story, side gable with one-story, end gable, projecting, entrance portico. Portico has partial return cornice, decorative shingles, fanlight with keystone and is supported by modern Doric posts and a dentiled entablature. Exposed, brick chimney. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows. Breezeway on side attaches to a one-story, gable addition. One-story, shed roof, rear porch with Doric posts on a concrete block and brick deck. Cut stone and concrete block foundation. 6 X 2 bays. Classical Revival style. Modified.

1 not-eligible building (NE)

**195A.**

date: Ca. 1980

description: One-story, shed roof outbuilding with shed roof wing for firewood.

Fiberglass roof. Vertical board siding. Pier foundation. 3 X 1 bays.

1 not-eligible building (NE)

**0196. WOLFPEN RUN ROAD/COUNTY ROUTE 31/2, residential**

HS-0625

**Marple/Barnett House & Farm**

date: Ca. 1860

description: Small, two-story, side gable house. Corrugated metal roof. Central, interior, stone chimney. Asphalt shingle, weatherboard and T-111 siding. 6/6 and 1/1 windows. One-story, shed roof, full length, front porch with chamfered posts. Far right end of porch has been enclosed for a bathroom. Stone pier and concrete block foundation. 4 X 1 bays. Single-Pen house. Mortise and tenon construction.

1 not-eligible building (NE)

**196A.**

date: Ca. 1980

description: One-story, shed roof outbuilding. Metal roof. Vertical board siding. Concrete block pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**196B.**

date: Ca. 1940

description: One-story, end gable, corn crib. Metal roof. Board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**196C.**

date: Ca. 1940

description: One-story, end gable, well house. Metal roof. Concrete block façade and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**196D.**

date: Ca. 1940

description: One-story, end gable outbuilding. Metal roof. Concrete block façade and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**196E.**

date: Ca. 1940

description: One-story, shed roof outbuilding. Metal roof. Horizontal board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**196F.**

date: Ca. 1940

description: Two-story, end gable barn with flanking, shed roof wings. Metal roof. Vertical board siding. Pier foundation. 3 X 3 bays.

1 not-eligible building (NE)

**0197. WOLFPEN RUN ROAD/COUNTY ROUTE 31/2, residential**

HS-0626

**Myers/Matheny House & Farm**

date: Ca. 1890

description: Two-story, front facing "T" house; the left side of the front "T" has been enclosed for two stories with modern board and batten siding. Two, interior, brick chimneys. Decorative shingles in the gable end. Slate and metal roof. Clapboard siding with frieze and corner boards. Modern 1/1 windows. One-story, gable addition on the right with a front porch with square posts and slatted balustrade. One-story, shed roof, rear porch with modern square posts on an enclosed balustrade – non-original. Stone foundation. 3 X 2 bays. "T" house. Modified.

1 not-eligible building (NE)

**197A.**

date: Ca. 1990

description: One-story, end gable barn with shed roof, open wing on right. Metal roof. Board and batten siding. Pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**197B.**

date: Ca. 1910

description: Two-story, end gable, cellar house. Metal roof. Horizontal wood siding on the second floor; cut stone on first floor and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**197C.**

date: Ca. 1990

description: One-story, end gable outbuilding/tool shed. Asphalt shingle roof. Vertical board siding. Concrete foundation.

1 not-eligible building (NE)

**197D.**

date: Ca. 1990

description: Two-story, side gable barn with shed roof wing. Roll roofing. Plywood siding. Pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**0198. LICK RUN ROAD/COUNTY ROUTE 31/1, residential**

HS-0627

date: Ca. 1920

description: One-story, side gable house with two-story, gable addition on the left of the house. Asphalt shingle roof. Central, interior, brick chimney. Original house has German siding; addition has vinyl siding. Original house has novelty windows; addition has 1/1 windows. One-story, shed roof, enclosed, front porch. One-story, shed roof wing on the right that attaches to a one and one-half-story addition on the rear. One-story, shed roof, full length, partially enclosed, rear porch. Concrete block foundation. 3 X 5 bays. Gable-front house. Very modified.

1 not-eligible building (NE)

**198A.**

date: Ca. 1990

description: One-story, shed roof outbuilding. Metal roof. Plywood siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**198B.**

date: Ca. 1950

description: One-story, shed roof outhouse. Metal roof. Horizontal board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**198C.**

date: Ca. 1940

description: Two-story, end gable barn. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0199. JARVISVILLE ROAD/COUNTY ROUTE 31, residential**

HS-0628

**Portillo House & Farm**

date: Ca. 1925

description: One-story, hip roof house. Two, interior, brick chimney. Asphalt shingle roof. Vinyl siding. Modern 6/6 and 1/1 windows. Small, entrance porch with fluted, square posts on a concrete deck. Small, shed roof porch on the side with sliding glass doors and modern square posts and slatted balustrade. Shed roof, enclosed rear porch. Gable wing attached to rear porch and has concrete block foundation. Rock-faced concrete block foundation. 2 X 4 bays. Bungalow style. Modified.

1 not-eligible building (NE)

**199A.**

date: Ca. 1925

description: Two-story, end gable, cellar house. Corrugated metal roof. Clapboard siding on second floor; rock-faced concrete block first floor and foundation. Original, 6/6 windows. 1 X 2 bays.

1 not-eligible building (NE)

**199B.**

date: Ca. 1940

description: One-story, shed roof outbuilding. Metal roof. Horizontal board siding. 1 X 1 bays.

1 not-eligible building (NE)

**199C.**

date: Ca. 1940

description: Two-story, side gable barn. Metal roof. Vertical board siding. Pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**199D.**

date: Ca. 1940

description: Small, one-story, end gable garage. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0200. BUFFALO CREEK ROAD/COUNTY ROUTE 32, residential      HS-0629**  
**Deverick House & Farm**

date: Ca. 1875

description: Two-story, front facing "L" house. Central, interior, brick chimney. Metal roof. Clapboard siding. Vertical 2/2 windows. One-story, hip roof, three-quarter length, front porch with slightly battered square posts on an enclosed balustrade. Rear wing originally had a two-story, open porch but the first floor is now enclosed; second floor is partially enclosed. Stone pier foundation. 3 X 4 bays. "I" house.

1 not-eligible building (NE)

**200A.**

date: Ca. 1870

description: Two-story, end gable, cellar house. Metal roof. Board and batten siding on second floor; cut stone first floor and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**200B.**

date: Ca. 1920

description: One-story, end gable outbuilding. Metal roof. German siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**200C.**

date: Ca. 1920

description: Large, two-story, end gable barn with forebay and large, shed roof wings on the sides and on the rear. Metal roof. Board and batten and vertical board siding. Stone pier foundation. 5 X 2 bays.

1 not-eligible building (NE)

**200D.**

date: Ca. 1920

description: One-story, end gable garage/barn. Metal roof. Board and batten siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0201. BUFFALO CREEK ROAD/COUNTY ROUTE 32, residential      HS-0630**  
**Webb House**

date: Ca. 1860

description: Two-story, side gable with one and one-half-story, gable wing on the rear. Asphalt shingle roof. Partial return cornice. Aluminum siding on the front; asphalt shingle siding elsewhere. Novelty and 6/6 windows. One-story, hip roof, three-quarter length, front porch with turned posts on a wood deck. Entrance door has infilled transom and glazed and paneled sidelights. Cut stone foundation. 5 X 4 bays. "I" house.

1 not-eligible building (NE)

**201A.**

date: Ca. 1990

description: One and one-half-story, shop building. Metal roof. Metal siding. Concrete foundation. 2 X 1 bays.

1 not-eligible building (NE)

**201B.**

date: Ca. 1930

description: One-story, side gable outbuilding. Metal roof. Board and batten siding. Pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**201C.**

date: Ca. 1890

description: Two-story, end gable, cellar house. Roll roofing. Asbestos shingle siding over vertical board siding on second floor; cut stone first floor and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0202. BUFFALO CREEK ROAD/COUNTY TOUTE 32, residential**

HS-0631

**Riley House & Farm**

date: Ca. 1880

description: Large, two-story, side facing "T" house. Three, interior, corbelled brick chimneys. Asphalt shingle roof. Painted brick façade. Vertical 2/2 windows with segmental arches; the arches have been infilled. Decorative frieze board with applied florettes and scrolled brackets. Two-story, shed roof, front porch with turned posts, cut-out balustrade, scrolled brackets and decorative vergeboard on both floors. Modern, one-story, hip roof wing on rear with asphalt shingle roof, vinyl siding, 1/1 windows and concrete block foundation and entrance deck with sliding glass doors. Front and side bay is a three-sided, projecting bay. Gable wing on the rear has a two-story, open porch with slightly chamfered posts, cut-out balustrade and scrolled brackets. Stone foundation. 3 X 4 bays. Italianate style.

1 building eligible to the National Register (CE)

**202A.**

date: Ca. 1900

description: Large, two-story, end gable barn with shed roof wing on the left and on the rear. Shed roof wing attached to rear wing and is open. Metal roof. Board and batten and vertical board siding. Pier foundation. 3 X 1 bays.

1 building eligible to the National Register (CE)

**202B.**

date: Ca. 1945

description: One-story, hip roof garage. Asphalt shingle roof. Concrete block façade and foundation. Metal casement windows. 2 X 2 bays.

1 building eligible to the National Register (CE)

**202C.**

date: Ca. 1900

description: One-story, side gable outbuilding. Interior, stone chimney. Asphalt shingle roof. Board and batten siding. 2 X 1 bays.

1 building eligible to the National Register (CE)

**202D.**

date: Ca. 1900

description: Two-story, end gable, cellar house. Asphalt shingle roof. Weatherboard siding on second floor; cut stone first floor and foundation. 1 X 1 bays.

1 building eligible to the National Register (CE)

**202E.**

date: Ca. 1990

description: "Mother-in-law house." One-story, end gable house. Asphalt shingle roof. Vinyl siding. Concrete foundation. 2 X 4 bays.

1 not-eligible building (NE)

**0203. BUFFALO CREEK ROAD/COUNTY ROUTE 32, residential**

HS-0632

**Cork House**

date: Ca. 1870

description: Two-story, side gable house with one-story, shed roof wing on the rear. Two, interior, end, stone chimneys. Asphalt shingle roof. Partial return cornice. Asbestos shingle siding. 1/1 and 6/1 windows. Small, one-story, hip roof, entrance porch with two pairs of square posts on a concrete deck with concrete block foundation. Entrance door has divided transom and divided sidelights with simple surround with flanking brackets. Stone foundation; rear wing has concrete foundation.. 5 X 2 bays. "T" house.

1 not-eligible building (NE)

**203A.**

date: Ca. 1940

description: Two-story, end gable barn with shed roof, enclosed wing on the left. Metal roof. Vertical board siding. Pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**203B.**

date: Ca. 1885

description: Two-story, side gable, cellar house. Asphalt shingle roof. German siding on second floor; cut stone on first floor and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0204. US ROUTE 19, residential**

**Snyder House**

HS-0633

date: Ca. 1900

description: Two-story, front facing "L" house. Interior, corbelled brick chimney. Asphalt shingle roof. Metal board and batten and aluminum siding. Variety of window types. One-story, hip roof, entrance porch with wrought iron posts on a concrete deck. One-story, shed roof, side porch with square posts on a concrete deck. Foundation covered. 3 X 3 bays. Gabled-ell house. Modified.

1 not-eligible building (NE)

**204A.**

date: Ca. 1950

description: Two-story, end gable garage. Asphalt shingle roof. German siding on the second floor; rubble stone first floor and foundation. 1/1 windows. 2 X 2 bays.

1 not-eligible building (NE)

**204B.**

date: Ca. 1950

description: One-story, end gable outbuilding. Metal roof. Concrete block façade and foundation. 2 X 5 bays.

1 not-eligible building (NE)

**204C.**

date: Ca. 1950

description: One-story, side gable outbuilding. Metal roof. Rubble stone façade and foundation. 3 X 1 bays.

1 not-eligible building (NE)

**204D.**

date: Ca. 1950

description: One-story, end gable barn with shed roof wing on the side and the front. Metal roof. Vertical board siding. Pier foundation. 4 X 1 bays.

1 not-eligible building (NE)

**204E.**

date: Ca. 1950

description: One-story, shed roof garage. Metal roof. Rubble stone façade and foundation. Partially below grade. 3 X 1 bays.

1 not-eligible building (NE)

**2025. ISAACS CREEK ROAD/COUNTY ROUTE 38, residential**

HS-0634

**Post House & Farm**

date: Ca. 1950

description: One-story, cross gable house. Asphalt shingle roof. Asbestos shingle siding. Modern 1/1 windows. Small, projecting, end gable portico on the side supported by wrought iron posts. Sliding glass doors on side porch. Two-story, end gable garage/cellar house attached on the rear. Small, recessed, entrance porch on the front with wrought iron post. Concrete block foundation. 3 X 5 bays. Minimal Traditional style.

1 not-eligible building (NE)

**205A.**

date: Ca. 1942

description: Large, two-story, gambrel roof barn with projecting wing on the side. Metal roof. Board and batten siding. Pier foundation. 3 X 3 bays.

1 not-eligible building (NE)

**205B.**

date: Ca. 1990

description: One-story, end gable garage. Asphalt shingle roof. Concrete block façade and foundation. 2 X 2 bays.

1 not-eligible building (NE)

**205C.**

date: Ca. 1950

description: One-story, end gable outbuilding with several, shed roof wings attached. Corrugated metal roof. Asbestos shingle siding. Pier foundation. 1 X 4 bays.

1 not-eligible building (NE)

**205D.**

date: Ca. 1990

description: Trailer.

1 not-eligible building (NE)

**0206. ISAACS CREEK ROAD/COUNTY ROUTE 38, residential**

HS-0635

**Rapking House/Post House & Farm**

date: 1892

description: Large, two-story, hip roof house with gable bays and a large, two-story gable wing on the rear. Second floor of the rear wing is ca. 2004 and it was enlarged. Asphalt shingle roof imitates slate which the house had originally. Vinyl siding. 1/1 windows. Fishscale shingles, decorative vergeboard and scrolled brackets in gable ends. Two-story, entrance porch with decorative frieze board, cut-out and scrolled brackets, Eastlake vergeboard, chamfered posts and cut-out balustrade. Cut stone foundation. 4 X 5 bays. Folk Victorian style. Modified.

1 not-eligible building (NE)

**206A.**

date: Ca. 1892

description: Two-story, side gable, cellar house with shed roof, garage bay on the rear and shed roof wing on the left. Onduline roofing. Board and batten siding on the second floor; cut stone facade and foundation first floor. Partially below grade.

1 not-eligible building (NE)

**206B.**

date: Ca. 2003

description: One-story, end gable garage with open, shed roof wing on the left. Asphalt shingle roof. Vinyl siding. Concrete block foundation. 2 X 1 bays.

1 not-eligible building (NE)

**206C.**

date: Ca. 1900

description: One-story, end gable barn with shed roof wing on the right. Metal roof. Vertical board siding. Stone and stone pier foundation. 5 X 1 bays.

1 not-eligible building (NE)

**206D.**

date: Ca. 1940

description: Two-story, end gable outbuilding. Metal roof. Asbestos shingle siding on second floor; terra cotta block first floor and foundation. Four pane windows. 5 X 3 bays.

1 not-eligible building (NE)

**206E.**

date: Ca. 1940

description: Two-story, end gable barn with shed roof, open wing on the right and shed roof wing on left of terra cotta block. Corrugated metal roof. Board and batten and vertical board siding. Stone foundation. 4 X 2 bays.

1 not-eligible building (NE)

**206F.**

date: Ca. 1942

description: Large, two and one-half-story, gambrel roof, dairy barn with forebay and enclosed, one-story, shed roof, concrete block wing on the front and attached to that is a hip roof wing of terra cotta block and two terra cotta block silos. Large, gable wing also attached to front of barn with German siding and terra cotta block. Large, shed roof, machine shed/hay storage barn attached on the rear. "V" seam metal roof. German siding on the second floor; terra cotta block first floor and foundation.

1 not-eligible building (NE)

**206G.**

date: Ca. 1990

description: One-story, side gable, machine shed. "V" seam metal roof. Metal siding. Pier foundation. 3 X 1 bays.

1 not-eligible building (NE)

**0207. ISAACS CREEK ROAD/COUNTY ROUTE 38, residential                      HS-0636**  
**Metheny House/McConkey/Rosco Washburn/Cole House**

date: Ca. 1860

description: Two-story, side gable house with small, one-story, gable wing on the rear with shed roof wing attached. Asphalt shingle roof. Central, interior, corbelled brick chimney. Partial return cornice. Asbestos shingle siding. Variety of windows. One-story, hip roof, three-quarter length, front porch with battered square posts on an enclosed balustrade. Stone and rock-faced concrete block foundation. 4 X 2 bays. "I" house.

1 not-eligible building (NE)

**207A.**

date: Ca. 1925

description: One-story, end gable garage. Roll roofing. Rock-faced concrete block façade and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**207B.**

date: Ca. 1940

description: One-story, end gable, cellar house. Was most likely two-story originally. Roll roofing. Terra cotta block façade and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0208. ISAACS CREEK ROAD/COUNTY ROUTE 38, residential                      HS-0637**  
**Butcher House**

date: Ca. 1885

description: Large, two-story, front facing "L" house. Asphalt shingle roof. Central, cut stone chimney has been removed from the roofline up. Modern, exposed, concrete block chimney on the side. Shingles in the gable ends. Modern clapboard siding. Modern 1/1 windows. One-story, hip roof, three-sided, projecting bay on the front. One-story, hip roof, wraparound porch with square posts and spindled balustrade – modern components. Shed roof, rear porch enclosed and enlarged. Modern deck on the rear. Non-original, two-story, hip roof, open porch on the rear. Stone pier foundation infilled with concrete block. 3 X 3 bays. Gabled-ell house. Modified.

1 not-eligible building (NE)

**208A.**

date: Ca. 1995

description: One-story, gambrel roofed garage. Asphalt shingle roof. Concrete block façade and foundation. 3 X 1 bays.

1 not-eligible building (NE)

**208B.**

date: Ca. 1885

description: Two-story, end gable, cellar house with forebay. Metal roof. Vertical board siding on the second floor; cut stone first floor and foundation. 1 X 1 bays. Somewhat deteriorated.

1 not-eligible building (NE)

**208C.**

date: Ca. 1920

description: One-story, end gable barn. Metal roof. Vertical board and board and batten siding. Pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**0209. ISAACS CREEK ROAD/COUNTY ROUTE 38, residential      HS-0638  
Gaines/Sommerville/Thrash House & Farm**

date: Ca. 1890

description: Large, two-story, side gable house with one-story, gable wing on the rear. Asphalt shingle roof. Scrolled, corner brackets. Interior, end, stone chimney. Vinyl siding. Modern 9/9 windows with shutters. One-story, shed roof, entrance porch with square brick columns on an enclosed brick balustrade with concrete cap. Entrance door has divided transom and glazed and paneled sidelights. One-story, full length, rear porch fully enclosed and attaches to two-story, gable, original cellar house. Attached to the cellar house is a modern, one-story, shed roof, open porch with square posts on a concrete balustrade. Cellar house has vinyl siding on second floor and terra cotta block first floor and foundation. Stone foundation. 5 X 5 bays. "I" house. Modified.

1 not-eligible building (NE)

**209A.**

date: Ca. 1890

description: Large, two-story, end gable barn with two roof monitors. Metal roof. Vertical board siding. Pier foundation. 3 X 1 bays.

1 not-eligible building (NE)

**209B.**

date: Ca. 1950

description: One-story, end gable outbuilding. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**209C.**

date: Ca. 1890

description: Tall, one and one-half-story, end gable outbuilding. Metal roof. Board and batten siding. Stone foundation. 1 X 1 bays.

1 not-eligible building (NE)

**209D.**

date: Ca. 1890

description: One-story, end gable, corn crib. Metal roof. Horizontal board siding. Stone pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**209E.**

date: Ca. 1890

description: Tall, one and one-half-story granary. "V" seam metal roof. Vertical board and lattice siding. Stone pier, concrete block pier and wood pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**209F.**

date: Ca. 1940

description: One-story, end gable outbuilding attached to one-story, end gable wing. Metal roof. Board and batten siding. Pier foundation. 3 X 4 bays.

1 not-eligible building (NE)

**209G.**

date: Ca. 1995

description: One-story, shed roof outbuilding. Asphalt shingle roof. Plywood siding. Concrete block pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**209H.**

date: Ca. 1995

description: One-story, shed roof, chicken coop. Metal roof. Metal siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0210. ISAACS CREEK ROAD/COUNTY ROUTE 38, residential  
Hurst House & Farm/Flying H Ranch/McGahan/Curry House & Farm**

HS-0639

date: Ca. 1880

description: Two-story, hip roof house with two-story gable bays. One-story, gable wing on the left of concrete block. Central, interior, stone chimney. Slate roof. Fishscale shingles in the gable ends. Scrolled corner brackets. German siding with frieze and corner boards. Vertical 2/2 windows. Original front porch is fully enclosed and has been enlarged and enclosed with plywood siding and modern windows. There was also originally a two-story, corner entrance but this has been incorporated into the main body of the house. One-story, shed roof, rear porch with modern square posts on a modern deck. Stone pier foundation. 2 X 2 bays. "T" house. Modified.

1 not-eligible building (NE)

**210A.**

date: Ca. 1880

description: One-story, end gable granary with flanking, shed roof wings. Metal roof. Vertical board siding. Pier foundation. 3 X 1 bays.

1 not-eligible building (NE)

**210B.**

date: Ca. 1960

description: One-story, side gable barn/chicken coop. Metal roof. Vertical board siding. Pier foundation. 1 X 2 bays.

1 not-eligible building (NE)

**210C.**

date: Ca. 1990

description: One-story, shed roof, machine shed. Metal roof. Metal siding. Wood pier foundation. 4 X 1 bays.

1 not-eligible building (NE)

**210D.**

date: Ca. 1880

description: Large, two-story, side gable barn. Metal roof. Log framing covered with board and batten siding. Stone pier foundation. 3 X 2 bays.

1 not-eligible building (NE)

**210E.**

date: Ca. 1960

description: One-story, shed roof, chicken coop. Metal roof. Vertical board siding. Pier foundation. 3 X 1 bays.

1 not-eligible building (NE)

**0211. ISAACS CREEK ROAD/COUNTY ROUTE 38, residential**

HS-0640

**Bowyer House & Farm**

date: Ca. 1870

description: One and one-half-story, end gable house. Metal roof. German siding. Vertical 3/1 and 1/1 windows. One-story, end gable, entrance portico with battered square posts on a wood deck with concrete block foundation. One-story, shed roof, side porch with square posts and wrought iron railings. Concrete block foundation. 3 X 4 bays. Bungalow style.

1 not-eligible building (NE)

**211A.**

date: Ca. 2000

description: Tall, one-story, end gable barn. Metal roof. Metal siding. Concrete foundation. 1 X 1 bays.

1 not-eligible building (NE)

**211B.**

date: Ca. 1990

description: One-story, end gable outbuilding with shed roof wing on left. Metal roof. Metal and horizontal board siding. 2 X 1 bays.

1 not-eligible building (NE)

**211C.**

date: Ca. 1930

description: One-story, end gable, corn crib. Metal roof. Lattice and vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**211D.**

date: Ca. 1930

description: One and one-half-story, shed roof, hay storage barn. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0212. ISAACS CREEK ROAD/COUNTY ROUTE 38, residential**

HS-0641

**Sears House**

date: Ca. 1875

description: Two-story, rear facing "L" house. Metal roof. Original, exposed, stone chimney has been removed. Asphalt shingle siding on the front and rear; elsewhere is clapboard siding over logs. Vertical 2/2, 6/6 and 1/1 windows. Front porch is gone. Rear wing has shed roof porch with square posts on a concrete deck. Stone pier foundation. 3 X 4 bays. "T" house.

1 not-eligible building (NE)

**212A.**

date: Ca. 1950

description: One-story, shed roof outbuilding. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**212B.**

date: Ca. 1950

description: One-story, end gable outbuilding. Metal roof. Vertical board siding. 1 X 1 bays.

1 not-eligible building (NE)

**212C.**

date: Ca. 1950

description: One-story, end gable garage with partially collapsed shed roof wing on the left. Metal roof. Vertical board and board and batten siding. Stone pier foundation. 2 X 1 bays. Deteriorated.

1 not-eligible building (NE)

**212D.**

date: Ca. 1950

description: One-story, gambrel roof barn with shed roof wing on the right. Metal roof. Vertical board siding. Stone pier foundation. 3 X 1 bays.

1 not-eligible building (NE)

**0213. TWO LICK RUN ROAD/COUNTY ROUTE 19/18, residential  
McDougal/Law House and Farm**

HS-0642

date: Ca. 1840

description: Two-story, front facing "L" house. "V" seam metal roof. Originally there were two, interior, stone chimneys; these have been removed. Currently, there is an interior, brick chimney. Vinyl siding. Vertical 2/2 windows. Original front door removed and replaced with a picture window with a metal canopy. One-story, shed roof, full length, enclosed rear porch. Small breezeway attaches house to a two-story, end gable, cellar house and attached to that is a one-story, hip roof, one bay garage. Garage has a metal roof and terra cotta block façade and foundation. Brick and stone foundation. 4 X 2 bays. Queen Anne Cottage style. Modified.

1 not-eligible building (NE)

**213A.**

date: Ca. 1850

description: Large, two-story, end gable barn with flanking, shed roof, enclosed wings. Metal roof. Vertical board siding. Stone pier infilled with concrete block foundation. 4 X 3 bays.

1 not-eligible building (NE)

**213B.**

date: Ca. 1915

description: Two, concrete silos attached to the front of the barn. They are built like large barrels with wooden staves, etc.

1 not-eligible building (NE)

**213C.**

date: Ca. 1940

description: One-story, shed roof outbuilding. Metal roof. Metal and vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**213D.**

date: Ca. 1940

description: Two-story, barrel roof barn. Metal roof. Vertical board siding. Stone pier foundation. 2 X 2 bays.

1 not-eligible building (NE)

**213E.**

date: Ca. 1940

description: One-story, shed roof outbuilding. Metal roof. Vertical board siding. Stone pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0214. TWO LICK RUN ROAD/COUNTY ROUTE 19/18, residential  
Stutler House**

HS-0643

date: Ca. 1890

description: Large, two-story, rear facing "L" house with rear wing one-story. Corrugated metal roof. Original chimney(s) have been removed. Vinyl siding. 6/6, 1/1 and 3/1 windows. Two-story, hip roof, enclosed, front porch. Rear porch on one-story wing

enclosed. Stone pier foundation infilled with concrete block. 5 X 4 bays. "I" house. Modified.

1 not-eligible building (NE)

**214A.**

date: Ca. 1890

description: Large, two-story, end gable barn with forebay. Asphalt shingle roof. German siding. Stone pier foundation. 3 X 5 bays.

1 not-eligible building (NE)

**214B.**

date: Ca. 1940

description: One-story, end gable outbuilding. Metal roof. Asphalt shingle siding over vertical board siding. Vertical 3/1 windows. Stone pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**214C.**

date: Ca. 1940

description: One-story, end gable garage. Metal roof. Concrete block façade and foundation. 1 X 3 bays.

1 not-eligible building (NE)

**214D.**

date: Ca. 1945

description: One-story, barrel roof, chicken coop. Metal roof. Terra cotta block façade and foundation. Metal casement windows. 2 X 2 bays.

1 not-eligible building (NE)

**214E.**

date: Ca. 1940

description: One and one-half-story, end gable barn with flanking, shed roof wings. Metal roof. Board and batten siding. Pier foundation. 3 X 1 bays.

1 not-eligible building (NE)

**214F.**

date: Ca. 1940

description: One-story, end gable, corn crib. Metal roof. Board and batten siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**214G.**

date: Ca. 1940

description: One-story, shed roof, corn crib. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**214H.**

date: Ca. 1960

description: Large, tall, one-story, shed roof, machine shed/barn. Metal roof. Metal siding. Metal casement windows. Pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**214I.**

date: Ca. 1945

description: One-story, side gable outbuilding. Metal roof. Terra cotta block façade and foundation. 2 X 1 bays.

1 not-eligible building (NE)

**214J.**

date: Ca. 1940

description: One-story, shed roof outbuilding. Metal roof. Board and batten siding. Stone foundation. 1 X 1 bays.

1 not-eligible building (NE)

**214K.**

date: Ca. 1980

description: Two-story, end gable barn with concrete silo attached on the rear. "V" seam metal roof. Vertical board siding. Concrete block foundation. 2 X 1 bays.

1 not-eligible building (NE)

**215. TWO LICK RUN ROAD/COUNTY ROUTE 19/18, residential**

**Allman House/James Law House & Farm**

HS-0644

date: Ca. 1890/Ca. 1945

description: Large, two-story, rear facing "L" house with a breezeway on the left that attaches to a two-story, gable addition. Asphalt shingle roof. Weatherboard siding. Addition has stucco façade over terra cotta block. Three garage bays on front of addition. Modern 1/1 windows. One-story, shed roof, enclosed porch on side with two sets of sliding glass doors. Cut stone foundation. 7 X 3 bays. "I" house. Modified.

1 not-eligible building (NE)

**215A.**

date: Ca. 1915

description: One-story, end gable outbuilding. Metal roof. Clapboard siding. Stone pier foundation. 6/6 windows. 1 X 2 bays.

1 not-eligible building (NE)

**215B.**

date: Ca. 1945

description: One-story, side gable, milking parlor. "V" seam metal roof. Terra cotta block façade and foundation. 3 X 1 bays.

1 not-eligible building (NE)

**215C.**

date: Ca. 1925

description: Large, two-story, end gable barn with flanking, two-story wings. Metal roof. Clapboard siding on second floor; concrete block first floor and foundation. Forebay and two roof monitors. Two-story, gable wing on the rear with vertical board siding on the second floor; first floor is terra cotta block. 5 X 8 bays. Silo to the right of the barn.

1 not-eligible building (NE)

**215D.**

date: Ca. 1995

description: Large, one-story machine shed. Metal roof. Concrete block back wall; open on the front. Supports are metal beams and posts. 4 X 1 bays.

1 not-eligible building (NE)

**215E.**

date: Ca. 1935

description: One-story, side gable machine shed. Metal roof. Vertical board siding and concrete block façade. 4 X 1 bays.

1 not-eligible building (NE)

**215F.**

date: Ca. 1890

description: One-story, end gable, cellar house partially below grade. Metal roof. Cut stone façade and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**215G.**

date: Ca. 1945

description: Large, two-story, gambrel roof barn with forebay. One-story, shed roof wing on the right. Metal roof. Vertical board siding. Concrete block foundation. 3 X 1 bays. Metal silo on the rear.

1 not-eligible building (NE)

**215H.**

date: Ca. 2003

description: One-story, shed roof outbuilding. Roll roofing. Horizontal board siding. Concrete block pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0216. TWO LICK RUN ROAD/COUNTY ROUTE 19/18, residential**

**RoseMary Allman House**

HS-0645

date: Ca. 1885

description: Two-story, rear facing "L" house with rear wing one-story. Chimneys have been removed. Asphalt shingle roof. Vinyl siding. Modern and original 6/6 windows. One-story, shed roof, full length, front porch partially enclosed on the right; open portion has non-original square columns on a concrete deck. One-story, shed roof, rear porch with round metal posts on a terra cotta block foundation. One-story, gable breezeway attaches to a one-story, side gable, two bay garage with laundry room. Stone pier infilled with various other materials foundation. 4 X 3 bays. "I" house. Modified.

1 not-eligible building (NE)

**216A.**

date: Ca. 1900

description: One-story, end gable barn. Metal roof. Board and batten siding. Stone pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0217. TWO LICK RUN ROAD/COUNTY ROUTE 19/18, residential**

**McDonald Farm**

HS-0646

date: Ca. 1885

description: Large, two-story, rear facing "L" house. Two, interior, corbelled brick chimneys. "V" seam and corrugated metal roof. Clapboard siding. 1/1 and vertical 2/2 windows with simple surrounds and hoods with decorative corner blocks. Two-story,

shed roof, full length, front porch: each end of the porch has been enclosed; the second floor has chamfered posts and cut-out balustrade; the first floor has wrought iron posts on a concrete deck. Two-story, shed roof, enclosed, rear porch. Small, shed roof, rear, entrance porch with square posts and slatted balustrade. Attached on the rear is a two-story, gable, cellar house. One-story, shed roof, partially enclosed, side porch. Stone foundation. 6 X 4 bays. Folk Victorian style.

1 building eligible to the National Register (CE)

**217A.**

date: Ca. 1900

description: Three-story, end gable barn with forebay. Metal roof. Vertical board and board and batten siding. Shed roof wing on the left. Stone pier foundation. 2 X 1 bays.

1 building eligible to the National Register (CE)

**217B.**

date: Ca. 1940

description: Two-story, end gable barn with enclosed, shed roof wing on the left. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 building eligible to the National Register (CE)

**217C.**

date: Ca. 1900

description: Two-story, end gable, sheep barn with shed roof, enclosed wing on the left. Metal roof. Vertical board siding. Pier foundation. 2 X 1 bays. Somewhat deteriorated.

1 building eligible to the National Register (CE)

**217D.**

date: Ca. 1900

description: One-story, long, end gable outbuilding. Metal roof. Clapboard siding. Pier foundation. 2 X 2 bays.

1 building eligible to the National Register (CE)

**217E.**

date: Ca. 1945

description: One-story, shed roof garage. Metal roof. Terra cotta block façade and foundation. 2 X 1 bays.

1 building eligible to the National Register (CE)

**217F.**

date: Ca. 1975

description: One-story, end gable garage. Metal roof. Concrete block façade and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**217G.**

date: Ca. 1885

description: One and one-half-story, side gable, cellar house with forebay. Slate roof. Clapboard siding. Vertical 2/2 windows with simple surrounds and hoods with decorative corner blocks. Stone foundation. 2 X 2 bays.

1 building eligible to the National Register (CE)

**217H.**

date: Ca. 1885

description: Two-story, side gable barn with concrete silo on the rear. Slate roof. Clapboard siding. Vertical 2/2 windows with simple surrounds and hoods with decorative corner blocks. Stone foundation. 4 X 2 bays.

1 building eligible to the National Register (CE)

**217I.**

date: Ca. 1945

description: One-story, end gable outbuilding. Metal roof. Vertical board and board and batten siding. Pier foundation. 1 X 1 bays.

1 building eligible to the National Register (CE)

**0218. CAMPBELL RUN ROAD/COUNTY ROUTE 38/2, residential**

HS-0647

**Exline House**

date: Ca. 1912

description: Large, two-story, hip roof house with gable bays. Two, interior, corbelled brick chimney. Asphalt shingle roof. Decorative louver with hood in gable end. Clapboard siding. 1/1 windows with simple surrounds and hoods. One-story, shed roof, front porch with non-original square posts on a wood deck; porch wraps around the side and has hip roof. One-story, shed roof, rear porch with square posts on a wood deck. Stone pier foundation covered with metal veneer. 4 X 3 bays. "I" house.

1 not-eligible building (NE)

**218A.**

date: Ca. 1900

description: Two-story, end gable barn. Metal roof. Board and batten siding. Stone pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**218B.**

date: Ca. 1900

description: Two-story, end gable barn with forebay with shed roof wing on left that is partially enclosed. Enclosed, shed roof wing on rear. Metal roof. Vertical board siding. Stone pier foundation. 2 X 5 bays.

1 not-eligible building (NE)

**218C.**

date: Ca. 1900

description: Two-story, end gable barn with large forebay. Corrugated metal roof. Board and batten siding. Pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**218D.**

date: Ca. 1900

description: Two-story, end gable, cellar house. Enclosed, shed roof wing on rear. Corrugated metal roof. Clapboard siding on second floor; cut stone first floor and foundation. Vertical 2/2 windows. 1 X 1 bays.

1 not-eligible building (NE)

**219. CAMPBELL RUN ROAD/COUNTY ROUTE 38/2, residential  
Gabriel/McDonald House & Farm**

HS-0648

date: Ca. 1920

description: Two-story, end gable house. Central, interior, brick chimney. Knee braces in gable end. Corrugated metal roof. German siding with corner boards. Vertical 4/1, 3/1 and 1/1 windows with simple surrounds and hoods. One-story, hip roof, three-quarter length, front porch with slightly battered and paneled square posts on brick piers with concrete caps. Rock-faced concrete block foundation. 4 X 3 bays. Bungalow style.

1 not-eligible building (NE)

**219A.**

date: Ca. 1920

description: Two-story, side gable, cellar house. "V" seam metal roof. Board and batten siding on second floor; rock-faced concrete block first floor and foundation.

1 not-eligible building (NE)

**219B.**

date: Ca. 1920

description: One-story, end gable, coal house. "V" seam metal roof. Board and batten and vertical board siding. 1 X 1 bays.

1 not-eligible building (NE)

**219C.**

date: Ca. 1870

description: One and one-half-story, rear facing "L" house. This was the original house on the property. Log structure. "V" seam metal roof. Board and batten siding. 6/6 windows. One-story, shed roof porch on the rear. Stone pier foundation. 4 X 1 bays.

Vacant and deteriorated.

1 not-eligible building (NE)

**219D.**

date: Ca. 1920

description: One-story, shed roof outbuilding. Metal roof. Vertical board and board and batten siding. Pier foundation. 2 X 1 bays. Deteriorated.

1 not-eligible building (NE)

**219E.**

date: Ca. 1945

description: One-story, shed roof, chicken coop. "V" seam metal roof. Terra cotta block façade and foundation. 3 X 1 bays. Partially collapsed.

1 not-eligible building (NE)

**219F.**

date: Ca. 1920

description: Two-story, gambrel roof barn with forebay and silo. Metal roof. Vertical board siding. Stone pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**219G.**

date: Ca. 1910

description: Large, two-story, end gable barn with forebay. Slate roof. Vertical board siding. Pier foundation. 1 X 2 bays.

1 not-eligible building (NE)

**219H.**

date: Ca. 1890

description: One-story, rear facing "L" house. "V" seam metal roof. Board and batten siding. Central, interior, brick chimney. One-story, shed roof porch on the rear with square posts. Vertical 2/2 windows. Stone pier foundation. 3 X 1 bays. Used as a barn. Deteriorated. Attached on the rear is a two-story, end gable, cellar house with forebay. Cellar house has metal roof, board and batten siding on second floor and cut stone first floor and foundation and is 1 X 1 bays.

1 not-eligible building (NE)

**219I.**

date: Ca. 1920

description: One-story, shed roof outbuilding. Metal roof. Vertical board and board and batten siding. Pier foundation. 2 X 1 bays. Partially collapsed.

1 not-eligible building (NE)

**219J.**

date: Ca. 1900

description: One-story, end gable, corn crib. Metal roof. Vertical board siding. Stone foundation. 1 X 1 bays.

1 not-eligible building (NE)

**219K.**

date: Ca. 1940

description: One-story, shed roof outhouse. Metal roof. Vertical board siding. Concrete foundation. 1 X 1 bays.

1 not-eligible building (NE)

**219L.**

date: Ca. 1920

description: One-story, shed roof, chicken coop. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**219M.**

date: Ca. 1920

description: Two-story, gambrel roof barn. One-story, gable roof, milking parlor on the front of concrete block. Metal roof. Vertical board and board and batten siding. Brick foundation. 1 X 6 bays.

1 not-eligible building (NE)

**219N.**

date: Ca. 1940

description: One-story, end gable garage. Metal roof. Vertical board siding. Stone pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**219O.**

date: Ca. 1920

description: One-story, shed roof outbuilding. Metal roof. Vertical board siding. Stone pier foundation. 1 X 1 bays. Deteriorated.

1 not-eligible building (NE)

**219P.**

date: Ca. 1990

description: Modular home.

1 not-eligible building (NE)

**219Q.**

date: Ca. 1900

description: Two-story, end gable barn with flanking, shed roof, enclosed wings.

Enclosed, shed roof wing on rear. Corrugated metal roof. Vertical board and board and batten siding. Pier foundation. 3 X 4 bays.

1 not-eligible building (NE)

**219R. SEE APPENDIX II**

**0220. CAMPBELL RUN ROAD/COUNTY ROUTE 38/2, residential**

HS-0649

**Hitt House & Farm**

date: Ca. 1880

description: Two-story, rear facing "L" house with rear wing one-story. "V" seam metal roof. Chimneys have been removed. Vinyl and clapboard siding. Modern 1/1 squat windows. Non-original, one-story, shed roof, entrance porch with modern square posts and modern slatted balustrade. Deck on front porch wraps around the side. One-story, gable wing on right with concrete block foundation. Breezeway/car port on rear attaches house to a two-story, end gable, cellar house with asphalt shingle siding on second floor and concrete block first floor and foundation. Concrete block foundation. 5 X 3 bays. "T" house. Modified.

1 not-eligible building (NE)

**220A.**

date: Ca. 1940

description: One-story, end gable barn. Metal roof. Vertical board siding. Concrete and brick foundation. 1 X 1 bays.

1 not-eligible building (NE)

**220B.**

date: Ca. 1900

description: One-story, shed roof garage/machine shed. Metal roof. Vertical board siding. Stone pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**220C.**

date: Ca. 1940

description: Large, two and one-half-story, gambrel roof barn with shed roof, enclosed wing on the front. Metal roof. Vertical board siding. Stone pier foundation. 1 X 3 bays.

1 not-eligible building (NE)

**220D.**

date: Ca. 1940

description: One-story, end gable outbuilding. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**220E.**

date: Ca. 1900

description: Large, two-story, end gable barn. Metal roof. Vertical board siding. Pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**0221. TWO LICK RUN ROAD/COUNTY ROUTE 19/18, residential**

HS-0650

**Gump/Ashcraft/Cole House & Farm**

date: Ca. 1892

description: Two-story, rear facing "L" house with rear wing one-story. Two-story, gable addition on right with exposed, brick chimney. Interior, stone, end chimney. Asphalt shingle and metal roof. Asbestos shingle siding over clapboard siding. 1/1 windows; paired on the front. Two-story, end gable, projecting, entrance portico: both floors have turned posts with spindled balustrades. Rear porch has been enclosed and incorporated into the house. Modern deck on rear. One-story, gable wing on rear with concrete block foundation. One-story, hip roof wing attached to addition. Stone pier infilled with concrete block foundation. 4 X 2 bays. "I" house.

1 not-eligible building (NE)

**221A.**

date: Ca. 1892

description: One-story, end gable, cellar house, below grade. Asphalt shingle roof. Cut stone façade and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**221B.**

date: Ca. 1895

description: One and one-half-story, side gable outbuilding. May have been Dr. Cole's office building. "V" seam metal roof. Horizontal board siding. Block pier foundation. 3 X 1 bays. The gable end siding has been removed and it is open for storage.

1 not-eligible building (NE)

**221C.**

date: Ca. 1980

description: Two-story, gambrel roof garage/residence. Asphalt shingle roof. Concrete block façade and foundation. Modern 1/1 windows. Garage bays on the front.

1 not-eligible building (NE)

**221D.**

date: Ca. 1980

description: One-story, shed roof outbuilding. Metal roof. Vertical board siding. Concrete foundation. 4 X 1 bays.

1 not-eligible building (NE)

**221E.**

date: Ca. 1945

description: Two-story, gambrel roof outbuilding. Metal roof. Clapboard siding on second floor; concrete block first floor. Concrete foundation. 2 X 1 bays.

1 not-eligible building (NE)

**0222. STUTLER FORK ROAD/COUNTY ROUTE 35/6, residential**

**Curry House & Farm**

HS-0651

date: Ca. 1927

description: Two-story, side gable house. Believe the right side of the house was originally a cellar house but it was either enlarged to accommodate a residence or incorporated into the residence. "V" seam metal roof. Exposed, concrete block, end chimneys. Vinyl siding over clapboard siding. Modern 6/6 squat windows with shutters. Non-original, shed roof, entrance porch with modern square posts and modern "X" balustrade. Two-story, shed roof addition on the rear. Stone and concrete foundation. 4 X 3 bays. "I" house. Modified.

1 not-eligible building (NE)

**222A.**

date: Ca. 1945

description: Large, three-story, end gable barn with central roof monitor. Metal roof. Vertical board siding on upper floors; concrete block first floor and foundation. 4 X 3 bays.

1 not-eligible building (NE)

**222B.**

date: Ca. 1980

description: One-story, end gable, corn crib with shed roof wing on the right. Metal roof. Board siding. Stone pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**222C.**

date: Ca. 1900

description: Two-story, end gable barn. Metal roof. Vertical board siding. Stone pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**222D.**

date: Ca. 1940

description: Small, one-story, side gable outbuilding/wash house. Asphalt shingle roof. Weatherboard siding. Stone pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**222E.**

date: Ca. 1945

description: One-story, end gable garage/barn. Metal roof. Concrete block façade and foundation. 3 X 2 bays.

1 not-eligible building (NE)

**0223. RIGHT FORK/COUNTY ROUTE 35/5, residential**

HS-0652

**Coffindaffer House & Farm**

date: Ca. 1890

description: Two-story, rear facing "L" house with rear wing one and one-half-story. Two, interior, stone, end chimneys; one, interior, stone chimney on rear. Metal roof. Vinyl siding. Vertical 2/2 windows. One-story, hip roof, three-quarter length, front porch with modern Doric posts on an enclosed balustrade and stone pier foundation. One-story, shed roof, rear, enclosed porch; opposite side of wing has a screened-in porch within the roof overhang. Small, entrance porch on the side. Cut stone foundation. 5 X 4 bays. "I" house.

1 not-eligible building (NE)

**223A.**

date: Ca. 1890

description: Two-story, end gable, cellar house. Metal roof. Vertical board siding on second floor; cut stone first floor and foundation. 1 X 1 bays. Partially below grade.

1 not-eligible building (NE)

**223B.**

date: Ca. 1960

description: One-story, end gable garage. Metal roof. Concrete block façade and foundation. 2 X 1 bays.

1 not-eligible building (NE)

**223C.**

date: Ca. 1980

description: One-story, end gable barn. Metal roof. Vertical board siding. Concrete block pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**223D.**

date: Ca. 1980

description: One-story, shed roof outbuilding. Metal roof. Board and batten siding. Concrete block pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**223E.**

date: Ca. 1940

description: One-story, end gable outbuilding. Metal roof. Board and batten siding. Stone pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**223F.**

date: Ca. 1890

description: One-story, end gable barn. Metal roof. Vertical board siding. Stone pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**223G.**

date: Ca. 1940

description: One-story, end gable, corn crib/granary. Metal roof. Lattice and vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**223H.**

date: Ca. 1900

description: Large, three-story, end gable barn with enclosed, shed roof wing on the right. Corrugated metal roof. Vertical board siding. Stone pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**223I.**

date: Ca. 1980

description: One-story, shed roof, machine shed. Metal roof. Vertical board siding. Wood pier foundation. 3 X 1 bays.

1 not-eligible building (NE)

**223J.**

date: Ca. 1940

description: Two-story, side gable outbuilding/garage with one-story, enclosed addition on the right. Metal roof. Clapboard siding on second floor; concrete block first floor and foundation. 7 X 1 bays.

1 not-eligible building (NE)

**0224. RIGHT FORK/COUNTY ROUTE 35/5, residential**

HS-0653

**Coffindaffer House & Farm**

date: Ca. 1900

description: One-story, cross gable house. Metal roof. Chimney has been removed. Chisel point shingles in gable end. Scrolled corner brackets. German siding with corner and frieze boards. 1/1 windows with simple surrounds and hoods with decorative corner blocks. One-story, hip roof, enclosed, front porch. Rear porch enclosed and attached to it is a shed roof, open porch with square posts on a concrete deck. Set of sliding glass doors in rear porch. Open porch in rear is attached to a two-story, end gable, cellar house with forebay. Cellar house has metal roof, T-111 siding on second floor and stone first floor and foundation. Stone foundation. 3 X 2 bays. Folk Victorian style.

1 not-eligible building (NE)

**224A.**

date: Ca. 1900

description: Two-story, end gable barn with enclosed, shed roof wing on the left and rear. Metal roof. Vertical board siding. Stone pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**224B.**

date: Ca. 1980

description: One-story, shed roof, machine shed. Corrugated metal roof. Vertical board siding. Pier foundation. 3 X 1 bays.

1 not-eligible building (NE)

**0225. RIGHT FORK/COUNTY ROUTE 35/5, residential**

HS-0654

**Davis House & Farm**

date: Ca. 1890

description: Two-story, rear facing "L" house with rear wing one-story. Central, interior, stone chimney. Asphalt shingle roof. Scrolled corner brackets. Vinyl siding. Modern 1/1 windows with shutters; many are paired. One-story, shed roof, three-quarter length, front porch with turned posts with spoked brackets and spindled balustrade with ball finials. One-story, shed roof, rear porch partially enclosed; remainder has modern square posts. Stone foundation. 3 X 3 bays. "I" house. Modified.

1 not-eligible building (NE)

**225A.**

date: Ca. 1890

description: One-story, end gable outbuilding. Metal roof. Board and batten siding. Stone pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**225B.**

date: Ca. 1980

description: One-story, end gable garage. Onduline roof. Concrete block façade and foundation. 2 X 2 bays.

1 not-eligible building (NE)

**225C.**

date: Ca. 1945

description: One-story, end gable garage/outbuilding with shed roof wing on right. "V" seam metal roof. Terra cotta block façade and foundation. 2 X 2 bays.

1 not-eligible building (NE)

**225D.**

date: Ca. 1980

description: One-story, end gable, machine shed. "V" seam metal roof. Vertical board siding. Block pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**225E.**

date: Ca. 1945

description: Large, two-story, end gable barn with enclosed, shed roof wing on right. Silo on rear. Front forebay. Metal roof. Vertical board siding on second floor; terra cotta block first floor and foundation. Concrete block addition on the rear. 4 X 9 bays.

1 not-eligible building (NE)

**0226. RIGHT FORK/COUNTY ROUTE 35/5, residential**

HS-0655

**Cottrill House**

date: Ca. 1890

description: One-story, rear facing "L" house. Central, interior, brick chimney. "V" seam metal roof. Clapboard siding with corner and frieze boards. Vertical 2/2 and 1/1 windows. Front porch has been removed. One-story, shed roof porch on the side with modern square posts on a wood deck supported by brick pier foundation. Rear porch has also been removed. Stone pier foundation covered with metal veneer. 3 X 3 bays. Central Passage house.

1 not-eligible building (NE)

**226A.**

date: Ca. 1890

description: Two-story, end gable, cellar house with forebay. Forebay has been enclosed with concrete block to create a machine shed. Metal roof. Board and batten siding on second floor; cut stone and concrete block first floor and foundation. 1/1 windows. 1 X 2 bays.

1 not-eligible building (NE)

**226B.**

date: Ca. 1980

description: One-story, shed roof, chicken coop. Metal roof. Vertical board siding. Pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**227. RIGHT FORK/COUNTY ROUTE 35/5, residential**

**Cumberledge House & Farm**

HS-0656

date: Ca. 1910

description: One-story, cross gable house. Central, interior, stone chimney. Asphalt shingle and roll roofing. Vinyl siding. 1/1 windows. One-story, shed roof, entrance porch with modern square posts. One-story, shed roof, rear porch has been enclosed. Stone pier foundation infilled with concrete block and covered with faux stone veneer. 4 X 1 bays. Modified.

1 not-eligible building (NE)

**227A.**

date: Ca. 1910

description: Two-story, end gable, cellar house. Roll roofing. Particle board on the second floor; cut stone first floor and foundation has been parged. 1 X 1 bays.

1 not-eligible building (NE)

**227B.**

date: Ca. 1950

description: One-story, end gable, well house. Roll roofing. Concrete block façade and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**227C.**

date: Ca. 1945

description: Large, two-story, end gable barn. Metal roof. Horizontal block siding on second floor; terra cotta block first floor and foundation. 3 X 4 bays.

1 not-eligible building (NE)

**227D.**

date: Ca. 1995

description: One-story, end gable garage. Asphalt shingle roof. Vinyl siding. Concrete block foundation. 2 X 1 bays.

1 not-eligible building (NE)

**0228. TWO LICK RUN ROAD/COUNTY ROUTE 19/18, residential**

**Marshall G. Law House & Farm**

HS-0657

date: Ca. 1930

description: Two-story, side gable house with large, central, shed roof dormer on the front and rear. Raised basement on the front with two garage bays in it. Knee braces. Asphalt shingle roof. Central, interior, brick chimney. Weatherboard and clapboard siding and log. 1/1 windows. One-story, hip roof, wraparound porch is partially enclosed and the remainder is screened-in. Rock-faced concrete block foundation. 3 X 3 bays. Bungalow style.

1 not-eligible building (NE)

**0229. COUNTY ROUTE 270, residential**

**Dawson/Bond House & Farm**

HS-0658

date: Ca. 1917

description: Two-story, hip roof house with gable bays. Interior, corbelled brick chimney. Slate roof. Aluminum siding. 1/1 windows. One-story, hip roof, wraparound porch with wrought iron posts on a concrete deck supported by concrete block foundation. Entrance door has undivided transom and glazed sidelights. Two-story, rear porch: right side has been enclosed; the remainder has turned posts and an enclosed balustrade on the second floor; first floor has turned posts on a concrete deck. One-story, gable addition on the rear of concrete block. Rock-faced concrete block foundation. 3 X 3 bays. Queen Anne style. Modified.

1 not-eligible building (NE)

**229A.**

date: Ca. 1945

description: One-story, end gable outbuilding. Metal roof. Terra cotta block façade and foundation. Six light windows. 1 X 2 bays.

1 not-eligible building (NE)

**229B.**

date: Ca. 1950

description: One-story, end gable barn with shed roof, open wing on the right. Metal roof. Vertical board and metal siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**229C.**

date: Ca. 1950

description: One-story, shed roof outbuilding. Metal roof. Vertical board siding. Stone pier foundation. 3 X 2 bays.

1 not-eligible building (NE)

**0230. COUNTY ROUTE 270, residential**

**Dawson/Kennedy House & Farm**

HS-0659

date: Ca. 1850

description: Two-story, front facing "L" house. Two, interior, corbelled brick chimneys; exposed concrete block chimney on addition. Asphalt shingle roof. Scrolled corner brackets. Decorative shingles in gable end. Vinyl siding. Modern 1/1 windows; paired in the front gable. Two-story, hip roof, front porch in the corner of the ell: the second floor

has spindled vergeboard, turned posts with brackets and slatted balustrade; the first floor is the same with no balustrade. Entrance door has arched glazing in the upper panel. Two-story, gable addition on rear. Cut stone, rubble stone and concrete block foundation. 4 X 3 bays. Folk Victorian style. Modified.

1 not-eligible building (NE)

**230A.**

date: Ca. 1945

description: One-story, end gable garage. "V" seam metal roof. Clapboard siding and terra cotta block façade and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**230B.**

date: Ca. 1990

description: One-story, end gable outbuilding. Corrugated metal roof. Plywood siding. Stone foundation. 2 X 1 bays.

1 not-eligible building (NE)

**230C.**

date: Ca. 1995

description: Large, one-story, end gable garage/machine shed. Metal roof. Metal siding. Concrete foundation. 2 X 3 bays.

1 not-eligible building (NE)

**230D.**

date: Ca. 1900

description: Two-story, end gable, cellar house. Roll roofing. Clapboard siding on the second floor; cut stone first floor and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**230E.**

date: Ca. 1900

description: Large, two-story, end gable barn. Metal roof. Vertical board siding. Pier foundation. 2 X 1 bays. Deteriorated.

1 not-eligible building (NE)

**230F.**

date: Ca. 1900

description: Two-story, gambrel roof barn with two, shed roof wings on the left. Metal roof. Vertical board siding. Pier foundation. 3 X 1 bays. Deteriorated.

1 not-eligible building (NE)

**0231. COUNTY ROUTE 270, residential**

HS-0660

**Jones House/Swisher/Kennedy House & Farm**

date: Ca. 1895

description: Two-story, front facing "L" house. Asphalt shingle roof. Partial return cornice. Chimney has been removed. Vinyl siding. 1/1 windows. One-story, shed roof, front porch with modern Doric posts and wrought iron railing. One-story, hip roof, three-sided, projecting bay on the right. One-story, shed roof, enclosed, rear porch. Stone and concrete block foundation. 3 X 2 bays. Gabled-ell house. Modified.

1 not-eligible building (NE)

**231A.**

date: Ca. 1895

description: One-story, end gable, cellar house/outbuilding. Corrugated metal roof. German siding. Pier foundation. 1 X 2 bays.

1 not-eligible building (NE)

**231B.**

date: Ca. 1995

description: One-story, shed roof, car port. Metal roof supported by square posts.

1 not-eligible building (NE)

**0232. LONG RUN/COUNTY ROUTE 27/2, residential**

HS-0661

**Smith/Nutter House & Farm**

date: Ca. 1880

description: Large, two-story, rear facing "T" house. The rear wing was originally a one-story but this was removed and a two-story, gable addition put on. Chimneys have been removed. Asphalt shingle roof. Partial return cornice. Vinyl siding. Modern 6/6 windows with shutters. One-story, hip roof, entrance porch with Doric columns on an enclosed balustrade. The porch was original two-story. Entrance doors has divided transom and sidelights. The rear addition has two sets of French doors – one on each floor. Stone and concrete block foundation. 5 X 4 bays. "T" house. Modified.

1 not-eligible building (NE)

**232A.**

date: Ca. 1880

description: One-story, side gable outbuilding. Corrugated metal roof. Combination of sidings. Concrete block pier foundation. 1 X 1 bays. Believe this may have originally been the one-story wing of the main house. It has been removed and is being used as a play house for children.

1 not-eligible building (NE)

**232B.**

date: Ca. 1880

description: Large, two-story, side gable barn with one-story, shed roof wing on the right and a two-story, shed roof wing on the rear. Corrugated metal roof. Vertical board siding over logs. Stone foundation. 2 X 2 bays.

1 not-eligible building (NE)

**232C.**

date: Ca. 1980

description: One-story, shed roof, wood shed. Metal roof. Vertical board siding. Pier foundation.

1 not-eligible building (NE)

**232D.**

date: Ca. 1950

description: One-story, side gable outbuilding with enclosed, shed roof wing on the rear. Metal roof. Combination of sidings. Block pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**232E.**

date: Ca. 1945

description: One-story, end gable garage. Metal roof. Terra cotta block façade and foundation. 2 X 1 bays.

1 not-eligible building (NE)

**232F.**

date: Ca. 2000

description: One-story, end gable garage/outbuilding. Metal roof. Metal siding. Concrete foundation. 2 X 2 bays.

1 not-eligible building (NE)

**0233. LONG RUN/COUNTY ROUTE 27/2, residential**

HS-0662

**Davisson House & Farm**

date: Ca. 1870

description: Two-story, rear facing "L" house with rear wing one-story. Breezeway on rear attaches rear wing to a two-story, gable garage/cellar house. Cellar house has aluminum siding on second floor and terra cotta block first floor. Log structure. Metal roof. Interior, brick, end chimney. Aluminum siding. 1/1 windows. One-story, shed roof, entrance porch with turned posts with brackets. One-story, shed roof, rear, enclosed porch. One-story, shed roof, entrance porch on the side with square posts. Stone pier and stone foundation. 3 X 4 bays. "I" house. Modified.

1 not-eligible building (NE)

**233A.**

date: Ca. 1920

description: Large, two-story, end gable barn with shed roof wing on the right. Metal roof. Horizontal board siding. Pier foundation. 4 X 2 bays.

1 not-eligible building (NE)

**0234. LONG RUN/COUNTY ROUTE 27/2, residential**

HS-0663

**Richards/Davisson House & Farm**

date: Ca. 1913

description: One-story, hip roof house with gable bays. Two, interior, corbelled brick chimneys. Metal shingle roof. Decorative round louver in gable ends. Clapboard siding with frieze and corner boards. 1/1 windows with simple surrounds and hoods. One-story, wraparound porch with Doric columns on a wood deck with brick pier foundation; porch has been enclosed where it wraps around the side. One-story, three-sided, projecting bay on the side. One-story, shed roof wing on the right with concrete block foundation. Brick foundation. 5 X 3 bays. Queen Anne Cottage style.

1 not-eligible building (NE)

**234A.**

date: Ca. 1913

description: Two-story, end gable, cellar house. Gable addition on the rear. Metal roof. Clapboard siding on the second floor; brick first floor and foundation. Vertical 2/2 windows. 2 X 2 bays.

1 not-eligible building (NE)

**0235. LONG RUN/COUNTY ROUTE 27/2, residential**

HS-0664

**"R" Acres/Rigdon House**

date: Ca. 1905

description: One-story, hip roof house with partially raised basement and central, wall gable on the front and a large, two-story, side gable addition on the right. Asphalt shingle roof. Vinyl siding. Modern squat 4/4 and sliding windows. One-story, hip roof, three-quarter length, front porch with wrought iron posts and railing. One-story, shed roof, three-quarter length, enclosed, rear porch with modern, shed roof, entrance porch with square posts on a concrete deck. Rock-faced concrete block and concrete block foundation. 5 X 2 bays. Minimal Traditional style. Modified.

1 not-eligible building (NE)

**235A.**

date: Ca. 1950

description: One-story, side gable, machine shed. Metal roof. Vertical board siding. Wood pier foundation. 3 X 1 bays.

1 not-eligible building (NE)

**235B.**

date: Ca. 1900

description: One-story, end gable barn/wagon shed. Metal roof. Vertical board and board and batten siding. 2 X 1 bays.

1 not-eligible building (NE)

**235C.**

date: Ca. 1990

description: One-story, shed roof, wood shed. Metal roof. Board and batten siding. Concrete block pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**0236. COUNTY ROUTE 270, residential**

**Post House**

HS-0665

date: Ca. 1890

description: Large, two-story, rear facing "L" house with two-story, enclosed bay in the corner of the ell on the rear and a two-story, gable wing on the rear. There is a one-story, end gable garage of terra cotta block attached to the rear wing. Two, interior, corbelled brick, end chimneys on the front; one, interior, corbelled brick chimney on the rear. Asphalt shingle roof. Scrolled corner brackets. Clapboard and vinyl siding. 1/1, vertical 2/2 and vertical 3/1 windows. One-story, shed roof, three-quarter length, front porch with battered square posts on an enclosed paneled balustrade. Entrance door has undivided transom and glazed and paneled sidelights and a simple hood with flanking brackets. Central, end gable, projecting bay on the second floor with tripartite novelty windows and paneled balustrade. One-story, shed roof, rear porch with turned posts. 5 X 6 bays. Stone and terra cotta block foundation. "T" house.

1 not-eligible building (NE)

**236A.**

date: Ca. 1975

description: One-story, shed roof barn. Metal roof. Vertical board siding. Wood pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0237. COUNTY ROUTE 270, residential**

HS-0666

**Maxson/Bond House & Farm**

date: Ca. 1932

description: Small, two-story, side gable house. Exposed, brick chimney on the end. Slate roof. Vinyl siding. Modern 1/1 windows. Small, projecting, end gable, entrance portico with slightly battered square posts. One-story, shed roof wing on the left. Foundation is covered with metal veneer. 4 X 3 bays. Colonial Revival style.

1 not-eligible building (NE)

**237A.**

date: Ca. 1930

description: Very large, three-story, gambrel roof barn with concrete silo. Metal roof. Vertical board siding. Stone pier foundation. 2 X 8 bays.

1 not-eligible building (NE)

**237B.**

date: Ca. 1975

description: One-story, shed roof, machine shed. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0238 STUTLER LANE, residential**

HS-0667

**Stutler/Richards/Sheets House & Farm**

date: Ca. 1902

description: Large, two-story, side facing "T" house with large, two-story, gable wing on the rear. Four, interior, brick chimneys veneered with rock-faced concrete block. Scrolled corner brackets. Slate roof. Clapboard siding with frieze and corner boards. 1/1 windows with simple surrounds and hoods. One-story, hip roof, front porch with battered square posts on square piers on a wood deck with a rock-faced foundation. One-story, hip roof porches flank rear wing and have battered square posts on square piers. Stone foundation covered with rock-faced concrete block. 3 X 6 bays. Queen Anne style.

1 building eligible to the National Register (CE)

**238A.**

date: Ca. 1940

description: One-story, end gable garage with open, shed roof wing on the left. Corrugated metal roof. Weatherboard siding. Six pane windows. Concrete block pier foundation. 2 X 1 bays.

1 building eligible to the National Register (CE)

**238B.**

date: Ca. 1880

description: Two-story, side gable, cellar house/house. Corrugated metal roof. Board and batten siding on the second floor; cut stone first floor and foundation. 6/6 windows. 3 X 1 bays. Original, exposed, stone chimney has collapsed.

1 building eligible to the National Register (CE)

**238C.**

date: Ca. 1995

description: One-story, shed roof, machine shed. Metal roof. Metal siding. Round wood post supports. 2 X 1 bays.

1 not-eligible building (NE)

**238D.**

date: Ca. 1900

description: One-story, end gable, machine shed/barn. Corrugated metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 building eligible to the National Register (CE)

**238E.**

date: Ca. 1985

description: One-story, shed roof barn. Metal roof. Vertical board siding. Pier foundation. 3 X 2 bays.

1 not-eligible building (NE)

**238F.**

date: Ca. 2003

description: One-story, side gable barn/machine shed. Metal roof. Vertical board and metal siding. Square wood posts. 8 X 1 bays. Attached is a side gable barn that attaches to a terra cotta block silo.

1 not-eligible building (NE)

**238G.**

date: Ca. 1855

description: Large, two and one-half-story, side gable barn. Half of the barn was destroyed in the latest bad snow storm but the remainder is being re-roofed. Metal roof. Hand hewn log timbers and vertical board siding. Pier foundation. 2 X 3 bays.

1 building eligible to the National Register (CE)

**0239. COUNTY ROUTE 270, residential**

HS-0668

**Daugherty House**

date: Ca. 1890

description: Two-story, rear facing "L" house. Central, interior, corbelled brick parged chimney; interior, corbelled brick parged chimney on rear wing. Asphalt shingle roof. Vinyl siding. Vertical 2/2 windows. Central, one-story, hip roof, entrance porch with battered square columns on a concrete deck. Entrance door has an undivided transom. One-story, shed roof, enclosed, rear porch. Stone foundation. 5 X 2 bays. "I" house. Modified.

1 not-eligible building (NE)

**239A.**

date: Ca. 1920

description: Two-story, end gable, cellar house with forebay. Metal roof. Weatherboard siding on the second floor; rock-faced concrete block first floor and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**239B.**

date: Ca. 1920

description: One-story, side gable outbuilding. Metal roof. Board and batten siding. Block pier foundation. 1 X 1 bays.  
1 not-eligible building (NE)

**239C.**

date: Ca. 1930

description: One-story, shed roof outbuilding. Metal roof. Weatherboard siding. Pier foundation. 3 X 1 bays.  
1 not-eligible building (NE)

**0240. COUNTY ROUTE 270, residential**

**McDaniel House**

HS-0669

date: Ca. 1850

description: Large, two-story, rear facing "L" house with rear wing one-story. Two, interior, corbelled brick, end chimneys. Corrugated metal roof. Vinyl siding. Modern 1/1 windows. One-story, central, hip roof, front porch with modern Doric columns and original Doric pilasters on a wood deck. One-story, shed roof, rear, enclosed porch. One-story, shed roof addition on the left. Rubble stone foundation. 5 X 5 bays. "I" house. Modified.

1 not-eligible building (NE)

**240A.**

date: Ca. 1950

description: Two-story, end gable garage/residence. Asphalt shingle roof. Vinyl siding on the second floor; concrete block first floor and foundation. 2 X 2 bays.

1 not-eligible building (NE)

**240B.**

date: Ca. 1950

description: One-story, end gable outbuilding. Metal roof. Asbestos shingle siding. Stone pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**240C.**

date: Ca. 1900

description: One-story, end gable outbuilding. Metal roof. Board and batten siding. Stone foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0241. COUNTY ROUTE 270, residential**

**Bartlett House**

HS-0670

date: Ca. 1925

description: Small, two-story, end gable house. Metal roof. Two, interior, corbelled brick chimneys. Small, shed roof dormer on the left. German and vinyl siding. Modern 1/1 windows. One-story, hip roof, central, entrance porch with square brick columns on an enclosed brick balustrade with concrete cap. Modern deck on the rear. Rock-faced concrete block and concrete block foundation. 3 X 4 bays. Bungalow style.

1 not-eligible building (NE)

**241A.**

date: Ca. 1970

description: Small, end gable, one-story, well house. Metal roof. Concrete block façade and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0242. US ROUTE 19, residential**

**Bunch/Sommerville House & Farm**

HS-0671

date: Ca. 1900

description: Large, two-story, rear facing "L" house. Chimneys have been removed; exposed, brick chimney on rear. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows. Two-story, hip roof, projecting, entrance portico: second floor has been fully enclosed; first floor has Doric columns and a non-original canopy. Rear wing was originally a kitchen with an open porch and it has all been enclosed and incorporated into the main body of the house. Stone foundation covered with faux stone veneer. 5 X 2 bays. "T" house. Modified.

1 not-eligible building (NE)

**242A.**

date: Ca. 1900

description: One-story, side gable outbuilding/cellar house. Metal roof. Clapboard siding. Vertical 2/2 windows. Stone foundation. 2 X 1 bays.

1 not-eligible building (NE)

**242B.**

date: Ca. 1945

description: One-story, shed roof, chicken coop. Metal roof. Terra cotta block façade and foundation. 20 X 2 bays.

1 not-eligible building (NE)

**242C.**

date: Ca. 1945

description: One-story, shed roof, brooder house. Metal roof. Terra cotta block façade and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0243. US ROUTE 19, residential**

**Tyler/Turner/Sommers House/J&T Produce/Jane Lew Tile & Block Company**

HS-0672

date: Ca. 1945

description: Large, two-story, hip roof house with central, hip dormer on the front. Interior, corbelled brick chimney. Asphalt shingle roof. Brick over terra cotta block façade. Modern 9/9 and 4/4 windows with concrete lintels and sills; many are paired. One-story, hip roof, three-quarter length, front porch with modern square columns and wrought iron railing on a wood deck. Rock-faced concrete block and concrete block foundation. 2 X 3 bays. Four Square style.

1 not-eligible building (NE)

**243A.**

date: Ca. 1945

description: Large, two-story, clipped gable garage attached to an end gable, one-story garage on the front with shed roof wing on the left. Asphalt shingle roof. Terra cotta block façade and foundation on one-story portion. Rock-faced concrete block on first floor of two-story portion and vinyl siding on second floor. 2 X 4 bays.

1 not-eligible building (NE)

**243B.**

date: Ca. 1995

description: One-story, side gable garage. Asphalt shingle roof. Vinyl siding. Concrete foundation. 2 X 2 bays.

1 not-eligible building (NE)

**243C.**

date: Ca. 1945

description: One-story, end gable outbuilding with shed roof wing on the left. Asphalt shingle roof. Terra cotta block façade and foundation. 2 X 4 bays.

1 not-eligible building (NE)

**0244. US ROUTE 19, residential**

**Layman/Hughes House & Farm**

HS-0673

date: Ca. 1910

description: Two-story, front facing "T" house. Asphalt shingle roof. Central, interior, corbelled brick chimney. Scrolled brackets at the corners. Clapboard siding with frieze and corner boards. 1/1 windows with simple surrounds and hoods with corner rosette blocks. One-story, hip roof, wraparound porch with turned posts and spindled balustrade. Undivided transom on entrance doors; there are two on the porch. Two-story, rear, enclosed porch. Stone pier foundation under porch; stone foundation on house with grapevine joints. 2 X 2 bays. Queen Anne style.

1 building eligible to the National Register (CE)

**244A.**

date: Ca. 1945

description: Two-story, front facing "L" outbuilding/residence. Asphalt shingle roof. Clapboard siding on the second floor; terra cotta block on the first floor. 2/2 windows. Rear, shed roof, enclosed wing. 4 X 2 bays.

1 building eligible to the National Register (CE)

**244B.**

date: Ca. 1890

description: One-story, end gable outbuilding. "V" seam metal roof. Clapboard siding. Stone pier foundation. 1 X 1 bays.

1 building eligible to the National Register (CE)

**244C.**

date: Ca. 1950

description: One-story, side gable outbuilding. "V" seam metal roof. Vertical board siding. Stone pier foundation. 2 X 1 bays.

1 building eligible to the National Register (CE)

**244D.**

date: Ca. 1950

description: One-story, side gable barn with enclosed, shed roof wing on the rear. Metal roof. Horizontal board siding. Stone pier and concrete foundation. 1 X 1 bays.

1 building eligible to the National Register (CE)

**244E.**

date: Ca. 1950

description: Small, one-story, end gable outbuilding. Corrugated metal roof. Vertical board siding. Stone pier foundation. 1 X 1 bays.

1 building eligible to the National Register (CE)

**244F.**

date: Ca. 1890

description: Large, two-story, side gable barn with flanking, enclosed, shed roof wings. Metal roof. Vertical board siding. Stone pier foundation. 6 X 2 bays.

1 building eligible to the National Register (CE)

**0245. HIDDEN VALLEY ROAD/COUNTY ROUTE 19/20, residential**

**Ferrell/Gusman House & Farm**

HS-0674

date: Ca. 1890

description: Large, two-story, end gable house with flanking, two-story, hip roof, projecting, three-sided bays. Two, interior, parged stone chimneys. Standing seam metal roof. Scrolled corner brackets. Clapboard siding with frieze and corner boards. Pedimented and perforated louver in the gable end: the perforations read "J-B-G" on the first line; "1890" on the second line. Cut-out vergeboard in gable end. Narrow, 1/1 windows with simple surrounds and decorative hoods. Front porch has been removed; currently has a small, entrance deck. Undivided transom over entrance door. Side porch also removed. Side entrance door has an undivided transom and novelty glazing. One-story, shed roof, rear porch with non-original square posts on a wood deck with concrete block foundation. Cut stone foundation with grapevine joints. 2 X 4 bays. Folk Victorian style.

1 building eligible to the National Register (CE)

**245A.**

date: Ca. 1945

description: One-story, barrel vault roof garage. Roll roofing. Painted terra block façade and foundation. 1 X 2 bays.

1 building eligible to the National Register (CE)

**245B.**

date: Ca. 1950

description: One-story, end gable outbuilding. Metal roof. Weatherboard siding. Pier foundation covered with metal veneer. 2 X 1 bays.

1 building eligible to the National Register (CE)

**245C.**

date: Ca. 1900

description: One-story, end gable outbuilding with monitor on roof. Corrugated metal roof. Vertical board siding. Pier foundation covered with metal veneer. 3 X 1 bays.

1 building eligible to the National Register (CE)

**245D.**

date: Ca. 1945

description: Two-story, end gable barn with forebay. Metal roof. Board and batten siding and terra cotta block façade. Stone pier foundation. 2 X 2 bays.

1 building eligible to the National Register (CE)

**0246. US ROUTE 19, residential**

HS-0675

**Jenkins House & Farm**

date: Ca. 1945

description: Two-story, hip roof house. Two, interior, corbelled brick chimneys. Asphalt shingle roof. Red brick façade. Metal casement and novelty windows with brick sills.

One-story, hip roof wing on the right. One-story, flat roof, enclosed, projecting, entrance bay with wrought iron roof balustrade. Small, one-story, gable entrance bay on the left.

One-story, hip roof, enclosed, full length, rear porch. Small, central, gable dormer on the rear. Concrete foundation. 3 X 2 bays. Four Square style.

1 not-eligible building (NE)

**246A.**

date: Ca. 1945

description: One-story, hip roof garage. Asphalt shingle roof. Red brick façade. Concrete foundation. 2 X 1 bays.

1 not-eligible building (NE)

**246B.**

date: Ca. 1945

description: One-story, end gable, corn crib. Metal roof. Lattice siding. Stone pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**246C.**

date: Ca. 1945

description: Large, three-story, gambrel roof barn with forebay and enclosed, shed roof wing on the right. Metal roof. Vertical board siding on the upper floors; terra block first floor and foundation. 4 X 6 bays.

1 not-eligible building (NE)

**0247. US ROUTE 19, residential**

HS-0676

**Poole House/Maplewood**

date: Ca. 1840

description: Very large, two-story, rear facing "L" house. Two, large, exposed, end, parged stone chimneys. Asphalt shingle roof. Wide clapboard siding with frieze board. Vertical 2/2 windows with shutters. Two-story, end gable, projecting, entrance bay with dentiled entablature and cornice; chamfered posts and slatted balustrade on the second floor; square columns on the first floor. Entrance doors have fluted, paneled pilasters with rosette blocks and plinths and a dentiled hood, divided transom and divided sidelights. Gable wing attached to rear wing. Small, two-story, projecting, gable bay in the corner of the ell on the rear. Small entrance porch on rear wing with turned posts. One-story, flat roof wing attached to other rear wing with a roof balustrade with ball finials on the corner newell posts. Stone foundation. 5 X 8 bays. The interior was gutted in the 1960s. Greek Revival style.

1 not-eligible building (NE)

**247A.**

date: Ca. 1980

description: Large, one-story, side gable garage with shed roof barn attached on the rear. Asphalt shingle roof. Wide clapboard siding. Concrete foundation. 5 X 2 bays.

1 not-eligible building (NE)

**247B.**

date: Ca. 1840

description: One-story, shed roof, well house. Roll roofing. Stone first floor and foundation. 1 X 1 bays. Was probably originally a two-story, cellar house but the second floor is gone.

1 not-eligible building (NE)

**247C.**

date: Ca. 1840

description: Small, one-story, side gable outbuilding. Metal roof. Clapboard siding. Stone foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0248. KINCHELOE ROAD/COUNTY ROUTE 35, residential**

**Neely House & Farm**

HS-0677

date: Ca. 1890

description: Two-story, rear facing "L" house with the rear wing one-story. "V" seam metal roof. Scrolled corner brackets. Clapboard and German siding with frieze and corner boards. Vertical 2/2 windows with simple surrounds. One-story, shed roof, three-quarter length, front porch with slightly battered, square, paneled posts on an enclosed shingled balustrade. One-story, hip roof, three-quarter length, rear porch with square posts on a wood deck supported by stone pier foundation. Rubble stone foundation. 4 X 4 bays. "I" house.

1 not-eligible building (NE)

**248A.**

date: Ca. 1920

description: Two-story, end gable, cellar house with forebay. Metal roof. German siding on second floor; first floor and foundation is brick. 1 X 1 bays.

1 not-eligible building (NE)

**248B.**

date: Ca. 1890

description: Two-story, end gable barn with forebay. Open, shed roof wing on the right. Metal roof. Board and batten and vertical board siding. Stone pier foundation. 4 X 3 bays.

1 not-eligible building (NE)

**0249. KINCHELOE ROAD/COUNTY ROUTE 35, residential**

**G.S. Gillespie House & Taxidermy**

HS-0678

date: Ca. 1940

description: Two-story, side gable house with central, shed roof dormer on the front with exposed rafter tails. Knee braces in the gable ends. Asphalt shingle roof. No evidence of a chimney. Weatherboard siding. Modern 1/1 windows. Picture window and sliding glass doors on the side. Front porch within roof overhang and it has modern square posts and

modern lattice balustrade with deck that wraps around to the side. One-story, shed roof, full length, enclosed, rear porch. Shed roof breezeway on the rear attaches to a small, one-story, gable outbuilding with all the same materials. Terra cotta block foundation. 3 X 3 bays. Bungalow style. Modified.

1 not-eligible building (NE)

**249A.**

date: Ca. 1940

description: One-story, end gable garage. Roll roofing. Weatherboard siding. Concrete block pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**249B.**

date: Ca. 1940

description: One-story, end gable outbuilding/shop. Asphalt shingle roof. Weatherboard siding. Pier foundation. 1 X 2 bays.

1 not-eligible building (NE)

**249C.**

date: Ca. 1940

description: One-story, shed roof barn. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**249D.**

date: Ca. 1940

description: One-story, end gable barn. Metal roof. Vertical board siding. Pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**249E.**

date: Ca. 1970

description: One-story, end gable gas shed. Metal roof. Metal siding. 2 X 1 bays.

1 not-eligible building (NE)

**0250. KINCHELOE ROAD/COUNTY ROUTE 35, residential**

**Hayhurst/Burnside House & Farm**

HS-0679

date: Ca. 1890

description: One-story, rear facing "L" house. May have once been two-story. Corrugated metal roof. Partial return cornice. Chimney has been removed. German siding with frieze and corner boards. Vertical 2/2 windows. One-story, shed roof, central, entrance porch with square columns – non-original. One-story, shed roof, rear porch partially enclosed; remainder is screened-in. Stone pier foundation. 4 X 3 bays. Double-Pen house. Modified.

1 not-eligible building (NE)

**250A.**

date: Ca. 1950

description: One-story, side gable outbuilding with gable wing on the right. Metal roof. Combination of sidings. 2 X 1 bays.

1 not-eligible building (NE)

**250B.**

date: Ca. 1950

description: One-story, end gable barn with flanking, shed roof wings. Metal roof. Combination of sidings. Pier foundation. 1 X 2 bays.

1 not-eligible building (NE)

**250C.**

date: Ca. 1950

description: One-story, end gable, corn crib. Metal roof. Vertical board siding. Concrete block foundation. 1 X 1 bays.

1 not-eligible building (NE)

**250D.**

date: Ca. 1980

description: One-story, shed roof barn. Metal roof. Blackboard siding. Pier foundation. 3 X 1 bays.

1 not-eligible building (NE)

**250E.**

date: Ca. 1980

description: One-story, end gable, well house. Metal roof. Concrete block façade and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**250F.**

date: Ca. 1890

description: Two-story, side gable, cellar house. Metal roof. Horizontal board siding on second floor; cut stone first floor and foundation. 1 X1 bays.

1 not-eligible building (NE)

**250G.**

date: Ca. 1980

description: One-story, shed roof garage. Metal roof. Metal siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0251. TURKEYPEN CREEK ROAD/COUNTY ROUTE 10/12, residential**

**LEWIS COUNTY**

HS-0680

date: Ca. 1880

description: Two-story, rear facing "L" house with central, wall gable on the front that forms the entrance bay. Two, interior, end, stone chimneys; one, interior, stone chimney on rear wing. Metal roof. Asphalt shingle siding. Modern 1/1 windows and two picture windows on the front. One-story, hip roof, central, entrance porch with square posts and slatted balustrade on a wood deck and the deck is open on the left – non-original. Entrance door has divided transom and divided and paneled sidelights. Small, one-story, gable wing on the left. Original back porch is gone; currently has a small, shed roof, entrance porch with modern square posts and 2X4 rail. Stone pier foundation covered with metal veneer. 4 X 3 bays. Gothic Revival style. Modified.

1 not-eligible building (NE)

**251A.**

date: Ca. 1990

description: One-story, shed roof garage. "V" seam metal roof. T-111 siding. Concrete foundation. 2 X 1 bays.

1 not-eligible building (NE)

**251B.**

date: Ca. 1945

description: One-story, side gable outbuilding. Roll roofing. Terra cotta block façade and foundation. 2 X 1 bays.

1 not-eligible building (NE)

**251C.**

date: Ca. 1990

description: Large, one-story, side gable shop/residence. Asphalt shingle roof. T-111 siding. Modern windows. Concrete block foundation. 4 X 3 bays.

1 not-eligible building (NE)

**251D.**

date: Ca. 1990

description: One-story, shed roof machine shed. Metal roof. Metal siding. 3 X 1 bays.

1 not-eligible building (NE)

**251E.**

date: Ca. 1995

description: Large, one-story, side gable barn. Metal roof. Metal siding. Concrete foundation.

1 not-eligible building (NE)

**251F.**

date: Ca. 1995

description: One-story, end gable garage. Metal roof. Metal siding. Concrete foundation.

1 X 1 bays.

1 not-eligible building (NE)

**0252. KINCHELOE ROAD/COUNTY ROUTE 35, residential**

**Dallas House & Farm**

HS-0681

date: Ca. 1890

description: Large, two-story, front facing "L" house. Interior, stone chimney. "V" seam metal roof. Scrolled corner brackets. Perforated decorative round louver in gable end. German siding with frieze and corner boards. Vertical 2/2 windows with simple surrounds and decorative hoods with corner rosette blocks and garland and swag in between the blocks. One-story, modified hip roof, wraparound porch with slightly battered and paneled square posts on a wood deck. Small portion of the porch in the corner of the ell that is enclosed. Stone pier foundation covered with metal veneer. 4 X 3 bays. Gabled-ell house.

1 not-eligible building (NE)

**252A.**

date: Ca. 1890

description: Two-story, side gable, cellar house/residence. Large residential wing on the roof with concrete block foundation and roll roofing. Metal roof. German siding on the second floor; cut stone first floor and foundation. 3 X 3 bays.

1 not-eligible building (NE)

**252B.**

date: Ca. 1900

description: One-story, end gable barn with enclosed, shed roof wing on the left and rear. Metal roof. Combination of sidings. Pier foundation. 2 X 2 bays.

1 not-eligible building (NE)

**252C.**

date: Ca. 1890

description: One-story, shed roof outbuilding. Metal roof. Vertical board siding. Pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**252D.**

date: Ca. 1890

description: One-story, shed roof outbuilding. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**252E.**

date: Ca. 1890

description: One-story, end gable outbuilding. May have once been a small store or post office. Metal roof. Asphalt shingle siding over vertical board siding. Pier foundation. 3 X 1 bays.

1 not-eligible building (NE)

**0253. KINCHELOE ROAD/COUNTY ROUTE 35, residential**

**Baird House**

HS-0682

date: Ca. 1919

description: Large, two-story, hip roof house with projecting, gable bays. Fiberglass (Onduline) roof. Vinyl siding. Modern 1/1 windows. One-story, hip roof, wraparound curved porch with Doric posts and spindled balustrade. One-story, gable addition on the right with French doors. Modern elevated deck on the rear. Stone foundation; stone pier foundation on porch. Queen Anne style. 4 X 2 bays. Modified.

1 not-eligible building (NE)

**253A.**

date: Ca. 1900

description: Two-story, end gable, cellar house with forebay. Onduline roof. Vinyl siding on the second floor; cut stone first floor and foundation. Modern elevated deck. 1 X 1 bays.

1 not-eligible building (NE)

**0254. KINCHELOE ROAD/COUNTY ROUTE 35, residential**

**Beever House & Farm**

HS-0683

date: Ca. 1900

description: Large, two-story, rear facing "L" house. One, interior, stone chimney on front portion; one, interior, brick chimney on rear wing. Asphalt shingle roof. Weatherboard siding. Non-original 9// windows with simple surrounds. One-story, hip roof, full length, front porch with square posts on a concrete deck supported by concrete blocks. Two entrance doors. Two-story, shed roof porch on the side with the first floor enclosed and the second floor is open – it is currently being repaired. One-story, shed roof, enclosed, rear porch. Stone foundation. 4 X 4 bays. "I" house. Modified.  
1 not-eligible building (NE)

**254A.**

date: Ca. 1990

description: Small, one-story, gambrel roof, garden shed. Roll roofing. Painted plywood siding. Pier foundation. 2 X 1 bays.  
1 not-eligible building (NE)

**254B.**

date: Ca. 1990

description: Two-story, end gable, cellar house. Roll roofing. Vertical board siding on the second floor; concrete block first floor and foundation. 1 X 1 bays.  
1 not-eligible building (NE)

**254C.**

date: Ca. 1990

description: One-story, shed roof, wood shed. Roll roofing. Vertical board siding. Concrete block pier foundation. 2 X 1 bays.  
1 not-eligible building (NE)

**254D.**

date: Ca. 1990

description: One-story, end gable barn with open, shed roof wing on the rear. Corrugated metal roof. Painted plywood siding. Concrete block foundation. 3 X 1 bays.  
1 not-eligible building (NE)

**254E.**

date: Ca. 2000

description: Tall, one-story, side gable, machine shed/hay storage building. Metal roof. No siding as yet – still being worked on. Pier foundation. 1 X 1 bays.  
1 not-eligible building (NE)

**0255. KINCHELOE ROAD/COUNTY ROUTE 35, residential**

**Paugh House & Farm**

HS-0684

date: Ca. 1890

description: Small, two-story, rear facing "L" house. Central, interior, stone chimney. Metal roof. Vinyl siding. Modern 1/1 windows. Small, one-story, hip roof, entrance porch with square posts with brackets and lattice enclosure. One-story, shed roof porch in the corner of the ell on the rear/side with wrought iron posts and railing. One-story, shed roof, rear porch on the other side of the house has been enclosed. Modern deck added to

enclosed porch. Stone pier foundation covered with metal veneer. 5 X 4 bays. Center Passage house. Modified.

1 not-eligible building (NE)

**255A.**

date: Ca. 1950

description: One-story, end gable outbuilding. Asphalt shingle roof. Metal siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**255B.**

date: Ca. 1950

description: One-story, shed roof, well house. Metal roof. Concrete block façade and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**255C.**

date: Ca. 1890

description: Two-story, end gable garage/barn with flanking, shed roof, enclosed wings. Metal roof. German siding. Pier foundation. 4 X 1 bays.

1 not-eligible building (NE)

**255D.**

date: Ca. 1890

description: One-story, shed roof, chicken coop. Metal roof. Clapboard siding. Stone pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**255E.**

date: Ca. 1970

description: One-story, shed roof, machine shed/barn. Metal roof. Vertical board siding. Pier foundation. 4 X 1 bays.

1 not-eligible building (NE)

**0256. KINCHELOE ROAD/COUNTY ROUTE 35, residential**

**Coffindaffer House**

HS-0685

date: Ca. 1890

description: Two-story, front facing "L" house. Interior, stone chimney; interior, brick chimney. "V" seam metal roof. Chisel point shingles and novelty window in gable end. German siding with frieze and corner boards. Vertical 2/2 windows with simple surrounds and window hoods with corner blocks. Two-story, hip roof, front porch in the corner of the ell: first floor has chamfered posts with scrolled brackets, scrolled balustrade and Eastlake vergeboard; second floor has chamfered posts with scrolled brackets, cut-out and scrolled balustrade and Eastlake vergeboard. One-story, shed roof, rear, enclosed porch that attaches to a breezeway that attaches to a two-story, end gable, cellar house. Cellar house has metal roof, board and batten siding on the second floor and cut stone first floor and foundation. Stone pier foundation covered with metal veneer. 3 X 2 bays. Folk Victorian style.

1 not-eligible building (NE)

**0257. KINCHELOE ROAD/COUNTY ROUTE 35, residential**

HS-0686

**Lough House**

date: Ca. 1915

description: Very large, two-story, hip roof house with projecting, gable bays. Chimneys have been removed. Asphalt shingle roof. Palladian windows with keystones in gable ends. Herringbone siding band separates the floors on the front gable bay. German siding with frieze and corner boards. 1/1 windows with simple surrounds and hoods. One-story, hip roof, front porch with Doric posts on a concrete deck supported by concrete block foundation. Undivided transom over entrance door. One-story, hip roof, enclosed, rear porch. Breezeway on the rear attaches the house to a two-story, gable, cellar house. Cellar house has asphalt shingle roof, vertical 2/2 windows and German siding on second floor and cut stone first floor and foundation. Cut stone foundation. 3 X 3 bays. Queen Anne style.

1 not-eligible building (NE)

**257A.**

date: Ca. 1990

description: One-story, hip roof house with raised basement. Metal roof. Vinyl siding. Modern windows. Modern deck above with garage bays below on the raised basement portion. Concrete block foundation. 4 X 2 bays.

1 not-eligible building (NE)

**0258. TANNER FORK OF KINCHELOE ROAD/COUNTY ROUTE 35, residential**

**Titus House/Harvey Morris House & Farm**

HS-0687

date: Ca. 1880

description: Two-story, shallow side gable house. Two, interior, stone, end chimneys. Corrugated metal roof. Spindled brackets at the corners. Clapboard siding with wide frieze and corner boards. 1/1 windows with simple surrounds with corner blocks and shutters; windows are narrow on the second floor. Log framing. Two entrance doors on the front. Front porch has been removed and infilled with plywood siding and a pair of modern windows. One-story, shed roof, enclosed, rear porch. One-story, shed roof, open porch on one end with wrought iron posts on a concrete deck. Stone pier foundation infilled with terra cotta block. 4 X 1 bays. "I" house. Modified.

1 not-eligible building (NE)

**258A.**

date: Ca. 1900

description: Two-story, end gable barn. Metal roof. Vertical board siding. Pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**258B.**

date: Ca. 1945

description: One-story, side gable outbuilding. Corrugated metal roof. Terra cotta block façade. Concrete foundation. 3 X 1 bays.

1 not-eligible building (NE)

**258C.**

date: Ca. 1880

description: Two-story, end gable, cellar house with forebay. Metal roof. German siding on second floor; cut stone first floor and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**258D.**

date: Ca. 1945

description: One-story, shed roof garage. Metal roof. Vertical board siding. Terra cotta block foundation. Exposed rafter tails. 1 X 5 bays.

1 not-eligible building (NE)

**258E.**

date: Ca. 1950

description: One-story, end gable outbuilding with an enclosed, shed roof wing on the right. Metal roof. Metal siding. Pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**0259. TANNER FORK OF KINCHELOE ROAD/COUNTY ROUTE 35, residential  
Garska/Morris House & Farm** HS-0688

date: Ca. 1870

description: Two-story, side gable house with two-story, shed roof addition on the rear. Log framing. Central, interior, stone chimney. Asphalt shingle roof. Vinyl siding. Modern 1/1 windows with shutters. Front porch has been removed. One-story, shed roof canopy over entrance supported by modern Doric posts and wrought iron railing. Parged foundation. 3 X 2 bays. "I" house. Modified.

1 not-eligible building (NE)

**259A.**

date: Ca. 1970

description: One-story, side gable, two bay garage. Asphalt shingle roof. Weatherboard siding. Concrete foundation. 2 X 1 bays.

1 not-eligible building (NE)

**259B.**

date: Ca. 1880

description: One-story, end gable, cellar house. Asphalt shingle roof. Large cut stone and terra cotta block façade and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**259C.**

date: Ca. 1970

description: One-story, end gable outbuilding. Asphalt shingle roof. Weatherboard siding. Concrete foundation. 1 X 1 bays.

1 not-eligible building (NE)

**259D.**

date: Ca. 2000

description: One-story, side gable, machine shed/barn. Metal roof. Metal siding. Concrete foundation. 3 X 1 bays.

1 not-eligible building (NE)

**0260. TANNER FORK OF KINCHELOE ROAD/COUNTY ROUTE 35, residential**  
**Thompson House & Farm** HS-0689

date: Ca. 1900

description: One-story, end gable house. Metal roof. German siding with frieze and corner boards. 1/1 windows with simple surrounds and hoods; some are paired. One-story, hip roof, full length, front porch with slightly battered square posts on a wood deck. Stone pier foundation covered with metal veneer. 3 X 3 bays. Gable front house  
1 not-eligible building (NE)

**260A.**

date: Ca. 1920

description: One-story, side gable outbuilding. Corrugated metal roof. Two entrance doors flanked by vertical 2/2 windows. Board and batten siding. Stone pier foundation. One-story, shed roof, three-quarter length, front porch with chamfered posts on a wood deck. 3 X 1 bays.

1 not-eligible building (NE)

**260B.**

date: Ca. 1945

description: Two-story, end gable, cellar house. Metal roof. Board and batten siding on the second floor; terra cotta block façade first floor and foundation. Partially parged. 1 X 1 bays. Vertical 2/2 windows.

1 not-eligible building (NE)

**260C.**

date: Ca. 1920

description: One-story, end gable garage. Metal roof. Board and batten siding. Pier foundation. 1 X 2 bays.

1 not-eligible building (NE)

**260D.**

date: Ca. 1920

description: Two-story, end gable barn. Diamond-shaped louver in gable end. Metal roof. Board and batten and vertical board siding. Stone pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**0261. KINCHELOE ROAD/COUNTY ROUTE 35/10, residential**  
**Doak House & Farm** HS-0690

date: Ca. 1900

description: Very large, two-story, rear facing "T" house. Four, interior, corbelled brick chimneys. Asphalt shingle roof. Scrolled corner brackets. Vergeboard and fishscale shingles in the gable ends. German siding with frieze and corner boards. Modern 1/1 windows with simple surrounds and garland and swag hoods. Central, end gable, projecting bay on the front of the second floor. One-story, hip roof, full length, front porch with Doric posts and pilasters and cut-out balustrade. Entrance door has stained glass transom. The rear wing has an open porch on the first floor with Eastlake vergeboard, chamfered posts with brackets and a scrolled and cut-out balustrade. The other side of the wing has a non-original modern deck and an original, two-story, hip roof, three-sided, projecting bay in the corner. Stone foundation. 5 X 5 bays. Folk Victorian style.

1 building eligible to the National Register (CE)

**261A.**

date: Ca. 1900

description: Large, two-story, end gable barn with forebay. Metal roof. German and clapboard siding. Gable breezeway on left attaches to a two-story, end gable barn with horizontal board siding. Multi-pane windows. Stone pier foundation. 5 X 2 bays.

1 building eligible to the National Register (CE)

**261B.**

date: Ca. 1945

description: One-story, end gable garage. Standing seam metal roof. Painted terra cotta block façade and foundation. 1 X 1 bays.

1 building eligible to the National Register (CE)

**261C.**

date: Ca. 1900

description: One-story, side gable outbuilding. Central, interior, corbelled brick chimney. Standing seam metal roof. Clapboard siding. Vertical 2/2 and 1/1 windows. Stone pier and concrete block pier foundation. One-story, shed roof porch with turned posts with brackets on a concrete deck. 4 X 1 bays.

1 building eligible to the National Register (CE)

**0262. KINCHELOE ROAD/COUNTY ROUTE 35/3, residential**

**Moser/Clemans House & Farm**

HS-0691

date: Ca. 1890

description: Large, two-story, hip roof house with large, projecting, gable bays on all sides. One-story, gable wing on the rear with concrete foundation. The right side gable bay is three-sided. Asphalt shingle roof. Chimneys have been removed. Aluminum siding. Modern 1/1 windows; some are paired. Two-story, end gable, projecting, entrance bay with second floor enclosed; first floor has square posts on a wood deck. One-story, rear, enclosed porch. Stone pier foundation infilled with brick. 4 X 4 bays. Queen Anne style. Modified.

1 not-eligible building (NE)

**262A.**

date: Ca. 1890

description: Two-story, end gable, cellar house. Metal roof. Clapboard siding on the second floor; stone first floor and foundation. Vertical 2/2 windows. 1 X 1 bays.

1 not-eligible building (NE)

**262B.**

date: Ca. 1960

description: One-story, end gable garage. Metal roof. Vertical board siding. Wood pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**262C.**

date: Ca. 1960

description: Large, three-story, end gable barn with forebay. Metal roof. Vertical board and board and batten siding. Stone pier foundation. 2 X 3 bays.

1 not-eligible building (NE)

**262D.**

date: Ca. 1960

description: One-story, shed roof barn. Metal roof. Vertical board and board and batten siding. Pier foundation. 1 X 2 bays.

1 not-eligible building (NE)

**262E.**

date: Ca. 1995

description: One-story, shed roof, machine shed with shed roof wing on the left. Metal roof. Metal siding. Pier foundation. 5 X 1 bays.

1 not-eligible building (NE)

**262F.**

date: Ca. 1960

description: One-story, shed roof barn. Metal roof. Vertical board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0263. KINCHELOE ROAD/COUNTY ROUTE 35/3, residential**

**Lewis/Coffindaffer House & Farm**

HS-0692

date: Ca. 1886

description: Two-story, rear facing "L" house with the rear wing one-story. Central, interior, stone chimney. Metal roof. Clapboard siding with frieze and corner boards. Vertical 2/2 windows with simple surrounds. Two-story, shed roof, central, entrance, projecting bay: the second floor has Eastlake vergeboard, chamfered posts with scrolled brackets and spindled balustrade; the first floor has square posts on a wood deck. Modern deck on the rear. Stone pier foundation covered with faux stone veneer. 3 X 3 bays. "I" house.

1 not-eligible building (NE)

**263A.**

date: Ca. 1886

description: Two-story, end gable, cellar house with forebay. "V" seam metal roof. Board and batten siding on the second floor; first floor is cut stone and terra cotta block. 1 X 1 bays.

1 not-eligible building (NE)

**263B.**

date: Ca. 1995

description: One-story, shed roof, machine shed/barn with shed roof wings on the right. Metal and roll roofing. Metal and vertical board siding. Pier foundation. 4 X 1 bays.

1 not-eligible building (NE)

**263C.**

date: Ca. 1886

description: Two-story, end gable barn with shed roof, enclosed wing on the left. Metal roof. Vertical board and herringbone siding. Stone pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**263D.**

date: Ca. 1995

description: One-story, shed roof, chicken coop. Metal roof. Vertical board siding. Stone pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**0264. KINCHELOE ROAD/COUNTY ROUTE 35/3, residential**

**Sowell House & Farm**

HS-0693

date: Ca. 1890

description: Two-story, side gable house with one-story, end gable addition on the front, a one-story, shed roof addition on the side and a one-story, shed roof addition on the rear. Small, modern deck on the side with ramp. Metal roof. Chimney(s) has been removed. Weatherboard siding. Modern 1/1 and other modern windows. Non-original, one-story, shed roof, rear porch attached to rear addition and it has modern square posts on a wood deck. Concrete block pier foundation on the additions; stone pier on the main house. 3 X 3 bays. "I" house. Modified.

1 not-eligible building (NE)

**264A.**

date: Ca. 1990

description: One-story, side gable barn. Metal roof. Vertical board siding. Concrete block foundation. 3 X 1 bays.

1 not-eligible building (NE)

**264B.**

date: Ca. 1945

description: Two-story, end gable, cellar house. Metal roof. Clapboard siding on the second floor; terra cotta block first floor and foundation. Vertical 2/2 windows. 1 X 1 bays.

1 not-eligible building (NE)

**264C.**

date: Ca. 1995

description: One-story, side gable garage. Onduline roof. Vinyl siding. Concrete block foundation. 3 X 2 bays.

1 not-eligible building (NE)

**264D.**

date: Ca. 1995

description: Large, steep, two-story, end gable barn with flanking, one-story, shed roof, enclosed wings. Metal roof. Vertical board siding. Pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**264E.**

date: Ca. 1890

description: Two-story, end gable barn with shed roof wing on the left and a forebay. Metal roof. Vertical board siding. Pier foundation. 2 X 1 bays. Deteriorated.

1 not-eligible building (NE)

**0265. KINCHELOE ROAD/COUNTY ROUTE 35/3, residential**

**Chi/Chang House & Farm**

HS-0694

date: Ca. 1884

description: Two-story, rear facing "L" house with rear wing one-story. Two, interior, stone, end chimneys; interior, brick chimney on rear wing. Standing seam metal roof. Scrolled corner brackets. Vinyl siding. Vertical 2/2 windows. Two-story, hip roof, projecting, entrance bay with modern square posts on an enclosed balustrade on both floors. Small, entrance porch on rear wing with modern square posts and 2X4 balustrade. Rear wing attaches to a two-story, end gable cellar house that is partially below grade. Cellar house has forebay, asphalt shingle roof, vinyl siding on the second floor and stone on the first floor. Stone pier foundation infilled with concrete block. 5 X 4 bays. "I" house. Modified.

1 not-eligible building (NE)

**265A.**

date: Ca. 1890

description: One-story, end gable, corn crib. Metal roof. Vertical board siding. Stone pier foundation. 2 X 1 bays.

1 not-eligible building (NE)

**265B.**

date: Ca. 1890

description: Large, two-story, end gable barn with flanking, shed roof, enclosed wings. Metal roof. Vertical board siding. Pier foundation. 5 X 3 bays.

1 not-eligible building (NE)

**265C.**

date: Ca. 1995

description: One-story, end gable outbuilding. Metal roof. Vinyl siding. Stone pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**0266. KINCHELOE ROAD/COUNTY ROUTE 35, residential**

**Riverbend Dairy Farm/Nay House & Farm**

HS-0695

date: Ca. 1950

description: One-story, end gable house. Exposed, brick chimney on the front. Asphalt shingle roof. Red brick façade. Horizontal 2/2 windows. Recessed entrance porch on the front corner with wrought iron post on a concrete deck. One-story, rear porch with square posts on a concrete deck. Concrete foundation. 2 X 6 bays. Ranch style.

1 not-eligible building (NE)

**266A.**

date: Ca. 1950

description: Three-story, gambrel roof barn with forebay. Metal roof. Metal and asbestos panel siding on upper floors; first floor and foundation concrete block. Metal windows. 3 X 4 bays.

1 not-eligible building (NE)

**266B.**

date: Ca. 1950

description: Two-story, gambrel roof barn. Three concrete silos on the side. Metal roof. Metal and asbestos panel siding on second floor; concrete block first floor and foundation. Metal windows. 12 X 3 bays.

1 not-eligible building (NE)

**266C.**

date: Ca. 1950

description: One-story, side gable outbuilding with shed roof wing on the rear. Metal roof. Terra cotta block façade and foundation. 2 X 2 bays.

1 not-eligible building (NE)

**266D.**

date: Ca. 1950

description: One-story, end gable, machine shed with enclosed wing on the left. Metal roof. Metal siding. Pier foundation. 3 X 5 bays.

1 not-eligible building (NE)

**266E.**

date: Ca. 1950

description: One-story, end gable, corn crib. Onduline roof. Lattice and board siding. Metal post pier foundation. 1 X 2 bays.

1 not-eligible building (NE)

**266F.**

date: Ca. 1950

description: One-story, end gable outbuilding. Metal roof. Metal siding. Pier foundation. 3 X 1 bays.

1 not-eligible building (NE)

**0267. ELK CITY ROAD/COUNTY ROUTE 19/21, residential**

**Snyder House & Farm**

HS-0696

date: Ca. 1945

description: Small, one-story, cross gable house with raised basement. Asphalt shingle roof. Exposed rafter tails. Asbestos shingle siding. 1/1 windows. End gable, entrance porch with square brick posts on square brick piers. Terra cotta block foundation and basement level. Garage bay on rear. 3 X 2 bays. Craftsman style.

1 not-eligible building (NE)

**0268. VENS RUN ROAD, residential**

**Barron House** HS-0697

date: Ca. 1900

description: Two-story, side facing "T" house with two-story, shed roof addition on the rear. Asphalt shingle roof. Chimney(s) has been removed. Vinyl siding. Modern 1/1 windows with shutters. One-story, end gable, entrance bay with modern square posts and balustrade. The entrance bay connects to a one-story, shed roof, wraparound porch/deck with modern square posts and modern balustrade. One-story, shed roof, rear, enclosed porch. Stone pier foundation infilled with concrete block; additions have concrete block foundation. 3 X 4 bays. "T" house. Very modified.

1 not-eligible building (NE)

**268A.**

date: Ca. 1945

description: One-story, end gable, cellar house. Metal roof. Terra cotta block façade and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**268B.**

date: Ca. 1995

description: One-story, end gable garage/barn. Metal roof. Metal siding. Concrete foundation. 1 X 1 bays.

1 not-eligible building (NE)

**268C.**

date: Ca. 1950

description: One-story, end gable garage. Metal roof. Concrete block façade and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**268D.**

date: Ca. 1950

description: Long, large, two-story, end gable barn with one-story, shed roof, enclosed wing on the left. Concrete silo on rear. Metal roof. Second floor has metal siding; concrete block first floor and foundation. 7 X 3 bays.

1 not-eligible building (NE)

**0269. VENS RUN ROAD, residential**

**Allman House HS-0698**

date: Ca. 1890

description: Two-story, hip roof house with gable bays. Two-story, three-sided, projecting bay on the side. Interior, brick chimney. Standing seam metal roof. Scrolled corner brackets. Clapboard siding with frieze and corner boards. Vertical 2/2 windows with simple surrounds and corner blocks. Central, projecting, end gable bay on the second floor with chisel-point shingles in the gable end, Eastlake vergeboard, chamfered posts with scrolled brackets and an enclosed balustrade. One-story, shed roof, three-quarter length, front porch with battered square posts on brick piers with concrete caps; posts are paired in the middle. Small, one-story, shed roof, rear, enclosed, entrance porch. Stone foundation. 3 X 2 bays. "I" house.

1 not-eligible building (NE)

**269A.**

date: Ca. 1950

description: One-story, end gable garage. Metal roof. Metal siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**269B.**

date: Ca. 1900

description: Two-story, end gable barn. Metal roof. Vertical board siding. Pier foundation. 1 X 2 bays.

1 not-eligible building (NE)

**0270. VENS RUN ROAD, residential**

**Freeman House & Farm HS-0699**

date: Ca. 1911

description: Large, two-story, hip roof house with off-set, wall gable on the front with partial return cornice. Palladian window in wall gable. Two, interior, corbelled brick chimneys. Metal roof. German siding with frieze and corner boards. Modern 1/1 windows with simple surrounds. One-story, shed roof, three-quarter length, front porch with non-original square posts on an enclosed balustrade. One-story, shed roof, three-quarter length, rear porch with turned posts on a wood deck. Stone pier foundation. 3 X 2 bays. Queen Anne style.

1 not-eligible building (NE)

**270A.**

date: Ca. 1980

description: Trailer.

1 not-eligible building (NE)

**270B.**

date: Ca. 1980

description: One-story, shed roof, well house. Metal roof. Concrete block façade and foundation. 1 X 1 bays.

1 not-eligible building (NE)

**270C.**

date: Ca. 1980

description: One-story, end gable garage. Metal roof. Metal siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

**270D.**

date: Ca. 1980

description: One-story, shed roof outbuilding. Metal roof. Horizontal board siding. Pier foundation. 1 X 1 bays.

1 not-eligible building (NE)

|                                                                                                                                 |
|---------------------------------------------------------------------------------------------------------------------------------|
| <p style="text-align: center;"><b>HARRISON COUNTY AGRICULTURAL<br/>HISTORIC RESOURCE SURVEY/PHASE II<br/>PHOTOGRAPH LOG</b></p> |
|---------------------------------------------------------------------------------------------------------------------------------|

| <u>SITE NUMBER</u> | <u>ROLL NUMBER</u> | <u>NEGATIVE NUMBER</u> |
|--------------------|--------------------|------------------------|
| 0151.              | 1                  | 1-4                    |
| 0152.              | 1                  | 5-7                    |
| 0153.              | 1                  | 8-10                   |
| 0154.              | 1                  | 12                     |
| 0155.              | 1                  | 13-15                  |
| 0156.              | 1                  | 16-19                  |
| 0157.              | 1                  | 20 & 21                |
| 0158.              | 1                  | 22 & 23                |
| 0159.              | 1                  | 24 & 25                |
| 0160.              | 1                  | 26 & 27                |
| 0161.              | 1                  | 28 & 29                |
| 0162.              | 1                  | 30-33                  |
| 0163.              | 1                  | 35                     |
| 0164.              | 1 & 2              | 36/1                   |
| 0165.              | 2                  | 2 & 3                  |

|                                                                                                                                 |
|---------------------------------------------------------------------------------------------------------------------------------|
| <p style="text-align: center;"><b>HARRISON COUNTY AGRICULTURAL<br/>HISTORIC RESOURCE SURVEY/PHASE II<br/>PHOTOGRAPH LOG</b></p> |
|---------------------------------------------------------------------------------------------------------------------------------|

| <u>SITE NUMBER</u> | <u>ROLL NUMBER</u> | <u>NEGATIVE NUMBER</u> |
|--------------------|--------------------|------------------------|
| 0166.              | 2                  | 4                      |
| 0167.              | 2                  | 5 & 6                  |
| 0168.              | 2                  | 7 & 8                  |
| 0169.              | 2                  | 9-11                   |
| 0170.              | 2                  | 12-15                  |
| 0171.              | 2                  | 16 & 17                |
| 0172.              | 2                  | 18                     |
| 0173.              | 2                  | 19                     |
| 0174.              | 2                  | 20 & 21                |
| 0175.              | 2                  | 22 & 23                |
| 0176.              | 2                  | 24 & 25                |
| 0177.              | 2                  | 26-28                  |
| 0178.              | 2                  | 29 & 30                |
| 0179.              | 2                  | 31 & 32                |
| 0180.              | 2                  | 33                     |

|                                                                                                                                 |
|---------------------------------------------------------------------------------------------------------------------------------|
| <p style="text-align: center;"><b>HARRISON COUNTY AGRICULTURAL<br/>HISTORIC RESOURCE SURVEY/PHASE II<br/>PHOTOGRAPH LOG</b></p> |
|---------------------------------------------------------------------------------------------------------------------------------|

| <u>SITE NUMBER</u> | <u>ROLL NUMBER</u> | <u>NEGATIVE NUMBER</u> |
|--------------------|--------------------|------------------------|
| 0181.              | 2                  | 34 & 35                |
| 0182.              | 3                  | 1                      |
| 0183.              | 3                  | 2 & 4                  |
| 0184.              | 3                  | 3                      |
| 0185.              | 3                  | 5 & 6                  |
| 0186.              | 3                  | 7 & 8                  |
| 0187.              | 3                  | 9, 10 & 13             |
| 0188.              | 3                  | 11 & 14                |
| 0189.              | 3                  | 15-17                  |
| 0190.              | 3                  | 18 & 19                |
| 0191.              | 3                  | 20 & 21                |
| 0192.              | 3                  | 22                     |
| 0193.              | 3                  | 23-25                  |
| 0194.              | 3                  | 26                     |
| 0195.              | 3                  | 27 & 28                |

|                                                                                                                                 |
|---------------------------------------------------------------------------------------------------------------------------------|
| <p style="text-align: center;"><b>HARRISON COUNTY AGRICULTURAL<br/>HISTORIC RESOURCE SURVEY/PHASE II<br/>PHOTOGRAPH LOG</b></p> |
|---------------------------------------------------------------------------------------------------------------------------------|

| <u>SITE NUMBER</u> | <u>ROLL NUMBER</u> | <u>NEGATIVE NUMBER</u> |
|--------------------|--------------------|------------------------|
| 0196.              | 3                  | 29                     |
| 0197.              | 3                  | 30                     |
| 0198.              | 3                  | 31                     |
| 0199.              | 4                  | 1 & 2                  |
| 0200.              | 4                  | 3 & 4                  |
| 0201.              | 4                  | 5                      |
| 0202.              | 4                  | 6-10                   |
| 0203.              | 4                  | 11                     |
| 0204.              | 4                  | 12                     |
| 0205.              | 4                  | 13                     |
| 0206.              | 4                  | 14-18                  |
| 0207.              | 4                  | 19 & 20                |
| 0208.              | 4                  | 21 & 22                |
| 0209.              | 4                  | 23 & 24                |
| 0210.              | 4                  | 25-29                  |

|                                                                                                                    |
|--------------------------------------------------------------------------------------------------------------------|
| <p align="center"><b>HARRISON COUNTY AGRICULTURAL<br/>HISTORIC RESOURCE SURVEY/PHASE II<br/>PHOTOGRAPH LOG</b></p> |
|--------------------------------------------------------------------------------------------------------------------|

| <u>SITE NUMBER</u> | <u>ROLL NUMBER</u> | <u>NEGATIVE NUMBER</u> |
|--------------------|--------------------|------------------------|
| 0211.              | 4                  | 30                     |
| 0212.              | 4                  | 31 & 32                |
| 0213.              | 5                  | 1-5                    |
| 0214.              | 5                  | 6-8                    |
| 0215.              | 9                  | 1-7                    |
| 0216.              | 5                  | 9 & 10                 |
| 0217.              | 5                  | 11-13                  |
| 0218.              | 5                  | 14                     |
| 0219.              | 5                  | 15-22                  |
| 0220.              | 5                  | 23-25                  |
| 0221.              | 5                  | 26 & 27                |
| 0222.              | 5                  | 28                     |
| 0223.              | 5                  | 29-32                  |
| 0224.              | 5                  | 33 & 34                |
| 0225.              | 5                  | 35-36A                 |

|                                                                                                                                 |
|---------------------------------------------------------------------------------------------------------------------------------|
| <p style="text-align: center;"><b>HARRISON COUNTY AGRICULTURAL<br/>HISTORIC RESOURCE SURVEY/PHASE II<br/>PHOTOGRAPH LOG</b></p> |
|---------------------------------------------------------------------------------------------------------------------------------|

| <u>SITE NUMBER</u> | <u>ROLL NUMBER</u> | <u>NEGATIVE NUMBER</u> |
|--------------------|--------------------|------------------------|
| 0226.              | 6                  | 1 & 2                  |
| 0227.              | 6                  | 3-5                    |
| 0228.              | 6                  | 6 & 7                  |
| 0229.              | 6                  | 8                      |
| 0230.              | 6                  | 9                      |
| 0231.              | 6                  | 10 & 11                |
| 0232.              | 6                  | 12-14                  |
| 0233.              | 6                  | 15                     |
| 0234.              | 6                  | 16                     |
| 0235.              | 6                  | 17-19                  |
| 0236.              | 6                  | 20 & 21                |
| 0237.              | 6                  | 22 & 23                |
| 0238.              | 6                  | 24-26                  |
| 0239.              | 6                  | 27                     |
| 0240.              | 6                  | 28 & 29                |

|                                                                                                                                 |
|---------------------------------------------------------------------------------------------------------------------------------|
| <p style="text-align: center;"><b>HARRISON COUNTY AGRICULTURAL<br/>HISTORIC RESOURCE SURVEY/PHASE II<br/>PHOTOGRAPH LOG</b></p> |
|---------------------------------------------------------------------------------------------------------------------------------|

| <u>SITE NUMBER</u> | <u>ROLL NUMBER</u> | <u>NEGATIVE NUMBER</u> |
|--------------------|--------------------|------------------------|
| 0241.              | 6                  | 30                     |
| 0242.              | 6                  | 31 & 32                |
| 0243.              | 6                  | 33                     |
| 0244.              | 7                  | 1                      |
| 0245.              | 7                  | 2 & 3                  |
| 0246.              | 7                  | 4-6                    |
| 0247.              | 7                  | 7                      |
| 0248.              | 7                  | 8 & 9                  |
| 0249.              | 7                  | 10                     |
| 0250.              | 7                  | 11                     |
| 0251.              | 7                  | 12                     |
| 0252.              | 7                  | 13                     |
| 0253.              | 7                  | 14 & 15                |
| 0254.              | 7                  | 16                     |
| 0255.              | 7                  | 17                     |

|                                                                                                                                 |
|---------------------------------------------------------------------------------------------------------------------------------|
| <p style="text-align: center;"><b>HARRISON COUNTY AGRICULTURAL<br/>HISTORIC RESOURCE SURVEY/PHASE II<br/>PHOTOGRAPH LOG</b></p> |
|---------------------------------------------------------------------------------------------------------------------------------|

| <u>SITE NUMBER</u> | <u>ROLL NUMBER</u> | <u>NEGATIVE NUMBER</u> |
|--------------------|--------------------|------------------------|
| 0256.              | 7                  | 18                     |
| 0257.              | 7                  | 19 & 20                |
| 0258.              | 7                  | 21                     |
| 0259.              | 7                  | 22                     |
| 0260.              | 7                  | 23 & 24                |
| 0261.              | 7                  | 25-28                  |
| 0262.              | 7                  | 29-31                  |
| 0263.              | 7                  | 32 & 33                |
| 0264.              | 7                  | 34-36A                 |
| 0265.              | 8                  | 1-3                    |
| 0266.              | 8                  | 4-7                    |
| 0267.              | 8                  | 8                      |
| 0268.              | 8                  | 9-11                   |
| 0269.              | 8                  | 12 & 13                |
| 0270.              | 8                  | 14 & 15                |

|                                                                                                                                 |
|---------------------------------------------------------------------------------------------------------------------------------|
| <p style="text-align: center;"><b>HARRISON COUNTY AGRICULTURAL<br/>HISTORIC RESOURCE SURVEY/PHASE II<br/>UTM REFERENCES</b></p> |
|---------------------------------------------------------------------------------------------------------------------------------|

| SITE # | QUADRANGLE       | ZONE | EASTING | NORTHING |
|--------|------------------|------|---------|----------|
| 0151.  | Wolf Summit, WVA | 17   | 544426  | 4349784  |
| 0152.  | Wolf Summit, WVA | 17   | 545303  | 4349073  |
| 0153.  | Wolf Summit, WVA | 17   | 544992  | 4350619  |
| 0154.  | Wolf Summit, WVA | 17   | 545618  | 4352430  |
| 0155.  | Wolf Summit, WVA | 17   | 544892  | 4353330  |
| 0156.  | Wolf Summit, WVA | 17   | 543753  | 4354549  |
| 0157.  | Wolf Summit, WVA | 17   | 543132  | 4353906  |
| 0158.  | Salem, WVA       | 17   | 542523  | 4353903  |
| 0159.  | Salem, WVA       | 17   | 541509  | 4353661  |
| 0160.  | Salem, WVA       | 17   | 540958  | 4353984  |
| 0161.  | Salem, WVA       | 17   | 540090  | 4353750  |
| 0162.  | Salem, WVA       | 17   | 540250  | 4354627  |
| 0163.  | Salem, WVA       | 17   | 540227  | 4355395  |
| 0164.  | Salem, WVA       | 17   | 541862  | 4354910  |
| 0165.  | Wolf Summit, WVA | 17   | 547882  | 4354003  |

|                                                                                                                    |
|--------------------------------------------------------------------------------------------------------------------|
| <p align="center"><b>HARRISON COUNTY AGRICULTURAL<br/>HISTORIC RESOURCE SURVEY/PHASE II<br/>UTM REFERENCES</b></p> |
|--------------------------------------------------------------------------------------------------------------------|

| SITE # | QUADRANGLE       | ZONE | EASTING | NORTHING |
|--------|------------------|------|---------|----------|
| 0166.  | Wolf Summit, WVA | 17   | 547418  | 4353238  |
| 0167.  | Wolf Summit, WVA | 17   | 545969  | 4354118  |
| 0168.  | Salem, WVA       | 17   | 541765  | 4350397  |
| 0169.  | Wolf Summit, WVA | 17   | 543339  | 4350590  |
| 0170.  | Wolf Summit, WVA | 17   | 543489  | 4350916  |
| 0171.  | Wolf Summit, WVA | 17   | 543361  | 4351950  |
| 0172.  | Salem, WVA       | 17   | 539633  | 4352720  |
| 0173.  | Salem, WVA       | 17   | 539424  | 4351867  |
| 0174.  | Salem, WVA       | 17   | 539733  | 4351883  |
| 0175.  | Salem, WVA       | 17   | 540129  | 4350474  |
| 0176.  | Salem, WVA       | 17   | 540374  | 4350269  |
| 0177.  | Salem, WVA       | 17   | 538410  | 4350899  |
| 0178.  | Salem, WVA       | 17   | 538138  | 4351089  |
| 0179.  | Salem, WVA       | 17   | 537259  | 4351449  |
| 0180.  | Salem, WVA       | 17   | 540484  | 4349527  |
| 0181.  | Salem, WVA       | 17   | 540590  | 4348954  |
| 0182.  | Salem, WVA       | 17   | 539026  | 4347266  |
| 0183.  | Salem, WVA       | 17   | 540681  | 4345719  |
| 0184.  | Salem, WVA       | 17   | 540852  | 4345819  |
| 0185.  | Salem, WVA       | 17   | 541442  | 4348548  |

|                                                                                                                    |
|--------------------------------------------------------------------------------------------------------------------|
| <p align="center"><b>HARRISON COUNTY AGRICULTURAL<br/>HISTORIC RESOURCE SURVEY/PHASE II<br/>UTM REFERENCES</b></p> |
|--------------------------------------------------------------------------------------------------------------------|

| SITE # | QUADRANGLE        | ZONE | EASTING | NORTHING |
|--------|-------------------|------|---------|----------|
| 0186.  | Salem, WVA        | 17   | 541340  | 4348521  |
| 0187.  | Salem, WVA        | 17   | 540943  | 4348470  |
| 0188.  | Salem, WVA        | 17   | 541012  | 4348363  |
| 0189.  | Salem, WVA        | 17   | 541029  | 4348027  |
| 0190.  | Wolf Summit, WVA  | 17   | 544159  | 4347347  |
| 0191.  | Wolf Summit, WVA  | 17   | 544018  | 4347265  |
| 0192.  | Wolf Summit, WVA  | 17   | 544417  | 4346226  |
| 0193.  | Wolf Summit, WVA  | 17   | 545545  | 4346282  |
| 0194.  | Wolf Summit, WVA  | 17   | 545467  | 4345983  |
| 0195.  | Wolf Summit, WVA  | 17   | 544079  | 4345462  |
| 0196.  | Wolf Summit, WVA  | 17   | 543917  | 4345143  |
| 0197.  | Salem, WVA        | 17   | 542664  | 4345159  |
| 0198.  | Wolf Summit, WVA  | 17   | 543488  | 4346167  |
| 0199.  | Wolf Summit, WVA  | 17   | 544102  | 4344876  |
| 0200.  | West Milford, WVA | 17   | 545711  | 4340393  |
| 0201.  | West Milford, WVA | 17   | 546470  | 4340375  |
| 0202.  | West Milford, WVA | 17   | 546904  | 4340431  |
| 0203.  | West Milford, WVA | 17   | 547487  | 4340369  |
| 0204.  | West Milford, WVA | 17   | 550544  | 4338998  |
| 0205.  | West Milford, WVA | 17   | 547619  | 4336844  |

|                                                                                                                    |
|--------------------------------------------------------------------------------------------------------------------|
| <p align="center"><b>HARRISON COUNTY AGRICULTURAL<br/>HISTORIC RESOURCE SURVEY/PHASE II<br/>UTM REFERENCES</b></p> |
|--------------------------------------------------------------------------------------------------------------------|

| SITE # | QUADRANGLE        | ZONE | EASTING | NORTHING |
|--------|-------------------|------|---------|----------|
| 0206.  | West Milford, WVA | 17   | 547554  | 4336901  |
| 0207.  | West Milford, WVA | 17   | 546553  | 4337163  |
| 0208.  | West Milford, WVA | 17   | 545136  | 4337668  |
| 0209.  | West Milford, WVA | 17   | 544199  | 4337705  |
| 0210.  | West Milford, WVA | 17   | 543800  | 4337450  |
| 0211.  | Big Isaac, WVA    | 17   | 542806  | 4338935  |
| 0212.  | Big Isaac, WVA    | 17   | 542558  | 4339117  |
| 0213.  | West Milford, WVA | 17   | 546736  | 4334677  |
| 0214.  | West Milford, WVA | 17   | 546385  | 4335265  |
| 0215.  | West Milford, WVA | 17   | 546228  | 4334762  |
| 0216.  | West Milford, WVA | 17   | 545704  | 4335108  |
| 0217.  | West Milford, WVA | 17   | 545070  | 4335284  |
| 0218.  | West Milford, WVA | 17   | 544979  | 4335847  |
| 0219.  | West Milford, WVA | 17   | 544675  | 4336317  |
| 0220.  | West Milford, WVA | 17   | 544837  | 4336686  |
| 0221.  | West Milford, WVA | 17   | 544326  | 4335464  |
| 0222.  | Big Isaac, WVA    | 17   | 541512  | 4335875  |
| 0223.  | Big Isaac, WVA    | 17   | 541282  | 4335192  |
| 0224.  | Big Isaac, WVA    | 17   | 541087  | 4335306  |
| 0225.  | Big Isaac, WVA    | 17   | 540564  | 4335518  |

|                                                                                                                    |
|--------------------------------------------------------------------------------------------------------------------|
| <p align="center"><b>HARRISON COUNTY AGRICULTURAL<br/>HISTORIC RESOURCE SURVEY/PHASE II<br/>UTM REFERENCES</b></p> |
|--------------------------------------------------------------------------------------------------------------------|

| SITE # | QUADRANGLE        | ZONE | EASTING | NORTHING |
|--------|-------------------|------|---------|----------|
| 0226.  | Big Isaac, WVA    | 17   | 540365  | 4335682  |
| 0227.  | Big Isaac, WVA    | 17   | 539704  | 4337042  |
| 0228.  | West Milford, WVA | 17   | 547203  | 4334964  |
| 0229.  | Mount Clare, WVA  | 17   | 555805  | 4334808  |
| 0230.  | Mount Clare, WVA  | 17   | 555234  | 4335318  |
| 0231.  | Mount Clare, WVA  | 17   | 555134  | 4335405  |
| 0232.  | Mount Clare, WVA  | 17   | 554663  | 4335146  |
| 0233.  | Mount Clare, WVA  | 17   | 554318  | 4333319  |
| 0234.  | Mount Clare, WVA  | 17   | 554027  | 4333042  |
| 0235.  | Mount Clare, WVA  | 17   | 554482  | 4334449  |
| 0236.  | Mount Clare, WVA  | 17   | 554285  | 4335832  |
| 0237.  | West Milford, WVA | 17   | 553321  | 4337468  |
| 0238.  | West Milford, WVA | 17   | 552545  | 4337214  |
| 0239.  | West Milford, WVA | 17   | 552094  | 4337962  |
| 0240.  | West Milford, WVA | 17   | 550992  | 4339353  |
| 0241.  | West Milford, WVA | 17   | 550908  | 4339280  |

|                                                                                                                    |
|--------------------------------------------------------------------------------------------------------------------|
| <p align="center"><b>HARRISON COUNTY AGRICULTURAL<br/>HISTORIC RESOURCE SURVEY/PHASE II<br/>UTM REFERENCES</b></p> |
|--------------------------------------------------------------------------------------------------------------------|

| SITE # | QUADRANGLE                          | ZONE | EASTING | NORTHING |
|--------|-------------------------------------|------|---------|----------|
| 0242.  | West Milford, WVA                   | 17   | 550542  | 4338684  |
| 0243.  | West Milford, WVA                   | 17   | 547772  | 4335500  |
| 0244.  | West Milford, WVA                   | 17   | 549317  | 4332743  |
| 0245.  | West Milford, WVA                   | 17   | 549207  | 4333256  |
| 0246.  | West Milford, WVA                   | 17   | 547907  | 4333991  |
| 0247.  | West Milford, WVA                   | 17   | 547638  | 4334338  |
| 0248.  | West Milford, WVA                   | 17   | 545771  | 4332908  |
| 0249.  | West Milford, WVA                   | 17   | 545137  | 4333019  |
| 0250.  | West Milford, WVA                   | 17   | 544604  | 4333008  |
| 0251.  | West Milford, WVA<br>(LEWIS COUNTY) | 17   | 543844  | 4332712  |
| 0252.  | Big Isaac, WVA                      | 17   | 542879  | 4333269  |
| 0253.  | Big Isaac, WVA                      | 17   | 542391  | 4333286  |
| 0254.  | Big Isaac, WVA                      | 17   | 542167  | 4333044  |
| 0255.  | Big Isaac, WVA                      | 17   | 541589  | 4332895  |
| 0256.  | Big Isaac, WVA                      | 17   | 540857  | 4333053  |
| 0257.  | Big Isaac, WVA                      | 17   | 539590  | 4333319  |
| 0258.  | Big Isaac, WVA                      | 17   | 538577  | 4334950  |
| 0259.  | Big Isaac, WVA                      | 17   | 538203  | 4335059  |
| 0260.  | Big Isaac, WVA                      | 17   | 538368  | 4336500  |

|                                                                                                                    |
|--------------------------------------------------------------------------------------------------------------------|
| <p align="center"><b>HARRISON COUNTY AGRICULTURAL<br/>HISTORIC RESOURCE SURVEY/PHASE II<br/>UTM REFERENCES</b></p> |
|--------------------------------------------------------------------------------------------------------------------|

| SITE # | QUADRANGLE        | ZONE | EASTING | NORTHING |
|--------|-------------------|------|---------|----------|
| 0261.  | West Milford, WVA | 17   | 546937  | 4332371  |
| 0262.  | Big Isaac, WVA    | 17   | 538262  | 4334427  |
| 0263.  | Big Isaac, WVA    | 17   | 538017  | 4334733  |
| 0264.  | Big Isaac, WVA    | 17   | 537965  | 4334445  |
| 0265.  | Big Isaac, WVA    | 17   | 537132  | 4334947  |
| 0266.  | West Milford, WVA | 17   | 548292  | 4333250  |
| 0267.  | West Milford, WVA | 17   | 549420  | 4332069  |
| 0268.  | West Milford, WVA | 17   | 550246  | 4331653  |
| 0269.  | West Milford, WVA | 17   | 550596  | 4332468  |
| 0270.  | West Milford, WVA | 17   | 551480  | 4332604  |

## SURVEY ANALYSIS AND RECOMMENDATIONS

The initial intent of the project was to determine the extent of agricultural historic resources in the survey area, identify the significant resources and prepare recommendations for additional activities. The potential for National Register eligibility for individual sites or historic districts was also to be investigated. In analyzing the results of the survey, the Criteria of Significance of the National Register of Historic Places was used.

The resources studied under this survey are generally residential in nature and primarily on farms. The resources also include many secondary agricultural buildings such as barns, corn cribs, chicken coops, etc. The resources ranged from the mid nineteenth century to the mid twentieth century. It was anticipated that there would be some modifications and some modern intrusions. It was anticipated that the resources found would relate to agriculture and the settlement and development of the county.

Modifications were found in number and these included the application of non-original sidings, modern windows installed, non-original porch components, porches enclosed and additions added. There were some modern intrusions but these were mainly closer to towns and not in the rural areas. There were also several vacant properties. Many of the resources identified and recorded were traditionally farms but the primary structures are vacant or the land is no longer used for self-sufficient farming. Many of the farms lease their land to family or neighbors for hay production and/or livestock pasture.

No historic districts are recommended for this survey area. Once the entire county has been surveyed, the consultant recommends that the county be investigated for a multiple property submission under the umbrella of "Agricultural Resources of Harrison County." Themes may include 100 year old farms; 200 year old farms; cattle production; secondary building types; architectural styles; dairy farming; and the relationship of the above to the county's turnpikes and railroads.

There are several individual resources that warrant further investigation and they may be individually eligible to the National Register of Historic Places. These include:

- The Randolph House & Farm, site #0171, ca. 1905. Significant for its association with the development of Harrison County through agriculture and significant for its association with the Folk Victorian style of architecture.
- The McWilliams/Shaffer/Haymond House & Farm, site #0173, 1905. Significant for its association with the development of Harrison County through agriculture. Significant also for its association with the pioneer family, the Haymonds. Also significant for its association with the Italianate style of architecture.

- The England/Stonestreet House & Farm, site #0190, 1918. Significant for its association with the development of Clarksburg and Harrison County through its association with local merchant, Stonestreet; and significant for its association with the Prairie style of architecture, unusual in West Virginia and particularly in such a rural location.
- The Riley House & Farm, site #0202, ca. 1880. Significant for its association with the Italianate style of architecture.
- The McDonald Farm, site #0217, ca. 1885. Significant for its association with the development of Harrison County through agriculture and for its association with the McDonald family, early settlers in the county.
- The Stutler/Richards/Sheets House & Farm, site #0238, ca. 1902. Significant for its association with the development of Harrison County through agriculture; for its association with the Richards and Sheets families; and for its association with the Queen Anne style of architecture.
- The Layman/Hughes House & Farm, site #0244, ca. 1910. Significant for its association with the development of Harrison County through agriculture; for its association with the Hughes family; and for its association with the Queen Anne style of architecture.
- The Ferrell/Gusman House & Farm, site #0245, ca. 1890. Significant for its association with the development of Harrison County through agriculture; for its association with the Gusman family; and for its association with the Folk Victorian style of architecture.
- The Doak House, site #0261, ca. 1900. Significant for its association with the development of Harrison County through agriculture and for its association with the Folk Victorian style of architecture.

The remaining resources do not contain enough architectural or historical integrity to warrant recommending listing in the National Register of Historic Places with the current available information. However, the following list of resources should be further investigated to verify this and to determine their potential for local significance in Harrison County. These sites, while not eligible under existing National Register criteria, are, in the opinion of the consultant team, significant to the historic and architectural heritage of Harrison County.

- The Wilcox/Fletcher House & Farm, site #0153, ca. 1890. Significant for its association with the settlement and development of Harrison County through its association with agriculture. The nearby Fletcher Covered Bridge, which is individually listed on the National Register of Historic Places, is named for this same family, early settlers in the area.

- The Fahey/Carter House & Farm, site #0156, ca. 1889. Significant for its association with the settlement and development of Harrison County through its association with agriculture.
- The Summers/Pinkham/Williams House & Farm, site #0157, ca. 1910. Significant for its association with the development of Harrison County through its association with agriculture and for its association with the Queen Anne style of architecture.
- The Hitt House & Farm, site #0158, ca. 1890. Significant for its association with the development of Harrison County through its association with agriculture and for its association with the Italianate style of architecture.
- The Butler House & Farm, site #0160, ca. 1910. Significant for its association with the development of Harrison County through its association with agriculture and for its association with the Four Square style of architecture.
- The Marsh/Goodwin House & Farm, site #0162, ca. 1910. Significant for its association with the settlement and development of Harrison County through its association with agriculture and through its association with the Goodwin family.
- The Cummings/Day House, site #0164, ca. 1890. Significant for its association with the development of Harrison County through its association with the Day family.
- The Jablon/Lanham Log House, site #0167, ca. 1875. Significant for its association with the settlement and development of Harrison County through its association with agriculture and for its association with the Midland Log style of architecture.
- Ebony Glen Farm/Reaser/Shahan House & Farm, site #0170, ca. 1890/ca. 1910. Significant for its association with the settlement and development of Harrison County through its association with agriculture and for its association with the settlement family, the Shahans.
- The Dennison House, site #0180, ca. 1915. Significant for its association with the Four Square style of architecture.
- The Haught House & Farm/New Dale Farm, site #0181, ca. 1916. Significant for its association with the settlement and development of Harrison County through its association with agriculture and for its association with the Folk Victorian style of architecture.
- The Barker/Edgar Matthey House & Farm, site #0186, ca. 1863. Significant for its association with the settlement and development of Harrison County through its

association with agriculture and through its association with the settlement family, Mattheys.

- The Ross/Golden/Johnson House & Farm, site #0188, ca. 1920. Significant for its association with the development of Harrison County through its association with agriculture and for its association with the Johnson family and for its association with the Queen Anne style of architecture.
- The Pedrick/Headley House & Farm, site #0189, ca. 1920. Significant for its association with the development of Harrison County through its association with agriculture and for its association with the Queen Anne style of architecture.
- The Myers House, site #0191, ca. 1910. Significant for its association with the development of Harrison County through its association with agriculture and for its association with the Italianate style of architecture.
- The Williams House & Farm, site #0193, ca. 1915. Significant for its association with the development of Harrison County through its association with agriculture and the Williams family and for its association with the Queen Anne style of architecture.
- The Laurel Run School, site #0195, ca. 1900. Significant for its association with the development of Harrison County through its association with the educational system.
- The Rapking/Post House & Farm, site #0206, 1892. Significant for its association with the settlement and development of Harrison County through its association with agriculture and the settlement family, the Posts and for its association with the Folk Victorian style of architecture.
- The McDougal/Law House & Farm, site #0213, ca. 1840. Significant for its association with the settlement and development of Harrison County through its association with agriculture and through its association with the settlement family, the Laws.
- The Allman/James Law House & Farm, site #0215, ca. 1890/ca. 1945. Significant for its association with the settlement and development of Harrison County through its association with agriculture and through its association with the settlement family, the Laws.
- The Gabriel/McDonald House & Farm, site #0219, ca. 1920. Significant for its association with the settlement and development of Harrison County through its association with agriculture and through its association with the settlement family, the McDonalds.

- The Gump/Ashcraft/Cole House & Farm, site #0221, ca. 1892. Significant for its association with the settlement and development of Harrison County through its association with agriculture and the Cole family.
- The Marshall G. Law House & Farm, site #0228, ca. 1930. Significant for its association with the settlement and development of Harrison County through its association with agriculture and through its association with the settlement family, the Laws.
- The Dawson/Kennedy House & Farm, site #0230, ca. 1850. Significant for its association with the settlement and development of Harrison County through its association with agriculture and the settlement family, the Kennedy's. Also significant for its association with the Folk Victorian style of architecture.
- The Davisson House & Farm, site #0233, ca. 1870. Significant for its association with the settlement and development of Harrison County through its association with agriculture and the settlement family, the Davissons.
- The Richards/Davisson House & Farm, site #0234, ca. 1913. Significant for its association with the settlement and development of Harrison County through its association with agriculture and the settlement family, the Davissons.
- The Post House, site #0236, ca. 1890. Significant for its association with the settlement and development of Harrison County through its association with agriculture and through its association with the settlement family, the Posts.
- The Jane Lew Tile & Block Company House, site #0243, ca. 1945. Significant for its association with the and development of Harrison County through its association with commerce and trade.
- Maplewood, site #0247, ca. 1840. Significant for its association with the settlement and development of Harrison County and for its association with the Greek Revival style of architecture.
- The Dallas House & Farm, site #0252, ca. 1890. Significant for its association with the settlement and development of Harrison County through its association with agriculture.
- The Coffindaffer House, site #0256, ca. 1890. Significant for its association with the settlement and development of Harrison County through its association with agriculture and for its association with the Folk Victorian style of architecture.
- The Titus/Harvey Morris House & Farm, site #0258, ca. 1880. Significant for its association with the settlement and development of Harrison County through its association with agriculture and for its association with the settlement family, the Morris'.

- The Morris House & Farm, site #0259, ca. 1870. Significant for its association with the settlement and development of Harrison County through its association with agriculture and for its association with the settlement family, the Morris'.
- The Lewis/Coffindaffer House & Farm, site #0263, ca. 1886. Significant for its association with the settlement and development of Harrison County through its association with agriculture and for its association with the Coffindaffer family.
- Riverbend Dairy Farm/Nay House & Farm, site #0266, ca. 1950. Significant for its association with the development of Harrison County through its association with dairy farming.

As seen by the list above, there are many significant resources associated with the settlement, growth and development of Harrison County and associated with the architectural styles of the mid nineteenth to mid twentieth centuries.

## **GENERAL RECOMMENDATIONS**

It is recommended in light of what was recorded in Phase I and Phase II survey projects that the Harrison County HLC continues their efforts to survey the county. It would benefit them to narrow their focus, pick a specific geographic section of the county, perhaps by district, and conduct an intensive Historic Resource Survey of that area. The consultant team believes that there are numerous other significant resources that remain unrecorded. Particular geographic areas that have not yet been surveyed include the Shinnston area, Bridgeport area and the Lumberport area.

It is also recommended that the Harrison County HLC survey some of the smaller communities within the county with the idea of establishing historic districts. The consultant team believes that potential districts exist in West Milford and other areas of the county.

As the survey area is primarily rural, design review and zoning, etc. is not applicable. In order to identify, document and protect significant resources it is recommended that the HLC establish a County Register.

A County Register works on a local level as the National Register works on a national level. It is simply a development tool and should not be viewed as a hindrance or detriment to personal property rights. It serves to identify and protect significant local resources.

The Harrison County Historic Landmarks Commission has identified 100 and 200 year old farms within the county previous to the Phase I and II Historic Resource Surveys and are using this information for planning in relation to heritage tourism and other aspects of county-wide planning. They have also incorporated the surveys done to date in their planning activities.

It is recommended that Harrison County participate in the West Virginia Farmland Protection Act authorized under the West Virginia Department of Agriculture. The website for information is: **wvfarmlandprotection.org**. It is also recommended that the HLC investigate possible inclusion in land trusts. The website for this information is: **wvlandtrust.org**. Both of these organizations work with private land owners to help them protect their farm or summer/home place forever.

The HLC should be commended for all that they have done to date. The consultant team would particularly like to acknowledge and thank Ms. Becky Nesbitt and Mr. Jeff Wyne for the extensive research they did on individual properties in Phase I and Phase II of the Agricultural Survey of Harrison County. Their research was invaluable to both of these projects and the agricultural history of Harrison County.

## BIBLIOGRAPHY

- Comstock, Jim. West Virginia Heritage Encyclopedia. Jim Comstock, Richwood, WV. 1976.
- Davis, Dorothy. History of Harrison County. McClain Printing Co., Parson, WV. 1970.
- Harrison County Courthouse Records and Deeds.
- Harrison County A Bicentennial Album 1784-1984. Walsworth Press, Inc., Marceline, MO. 1985.
- Harrison County 1784 Heritage 1995. Walsworth Publishing Co., PO Box 773, Summersville, WV 26651. 1995.
- Haymond, Henry. History of Harrison County. Acme Publishing Co., Morgantown, WV. 1910.
- Law 1992. Law Family History. Unpublished manuscript.
- McDougal, Lulu Belle Law. Personal correspondence with the consultant team.
- Morris, James V. Material of Historic and Scenic Interest in Harrison County, West Virginia. Unpublished manuscript. Morgantown, WV. 1946.
- Rapking, Jean Post. Good Hope History. Book Masters, 2541 Ashland Road, Mansfield, OH 44905. 2002.
- R.L. Polk and Co.'s Clarksburg Directory 1915 Volume VI. R.L. Polk & Co. Publishers, Pittsburgh, PA. 1915.
- Stealey, Robert F. Images of America Harrison County. Arcadia Publishing, 2 Cumberland Street, Charleston, SC 29401. 2000.

## BIBLIOGRAPHY

### Oral interviews:

Betty Wilcox on 03/10/04.  
Bill Fahey on 03/10/04.  
Emily Summers, Jr. on 03/10/04.  
Mrs. Harry Lynch on 03/10/04.  
Martha Davis on 03/10/04.  
Mr. Todd on 03/10/04.  
Linda Wikert on 03/10/04.  
Floyd George on 03/11/04.  
Tom Reaser on 03/11/04.  
Warner Matthey on 03/11/04.  
  
SueEllen Hill on 03/11/04.  
Greg McWilliams on 03/11/04.  
James Cole on 03/23/04.  
Bob Williams on 03/23/04.  
Marie Pedrick on 03/23/04.  
Delphia Marple on 03/23/04.  
Perry Post on 04/06/04.  
Mrs. Ed Rapping on 04/06/04.  
Jean Post Rapping on 04/06/04.  
Mr. & Mrs. Tom Butcher on 04/06/04.  
Ella Gaines on 04/06/04.  
Peggy Hurst on 04/06/04.  
Leland Freeman on 04/29/04.

James McDougal on 04/20/04.  
Wanda Law on 04/20/04.  
Lulu Belle Law McDougal on 04/20/04.  
Evelyn McDonald on 04/20/04.  
Cathy Exline on 04/20/04.  
David Gabriel & Son on 04/20/04.  
LeeAnn Gump on 04/20/04.  
Willis Cumberledge on 04/20/04.  
Mrs. George Dawson, Sr. on 04/21/04.  
Mr. & Mrs. George Dawson, Jr. on 04/21/04.  
Gary & Mary Jones on 04/21/04.  
Mary Richards on 04/21/04.  
Mrs. Dallas Bailey on 04/21/04.  
Jim Stutler on 04/21/04.  
Charles & Edna Bartlett on 04/21/04.  
Mrs. Harry Bunch on 04/21/04.  
Janice Tyler on 04/21/04.  
Kathy Beever on 04/28/04.  
Mrs. Francis Lough on 04/28/04.  
Nancy McCay on 04/29/04.  
Ray Moser on 04/29/04.  
Mrs. Paul Nay on 04/29/04.  
David & Joellen Allman on 05/14/04.


### Telephone interviews:

Matt Evans on 03/16/04.  
Ruth Bowen on 03/24/04.

## APPENDIX I


43°54' 20"  
43°53'  
43°52'  
43°51'  
43°50'  
17°30"

4862 / SE (SALEM)  
VA 233 3 4 MI




WOLF SUMMIT QUAD  
SITES #0151-0157





Copyright (C) 1997, Maptech, Inc.

WOLF SUMMIT QUAD SITES #0165-0167



SALEM QUAD SITE #0168


WOLF SUMMIT  
QUAD  
SITES #0169 -  
0171

4352

4862 / SE.  
(SALEM)

4351


4350






Copyright (C) 1997, Maptech, Inc.

SALEM QUAD SITES #0172-0181



Copyright (C) 1997, Maptech, Inc.

SALEM QUAD  
SITES #0182-0189



IBIG (SAAC)  
1962 II NE

Mapped, edited, and published by the Geological Survey

Control by USGS and USC&GS

Copyright (C) 1997, Maptech, Inc.

WOLF SUMMIT QUAD  
SITES #0190-0196



4345000mN

OR—GEOLOGICAL SURVEY, RESTON, VIRGINIA—1977

542

543000mE

80°30'

39°15'

### ROAD CLASSIFICATION



Light-duty



Unimproved dirt



U. S. Route



State Route

SALEM  
QUAD


SITE #0197

SALEM, W. VA.

SE/4 CENTER POINT '15' QUADRANGLE

WEST MIL  
4962 III NW

280 000  
FEET



39°15'

80°30'

544

1 720 000 FEET


Mapped, edited, and published by the Geologic  
Control by USGS and USC&GS

Topography by photogrammetric methods from aerial

Copyright (C) 1997, Maptech, Inc.

WOLF SUMMIT QUAD  
SITE #0198

280 000  
FEET



4345

39°15'

80°30'

544

1 720 000 FEET

545

Mapped, edited, and published by the Geological Survey

Control by USGS and USC&GS

Topography by photogrammetric methods from aerial  
photographs taken 1957. Field checked 1960

Polyconic projection. 1927 North American datum  
10,000-foot grid based on West Virginia coordinate system,  
north zone

1000-meter Universal Transverse Mercator grid ticks,  
zone 17, shown in blue

Fine red dashed lines indicate selected fence and field lines which  
generally visible on aerial photographs. This information is uncharted


Unlabeled wells are gas wells

Copyright (C) 1997, Maptech, Inc.

WOLF SUMMIT QUAD  
SITE #0199

(BIG ISAAC)  
4862 II NE






BIG ISAAC QUAD  
SITES #0211  
#0212


4339

4338




Copyright (C) 1997, Maptech, Inc.

W. MILFORD QUAD SITES #0213-0221



Copyright (C) 1997, Maptech, Inc.


BIG ISAAC QUAD SITES #0222-0227




Copyright (C) 1997, Maptech, Inc.

W. MILFORD QUAD  
SITE # 0228

WEST  
4336  
10'  
4335  
4334  
4333  
S 1912.8 MI.






Copyright (C) 1997, Maptech, Inc.

WEST MILFORD QUAD SITES #0237-0242




Copyright (C) 1997, Maptech, Inc.

WEST MILFORD QUAD SITE #0243



Copyright (C) 1997, Maptech, Inc.


WEST MILFORD QUAD  
SITES #0244 - 0247




Copyright (C) 1997, Maptech, Inc.


WEST MILFORD QUAD SITES# 0248-0251







BIG ISAAC QUAD SITES # 0262 - 0265



48 (WESTON) 4962 III SW 49 WEST MILFORD QUAD 25' 51 2 170 000 FEET (SOUTH)

SCALE 1:24 000 SITES # 0266 - 0270

1 MILE